

**Kingdom of Saudi Arabia  
General Authority of Civil Aviation**

# **GACA REGULATION**

## **Section 14 Aerodromes**

### **Volume I – Aerodrome Design and Operations**

Edition 3.0

## FOREWORD

The following Regulations governing Aerodromes - Volume I - Aerodrome Design and Operations are based on Articles 2, 3, 4, 5 , and Chapter 3 – Titled Aerodromes and Air Navigation Facilities Articles -33 thru 48 of the Civil Aviation Act that has been approved by the Council of Ministers Resolution No. 185 dated 17/07/1426H and issued by the Royal Decree No. M/44 dated 18/07/1426H. (23/08/2005G), and are in accordance with ICAO Annex 14 Aerodromes - Volume I - Aerodrome Design and Operations, and its related documents.

The promulgation of this regulation is based on the authority granted in Article 179 of the Civil Aviation Act, and is issued under the authority of the President, General Authority of Civil Aviation, as a duly delegated representative of the GACA Board of Directors, in accordance with Order No.T-41, dated 30/12/1429H (28/12/2008G).

The General Authority of Civil Aviation is responsible for the preparation and distribution of all regulations in sufficient quantities so that all service providers and aircraft operators based in the Kingdom of Saudi Arabia are able to obtain an authentic copy prior to the effective date of the Regulation.

### APPROVED:

*Original Signed*

Fahad Bin Abdullah Al Saud  
President, General Authority of Civil Aviation,

Effective Date: 14 November 2013

## CONTENT RULES

### 1) Introduction:

- a) This Section contains regulations that contain the specifications prescribed for the physical characteristics and obstacle limitation surfaces at civil aerodromes as well as certain facilities and technical services normally provided in conjunction with an aerodrome. These specifications are not intended to limit or regulate the operation of aircraft.
- b) To a great extent, the specifications for individual facilities detailed in the General Authority of Civil Aviation Regulation (GACAR) Section 14 - Aerodromes, Volume I – Aerodrome Design and Operation, have been interrelated by a reference code system described in this chapter and by the designation of the runway types that are to be provided, as described in the definitions. This simplifies the reading of Volume I of this Section, but in most cases, results in efficiently proportioned aerodromes when the specifications are followed.
- c) This document sets forth the minimum aerodrome specifications to accommodate aircraft that are currently operating or for aircraft that are known to be planned for future introduction. Accordingly, any more demanding safeguards for as yet unknown or unplanned aircraft have not been considered. Decisions regarding such matters are left to Airport Standards and Safety (AS&S) of the Safety Department (SD) of the Safety and Economic regulation Sector (S&ER) of GACA to consider regarding each individual aerodrome.
- d) Guidance on the possible effects of future aircraft on these specifications is given in the ICAO Aerodrome Design Manual (Doc 9157), Part 2. It should be noted that the specifications for categories II and III precision approach runways are only applicable to runways intended to be used by aircraft included in codes 3 and 4.
- e) GACAR Section 14 - Aerodromes, Volume I –Aerodrome Design and Operation, does not include specifications relating to the overall planning of aerodromes (such as separation between adjacent aerodromes or capacity of individual aerodromes); impact on the environment, or of economic and other non-technical factors that should be considered in the development of an aerodrome. Information on these subjects is included in the ICAO Airport Planning Manual (Doc 9184), Part 1. Guidance material on the environmental aspects of the development and operation of an aerodrome is included in the ICAO Airport Planning Manual, Part 2. Aviation security is an integral part of aerodrome planning and operations. GACAR Section 14, Volume I, contains several specifications aimed at enhancing the level of security at aerodromes. Specifications on other facilities related to security are given in GACA Regulation Section 17 and ICAO Annex 17 and detailed guidance on the subject is contained in the ICAO Security Manual.

## **2) Organization Structure:**

GACA has established Airport Standards and Safety Division (AS&S) within the Safety Department (SD) of the Safety and Economic Regulation Sector (S&ER) to carry out the function of enforcing compliance with the applicable specifications of GACAR Section 14, and to provide safety oversight of aerodromes to include audits, inspections, investigations and data analysis. In order to assure safety and the continued validity of the aerodrome certificate, GACA - SD inspectors are required to perform an onsite aerodrome inspection on an annual basis at a minimum; however, more frequent inspections may be directed by higher authority.

- a) The GACA – SD, AS&S, shall certify aerodromes used for international operations in accordance with the specifications contained in this Section as well as other relevant GACA/ICAO specifications.
- b) The GACA – SD, AS&S should certify aerodromes open to public use in accordance with specifications contained in this Section as well as other relevant GACA/ICAO specifications.
- c) The framework for the certification of aerodromes is given in the GACAR Section – 14 - Volume III - Aerodromes Certification, and ICAO Manual on Certification of Aerodromes. (Doc 9774).
- d) As part of the certification process, The GACA – SD, AS&S shall ensure that an aerodrome developed an Aerodrome Manual (AM) which includes all pertinent information on the aerodrome site, facilities, services, equipment, operating procedures, organization and management including a safety management system. The manual is to be submitted by the aerodrome for approval/acceptance prior to granting the aerodrome certificate. It is the responsibility of the certified aerodrome to keep the aerodrome manual revised and up to date.

## **3) Framework for the State Safety Programme (SSP) for Aerodromes:**

- a) In the kingdom of Saudi Arabia, the responsibility to implement an SSP rests with the GACA/S&ER.
- b) The GACA – SD, Airport Standards and Safety Division (AS&S) shall implement and maintain the SSP for Aerodromes in order to achieve an acceptable level of safety in aerodrome operations.
- c) The GACA – SD, AS&S shall establish the acceptable level(s) of safety to be achieved by utilizing the Guidance on safety program and on defining acceptable levels of safety that is contained in the ICAO Safety Management Manual (SMM) (Doc 9859).
- d) The GACA – SD, AS&S shall require, as part of its safety program, that a certified aerodrome operator implements a Safety Management System (SMS) acceptable to the GACA – SD, AS&S that, as a minimum:
  - 1. identifies safety hazards;

2. ensures that remedial action necessary to maintain an acceptable level of safety is implemented;
  3. provides for continuous monitoring and regular assessment of the safety level achieved; and
  4. aims to make continuous improvement to the overall level of safety.
- e) A Safety Management System shall clearly define lines of safety accountability throughout the staff of a certified aerodrome operator, including direct accountability for safety on the part of senior management.
- f) The intent of a Safety Management System is to have in place an organized and orderly approach in the management of aerodrome safety by the aerodrome operator. Guidance on an aerodrome Safety Management System is given in the GACAR - Section -21 - Safety Management System, and in the ICAO Safety Management Manual (SMM) (Doc 9859).

#### **4) Applicability:**

- a) The interpretation of some of the specifications in GACAR Section 14 expressly requires the exercise of discretion, decision making or the performance of a function by the appropriate authority. In other specifications, the named appropriate authority does not actually appear although its inclusion is implied. In both cases, the responsibility for whatever determination or action is necessary shall rest with the Airport Standards and Safety (AS&S) of the Safety Department (SD) of the Safety and Economic regulation Sector (S&ER) which have regulatory and safety oversight jurisdiction over the aerodromes.
- b) These specifications, unless otherwise noted in a particular context, shall apply to all aerodromes open to public use in accordance with the requirements of ICAO Article 15 of the Convention. The specifications of GACAR Section 14, Volume I, Chapter 3, apply only to land aerodromes. The specifications in this volume also apply, where appropriate, to heliports but not to stolports.

Note. — Although there are presently no specifications relating to stolports, specifications for stolports will be included as they are developed by ICAO. In the interim, guidance material for stolports is contained in the ICAO Stolports Manual (Doc 9150).

- c) Wherever a color is referred to in this GACAR Section, the specifications for the color are contained in Appendix 1 shall apply

#### **5) Rules of Constructions:**

- a) To avoid any misunderstanding within this regulation, certain words are to be interpreted as having specific meanings when they are used, unless the context requires otherwise:
1. Words importing the singular include the plural;
  2. Words importing the plural include the singular; and
  3. Words importing the masculine gender include the feminine

b) In this regulation, the following protocol is used:

1. The words "**Shall**" and "**must**" indicate that compliance is compulsory.
2. The word "**should**" indicates a recommendation. It does not mean that compliance is optional but rather that, where insurmountable difficulties exist, the GACA- S&ER may accept an alternative means of compliance, provided that an acceptable safety assurance from the Aerodrome shows that the safety requirements will not be reduced below that intended by the requirement.
3. The word "**Can**" or "**May**" is used in a permissive sense to state authority or permission to do the act prescribed, and the words "no person may \* \* \*" or "a person may not \* \* \*" mean that no person is required, authorized, or permitted to do the act prescribed;
4. The word "**will**" is used to express the future; and
5. The word "**Includes**" means "**includes but is not limited to**".

#### 6) Airport design:

- a) Architectural and infrastructure-related requirements for the optimum implementation of international civil aviation security measures shall be integrated into the design and construction of new facilities and included in the alterations to existing facilities at an aerodrome.

Note. — Guidance on all aspects of the planning of aerodromes, including security considerations, is contained in the ICAO Airport Planning Manual (Doc 9184), Part 1.

- b) The design of aerodromes should take into account, where appropriate, land-use and environmental control measures.

Note. — Guidance on land-use planning and environmental control measures is contained in the ICAO Airport Planning Manual (Doc 9184), Part 2.

#### 7) Common reference systems:

- a) Horizontal reference system - World Geodetic System- 1984 (WGS-84) shall be used as the horizontal (geodetic) reference system. Reported aeronautical geographical coordinates (indicating latitude and longitude) shall be expressed in terms of the WGS-84 geodetic reference datum.

Note. — Comprehensive guidance material concerning WGS-84 is contained in the World Geodetic System — 1984 (WGS-84) Manual (Doc 9674).

- b) Vertical reference system - Mean Sea Level (MSL) datum, which gives the relationship of gravity-related height (elevation) to a surface known as the geoid, shall be used as the vertical reference system.

Note 1 — The geoid globally most closely approximates MSL. It is defined as the equipotential surface in the gravity field of the Earth, which coincides with the undisturbed MSL extended



continuously through the continents.

Note 2 — Gravity-related heights (elevations) are also referred to as orthometric heights while distances of points above the ellipsoid are referred to as ellipsoidal heights.

- c) Temporal reference system - The Gregorian calendar and Coordinated Universal Time (UTC) shall be used as the temporal reference system. When a different temporal reference system is used, this shall be indicated in GEN 2.1.2 of the Aeronautical Information Publication (AIP), see GACA Regulation Section 15 and ICAO Annex 15, Appendix 1.

## 8) Reference code:

Introductory Note — The intent of the reference code is to provide a simple method for interrelating the numerous specifications concerning the characteristics of aerodromes so as to provide a series of aerodrome facilities that are suitable for the aeroplanes that are intended to operate at the aerodrome. The code is not intended to be used for determining runway length or pavement strength requirements. The code is composed of two elements which are related to the aeroplane performance characteristics and dimensions. Element 1 is a number based on the aeroplane reference field length and element 2 is a letter based on the aeroplane wing span and outer main gear wheel span. A particular specification is related to the more appropriate of the two elements of the code or to an appropriate combination of the two code elements. The code letter or number within an element selected for design purposes is related to the critical aeroplane characteristics for which the facility is provided. When applying GACAR Section 14, Volume I, the aeroplanes which the aerodrome is intended to serve are first identified and then the two elements of the code;

- a) An aerodrome reference code — code number and letter — which is selected for aerodrome planning purposes shall be determined in accordance with the characteristics of the aeroplane for which an aerodrome facility is intended.
- b) The aerodrome reference code numbers and letters shall have the meanings assigned to them in Table 1-1.
- c) The code number for element 1 shall be determined from Table 1-1, column 1, selecting the code number corresponding to the highest value of the aeroplane reference field lengths of the aeroplane for which the runway is intended.

Note. — The determination of the aeroplane reference field length is solely for the selection of a code number and is not intended to influence the actual runway length provided.

- d) The code letter for element 2 shall be determined from Table 1-1, column 3, by selecting the code letter which corresponds to the greatest wing span, or the greatest outer main gear wheel span, whichever gives the more demanding code letter of the aeroplanes for which the facility is intended.

Note. — Guidance to assist the appropriate authority in determining the aerodrome reference

**GACA REGULATIONS - SECTION 14 - AERODROMES**  
**VOLUME I - AERODROME DESIGN AND OPERATIONS**  
**CONTENT RULES**

code is given in the ICAO Aerodrome Design Manual (Doc 9157), Parts 1 and 2.

Table 1-1. Aerodrome reference code  
*(see 1.4.2 to 1.4.4)*

Code element 1		Code element 2		
Code number (1)	Aeroplane reference field length (2)	Code letter (3)	Wing span (4)	Outer main gear wheel span <sup>a</sup> (5)
1	Less than 800 m	A	Up to but not including 15 m	Up to but not including 4.5 m
2	800 m up to but not including 1 200 m	B	15 m up to but not including 24 m	4.5 m up to but not including 6 m
3	1 200 m up to but not including 1 800 m	C	24 m up to but not including 36 m	6 m up to but not including 9 m
4	1 800 m and over	D	36 m up to but not including 52 m	9 m up to but not including 14 m
		E	52 m up to but not including 65 m	9 m up to but not including 14 m
		F	65 m up to but not including 80 m	14 m up to but not including 16 m

a. Distance between the outside edges of the main gear wheels.

*Note.— Guidance on planning for aeroplanes with wing spans greater than 80 m is given in the Aerodrome Design Manual, Parts 1 and 2.*

Table 1-1 Aerodrome reference code  
(See Paragraph 8 - a to d above).



## 9) MANUALS:

The following ICAO manuals and documents related to the specifications of this Section have been approved by GACA for use as guidance materials;

Design Manual (Doc 9157)  
Part 1 — Runways  
Part 2 — Taxiways, Aprons and Holding Bays  
Part 3 — Pavements  
Part 4 — Visual Aids  
Part 5 — Electrical Systems  
Part 6 — Frangibility  
Aeronautical Information Services Manual (Doc 8126)  
Airport Planning Manual (Doc 9184)  
Part 1 — Master Planning  
Part 2 — Land Use and Environmental Control  
Part 3 — Guidelines for Consultant/Construction Services  
Airport Services Manual (Doc 9137)  
Part 1 — Rescue and Fire Fighting  
Part 2 — Pavement Surface Conditions  
Part 3 — Bird Control and Reduction  
Part 5 — Removal of Disabled Aircraft  
Part 6 — Control of Obstacles  
Part 7 — Airport Emergency Planning  
Part 8 — Airport Operational Services  
Part 9 — Airport Maintenance Practices  
Air Traffic Services Planning Manual (Doc 9426)  
Airworthiness Manual (Doc 9760)  
Volume I — Organization and Procedures  
Volume II — Design Certification and Continuing Airworthiness  
Guidance on the Balanced Approach to Aircraft Noise Management (Doc 9829)  
Heliport Manual (Doc 9261)  
Human Factors Training Manual (Doc 9683)  
Manual of Aircraft Ground De-icing/Anti-icing Operations (Doc 9640)  
Manual of Surface Movement Guidance and Control Systems (SMGCS) (Doc 9476)  
Manual on Certification of Aerodromes (Doc 9774)  
Manual on Laser Emitters and Flight Safety (Doc 9815)  
Manual on the ICAO Bird Strike Information System (IBIS) (Doc 9332)  
Procedures for Air Navigation Services — Aircraft Operations (PANS-OPS) (Doc 8168)  
Volume I — Flight Procedures  
Volume II — Construction of Visual and Instrument Flight Procedures  
Procedures for Air Navigation Services - Air Traffic Management (PANS-ATM) (Doc 4444)  
Safety Management Manual (SMM) (Doc 9859)  
Stolport Manual (Doc 9150)  
World Geodetic System — 1984 (WGS-84) Manual (Doc 9674)

## **AMENDMENT PROCEDURE**


The existing General Authority of Civil Aviation Regulations (GACAR) will be periodically reviewed to reflect the latest updates of International Civil Aviation Organization (ICAO) Standards and Recommended Practices (SARPs); it will be also amended to reflect the latest aviation safety provisions issued by GACA and other regional and international Civil Aviation organizations. A complete revised edition incorporating all amendments will be published every three years from the original effective date of this regulation. The amendment procedure shall be as follows;

1. When the General Authority of Civil Aviation (GACA) receives an amendment to any of the current ICAO Annexes that can affect the provisions of this regulation, it will be forwarded by the Vice President of International Organization Affairs to the Vice President, Safety and Economic Regulation (S&ER) who in turn will provide a copy of this amendment to the concerned department for study and comments taking into account the ICAO deadline for the reply.
2. When any GACA department or stakeholder proposes an amendment to this regulation, it will send a letter with the proposed amendment including a clear justification and argument for such amendment. Following the receipt of an amendment proposal, the S&ER will analyze this proposal and forward its comments and any proposed decision action to the S&ER Vice President.
3. An accepted amendment proposal will be prepared as draft amendment to the GACAR-Section 14 and forwarded to the originator of the amendment proposal and concerned GACA department (s) for further review and comment within a specified timeline.
4. All accepted amendments will be drafted in the form of Notices of Proposed Amendments (NPA) and forwarded to all concerned parties including stakeholders for comment within a two-month reply period. The NPA shall indicate the proposed Amendment's effective date.
5. Following the receipt of NPA replies, the S&ER will analyze the comments received and produce a new draft in consultation with the concerned GACA department. The final draft will be submitted to President of the General Authority of Civil Aviation for formal approval prior to publication.
6. The Amendment's effective date will take into account the comments of all the concerned parties and stakeholders.
7. Any differences between the GACAR Section 14 new amendment and ICAO Annexes Standards and Recommended Practices will be forwarded to ICAO as a Difference and published as it is in the Aeronautical Information Publication (AIP).
8. All concerned parties and stakeholders will be provided a copy of the new amendment and will be requested to update their copy of the GACAR Section 14 accordingly.
9. It is the responsibility of all concerned parties to keep their copy of GACAR-Section 14 and other GACA regulation publication up to date.

### **SUPPLEMENTARY REGULATIONS**

From time to time it will be necessary to issue regulations which supplement or augment the GACA Regulations. The following procedures will apply:

1. Supplementary regulations will be issued in the form of a GACA Regulation Circular (RC).
2. The GACA Regulation Circular will be approved by the President.
3. The process for preparation and publishing of the GACA Regulation Circular will be addressed in the GACA Quality System Manual.



### AMENDMENT RECORD

This edition incorporates all ICAO amendments to annex 14 - volume I, up to and including amendment 11.

Amendment number	Amendment date	Affected pages	Effective Date	Incorporated by	Incorporated on
Edition 1	Feb 2009	ALL	Feb 2009	ASSD	Feb. 2009
Edition 2	15 November 2012	ALL	15 Nov 2012	ASSD	15 November 2012
Edition 3	14 Nov 2013	ALL	14 Nov 2013	ASSD	14 Nov 2013

## LIST OF CURRENT DIFFERENCES TO ICAO SARPS

GACA Regulation – Section-14 Volume 1, is based on ICAO Annex 14 Volume 1. The following is a list of differences between the GACA Regulation and the ICAO Standards and Recommended Practices (SARPS). Differences have been notified to ICAO and are also published in the KSA Aeronautical Information Publication (AIP-GEN 1.7).

[illegible]

## TABLE OF CONTENTS

### TABLE OF CONTENTS

FOREWORD.....	i
CONTENT RULES.....	ii
AMENDMENT PROCEDURE.....	ix
SUPPLEMENTARY REGULATIONS.....	x
AMENDMENT RECORD.....	xi
LIST OF CURRENT DIFFERENCES TO ICAO SARPS.....	xii
TABLE OF CONTENTS.....	xiii
CHAPTER 1 DEFINITIONS .....	1-1
1.1 Certification of aerodromes .....	1-1
1.2 Framework for the State Safety Programme (SSP) for Aerodromes .....	1-1
1.3 Definitions .....	1-2
1.4 Abbreviations And Symbols .....	1-6
CHAPTER 2 AERODROME DATA .....	2-1
2.1 Aeronautical data .....	2-1
2.2 Aerodrome reference point .....	2-1
2.3 Aerodrome and runway elevations .....	2-2
2.4 Aerodrome reference temperature .....	2-2
2.5 Aerodrome dimensions and related information .....	2-2
2.6 Strength of pavements .....	2-3
2.7 Pre-flight altimeter check location .....	2-4
2.8 Declared distances .....	2-4
2.9 Condition of the movement area and related facilities .....	2-6
2.10 Disabled aircraft removal .....	2-5
2.11 Rescue and fire fighting .....	2-6
2.12 Visual approach slope indicator systems .....	2-6
2.13 Coordination between aeronautical information services and aerodrome authorities .....	2-7
CHAPTER 3 PHYSICAL CHARACTERISTICS .....	3-1
3.1 Runways .....	3-1
3.2 Runway shoulders .....	3-4
3.3 Runway turn pads .....	3-5
3.4 Runway strips .....	3-6
3.5 Runway end safety areas .....	3-8
3.6 Clearways .....	3-9
3.7 Stopways .....	3-10
3.8 Radio altimeter operating area .....	3-10
3.9 Taxiways .....	3-10
3.10 Taxiway shoulders .....	3-16
3.11 Taxiway strips .....	3-16
3.12 Holding bays, runway-holding positions, intermediate holding positions and road-holding positions .....	3-17
3.13 Aprons .....	3-19
3.14 Isolated aircraft parking position .....	3-19
3.15 De-icing/anti-icing facilities .....	3-19

## TABLE OF CONTENTS

<b>CHAPTER 4 OBSTACLE RESTRICTION AND REMOVAL .....</b>	<b>4-1</b>
4.1 Obstacle limitation surfaces	4-1
4.2 Obstacle limitation requirements	4-5
4.3 Objects outside the obstacle limitation surfaces	4-9
4.4 Other objects	4-9
<b>CHAPTER 5 Visual aids for navigation .....</b>	<b>5-1</b>
5.1 Indicators and signaling devices	5-1
5.1.1 Wind direction indicators	5-1
5.1.2 Landing direction indicator	5-1
5.1.3 Signaling lamp	5-1
5.1.4 Signal panels and signal area	5-2
5.2 Markings	5-2
5.2.1 General	5-2
5.2.2 Runway designation marking	5-2
5.2.3 Runway center line marking	5-5
5.2.4 Threshold marking	5-5
5.2.5 Aiming point marking	5-6
5.2.6 Touchdown zone marking	5-6
5.2.7 Runway side stripe marking	5-8
5.2.8 Taxiway center line marking	5-8
5.2.9 Runway turn pad marking	5-8
5.2.10 Runway-holding position marking	5-9
5.2.11 Intermediate holding position marking	5-12
5.2.12 VOR aerodrome check-point marking	5-12
5.2.13 Aircraft stand markings	5-12
5.2.14 Apron safety lines	5-15
5.2.15 Road-holding position marking	5-15
5.2.16 Mandatory instruction marking	5-15
5.2.17 Information marking	5-15
5.3 Lights	5-17
5.3.1 General	5-17
5.3.2 Emergency lighting	5-21
5.3.3 Aeronautical beacons	5-21
5.3.4 Approach lighting systems	5-22
5.3.5 Visual approach slope indicator systems	5-28
5.3.6 Circling guidance lights	5-37
5.3.7 Runway lead-in lighting systems	5-39
5.3.8 Runway threshold identification lights	5-39
5.3.9 Runway edge lights	5-40
5.3.10 Runway threshold and wing bar lights	5-40
5.3.11 Runway end lights	5-41
5.3.12 Runway center line lights	5-41
5.3.13 Runway touchdown zone lights	5-44
5.3.14 Rapid exit taxiway indicator lights	5-45
5.3.15 Stopway lights	5-46
5.3.16 Taxiway center line lights	5-46
5.3.17 Taxiway edge lights	5-49
5.3.18 Runway turn pad lights	5-49
5.3.19 Stop bars	5-51
5.3.20 Intermediate holding position lights	5-51
5.3.21 De-icing/anti-icing facility exit lights	5-52
5.3.22 Runway guard lights	5-54
5.3.23 Apron floodlighting	5-55
5.3.24 Visual docking guidance system	5-55
5.3.25 Advance visual docking guidance system	5-56



## TABLE OF CONTENTS

5.3.26 Road-holding position light	5-57
5.4 Signs	5-58
5.4.1 General	5-58
5.4.2 Mandatory instruction signs	5-58
5.4.3 Information signs	5-63
5.4.4 VOR aerodrome check-point sign	5-65
5.4.5 Aerodrome identification sign	5-65
5.4.6 Aircraft stand identification signs	5-65
5.4.7 Road-holding position sign	5-67
5.5 Markers	5-67
5.5.1 General	5-67
5.5.2 Unpaved runway edge markers	5-67
5.5.3 Stopway edge markers	5-67
5.5.4 Edge markers for snow-covered runways	5-67
5.5.5 Taxiway edge markers	5-68
5.5.6 Taxiway center line markers	5-68
5.5.7 Unpaved taxiway edge markers	5-68
5.5.8 Boundary markers	5-68
<b>CHAPTER 6 VISUAL AIDS FOR DENOTING OBSTACLES .....</b>	<b>6-1</b>
6.1 Objects to be marked and/or lighted	6-1
6.2 Marking of objects	6-2
6.3 Lighting of objects	6-4
6.4 Wind turbines	6-8
<b>CHAPTER 7 VISUAL AIDS FOR DENOTING RESTRICTED USE AREAS.....</b>	<b>7-1</b>
7.1 Closed runways and taxiways, or parts thereof	7-1
7.2 Non-load-bearing surfaces	7-1
7.3 Pre-threshold area	7-1
7.4 Unserviceable areas	7-1
<b>CHAPTER 8 ELECTRICAL SYSTEMS .....</b>	<b>8-1</b>
8.1 Electrical power supply systems for air navigation facilities	8-1
8.2 System design	8-2
8.3 Monitoring	8-2
<b>CHAPTER 9 AERODROME OPERATIONAL SERVICES, EQUIPMENT AND INSTALLATION</b>	<b>9-1</b>
9.1 Aerodrome emergency planning	9-1
9.2 Rescue and fire fighting	9-2
9.3 Disabled aircraft removal	9-6
9.4 wildlife strike hazard reduction	9-8
9.5 Apron management service	9-9
9.6 Ground servicing of aircraft	9-9
9.7 Aerodrome vehicle operations	9-10
9.8 Surface movement guidance and control systems	9-10
9.9 Siting of equipment and installations on operational areas	9-11
9.10 Fencing	9-11
9.11 Security lighting	9-11
<b>CHAPTER 10 AERODROME MAINTENANCE.....</b>	<b>10-1</b>
10.1 General	10-1
10.2 Pavements	10-1
10.3 Runway pavement overlays	10-2
10.4 Visual aids	10-2

## TABLE OF CONTENTS

<b>APPENDIX 1 COLORS FOR AERONAUTICAL GROUND LIGHTS, MARKINGS, SIGNS AND PANELS.....</b>	<b>APP 1-1</b>
1. General	APP 1-1
2. Colors for aeronautical ground lights	APP 1-1
3. Colors for markings, signs and panels	APP 1-2
<b>APPENDIX 2 AERONAUTICAL GROUND LIGHT CHARACTERISTICS.....</b>	<b>APP 2-1</b>
<b>APPENDIX 3 MANDATORY INSTRUCTION MARKINGS AND INFORMATION MARKINGS.....</b>	<b>APP 3-1</b>
<b>APPENDIX 4 REQUIREMENTS CONCERNING DESIGN OF TAXIING GUIDANCE SIGNS.....</b>	<b>APP 4-1</b>
<b>APPENDIX 5 AERONAUTICAL DATA QUALITY REQUIREMENTS.....</b>	<b>APP 5-1</b>
<b>APPENDIX 6 LOCATION OF LIGHTS ON OBSTACLES.....</b>	<b>APP 6-1</b>
<b>ATTACHMENT A. Guidance material supplementary to Section 14, Volume I.....</b>	<b>ATTA-1</b>
1. Number, siting and orientation of runways	ATT A-1
2. Clearways and stopways	ATT A-1
3. Calculation of declared distances	ATT A-3
4. Slopes on a runway	ATT A-3
5. Runway surface evenness	ATT A-3
6. Determining and expressing the friction characteristics of snow- and ice-covered paved surfaces	ATT A-5
7. Determination of friction characteristics of wet paved runways	ATT A-6
8. Strips	ATT A-8
9. Runway end safety areas	ATT A-9
10. Location of threshold	ATT A-10
11. Approach lighting systems	ATT A-10
12. Priority of installation of visual approach slope indicator systems	ATT A-16
13. Lighting of unserviceable areas	ATT A-17
14. Rapid exit taxiway indicator lights. . .	ATT A-17
15. Intensity control of approach and runway lights	ATT A-17
16. Signal area	ATT A-17
17. Rescue and fire fighting services	ATT A-17
18. Operators of vehicles	ATT A-19
19. The ACN-PCN method of reporting pavement strength	ATT A-19
<b>ATTACHMENT B. Obstacle limitation surfaces .....</b>	<b>ATT B-1</b>
<b>ATTACHMENT C Framework for the State Safety Programme</b>	<b>ATT C-1</b>
<b>LIMITED INDEX OF SIGNIFICANT SUBJECTS INCLUDED IN Section 14, VOLUME I</b>	<b>INDEX - 1</b>

## CHAPTER 1 - DEFINITIONS

### 1.1 Certification of aerodromes

Note.— The intent of these specifications is to ensure the establishment of a regulatory framework so that compliance with the specifications in this GACAR Section 14 Volume III – Aerodrome Certification can be effectively enforced.

The GACA – SD, AS&S shall ensure the means of compliance with applicable specifications through the AS&S as a separate safety oversight entity and a well-defined safety oversight mechanism.

When an aerodrome is granted a certificate, it signifies to aircraft operators and other organizations operating on the aerodrome that, at the time of certification, the aerodrome meets the specifications regarding the facility and its operation, and that it has, according to the certifying authority, the capability to maintain these specifications for the period of validity of the certificate.

The certification process also establishes the baseline for continued monitoring of compliance with the specifications. Information on the status of certification of aerodromes would need to be provided to the appropriate aeronautical information services for promulgation in the Aeronautical Information Publication (AIP). See 2.13.1 and Annex 15, Appendix 1, AD 1.5.

**1.1.1 GACA** shall certify aerodromes used for international operations in accordance with the specifications contained in this Section 14 Volume III – Aerodrome Certification as well as other relevant ICAO specifications through an appropriate regulatory framework.

**1.1.2 GACA** shall certify aerodromes open to public use in accordance with the 14 Volume III – Aerodrome Certification and these specifications as well as other relevant ICAO specifications through an appropriate regulatory framework.

**1.1.3** The regulatory framework shall include the establishment of criteria and procedures for the certification of aerodromes.

Note.— Guidance on a regulatory framework is given in

the Manual on Certification of Aerodromes

**1.1.4** As part of the certification process, **GACA** shall ensure that an Aerodrome Manual (AM) which will include all pertinent information on the aerodrome site, facilities, services, equipment, operating procedures, organization and management including a safety management system, is submitted by the applicant for approval/acceptance prior to granting the aerodrome certificate

Note.— The intent of a safety management system is to have in place an organized and orderly approach in the management of aerodrome safety by the aerodrome operator. Annex 19 contains the safety management provisions applicable to certified aerodromes. Guidance on an aerodrome safety management system is given in the Safety Management Manual (SMM) (Doc 9859) and in the Manual on Certification of Aerodromes (Doc 9774).

### 1.2 Framework for the State Safety Programme (SSP) for Aerodromes

**1.2.1** In the kingdom of Saudi Arabia, the responsibility to implement an SSP rests with the GACA/S&ER.

**1.2.2** The GACA – SD, Airport Standards and Safety Division (AS&S) shall implement and maintain the SSP for Aerodromes in order to achieve an acceptable level of safety in aerodrome operations.

**1.2.3** The GACA – SD, AS&S shall establish the acceptable level(s) of safety to be achieved by utilizing the Guidance on safety program and on defining acceptable levels of safety that is contained in the ICAO Safety Management Manual (SMM) (Doc 9859).

**1.2.4** The GACA – SD, AS&S shall require, as part of its safety program, that a certified aerodrome operator implements a Safety Management System (SMS) acceptable to the GACA – SD, AS&S that, as a minimum:

- a. identifies safety hazards;
- b. ensures that remedial action necessary to maintain an acceptable level of safety is implemented;
- c. provides for continuous monitoring and regular assessment of the safety level achieved; and
- d. aims to make continuous improvement to the overall level of safety.

**1.2.5** A Safety Management System shall clearly define lines of safety accountability throughout the staff of a certified aerodrome operator, including direct accountability for safety on the part of senior management.

1.2.6 The intent of a Safety Management System is to have in place an organized and orderly approach in the management of aerodrome safety by the aerodrome operator. Guidance on an aerodrome Safety Management System is given in the GACAR - Section -21 - Safety Management System, and in the ICAO Safety Management Manual (SMM) (Doc 9859).

Note.— Guidance on defining acceptable level of safety is contained in the Safety Management Manual (SMM) (Doc 9859).

### 1.3. Definitions

When the following terms are used in this regulation, they shall have the following meanings:

**Accuracy.** A degree of conformance between the estimated or measured value and the true value.

Note. — For measured positional data, the accuracy is normally expressed in terms of a distance from a stated position within which there is a defined confidence of the true position falling.

**Aerodrome.** A defined area on land or water (including any buildings, installations and equipment) intended to be used either wholly or in part for the arrival, departure and surface movement of aircraft.

**Aerodrome beacon.** Aeronautical beacon used to indicate the location of an aerodrome from the air.

**Aerodrome certificate.** A certificate issued by the appropriate authority under applicable regulations for the operation of an aerodrome.

**Aerodrome elevation.** The elevation of the highest point of the landing area.

**Aerodrome identification sign.** A sign placed on an aerodrome to aid in identifying the aerodrome from the air.

**Aerodrome reference point.** The designated geographical location of an aerodrome.

**Aerodrome traffic density.**

a) Light. Where the number of movements in the mean busy hour is not greater than 15 per runway or typically less than 20 total aerodrome movements.

b) Medium. Where the number of movements in the mean busy hour is of the order of 16 to 25 per runway or

typically between 20 to 35 total aerodrome movements c) Heavy. Where the number of movements in the mean busy hour is of the order of 26 or more per runway or typically more than 35 total aerodrome movements.

Note 1. — The number of movements in the mean busy hour is the arithmetic mean over the year of the number of movements in the daily busiest hour.

Note 2. — Either a take-off or a landing constitutes a movement.

**Aeronautical beacon.** An aeronautical ground light visible at all azimuths, either continuously or intermittently, to designate a particular point on the surface of the earth.

**Aeronautical ground light.** Any light specially provided as an aid to air navigation, other than a light displayed on an aircraft.

**Aeroplane reference field length.** The minimum field length required for take-off at maximum certificated take-off mass, sea level, standard atmospheric conditions, still air and zero runway slope, as shown in the appropriate aeroplane flight manual prescribed by the certificating authority or equivalent data from the aeroplane manufacturer. Field length means balanced field length for aeroplanes, if applicable, or take-off distance in other cases.

Note. — Attachment A, Section 2 provides information on the concept of balanced field length and the Airworthiness Manual (Doc 9760) contains detailed guidance on matters related to take-off distance.

**Aerodrome mapping data (AMD).** Data collected for the purpose of compiling aerodrome mapping information for aeronautical uses

Note — Aerodrome mapping data are collected for purposes that include the improvement of the user's situational awareness, surface navigation operations, training, charting and planning.

**Aerodrome mapping database (AMDB).** A collection of aerodrome mapping data organized and arranged as a structured data set.

**Aircraft classification number (ACN).** A number expressing the relative effect of an aircraft on a pavement for a specified standard sub-grade category.

Note. — The aircraft classification number is calculated with respect to the center of gravity (CG) position which yields the critical loading on the critical gear. Normally the aft most CG position appropriate to the maximum

gross apron (ramp) mass is used to calculate the ACN. In exceptional cases the forward most CG position may result in the nose gear loading being more critical.

**Aircraft stand.** A designated area on an apron intended to be used for parking an aircraft.

**Apron.** A defined area, on a land aerodrome, intended to accommodate aircraft for purposes of loading or unloading passengers, mail or cargo, fueling, parking or maintenance.

**Apron management service.** A service provided to regulate the activities and the movement of aircraft and vehicles on an apron.

**Balked landing.** A landing maneuver that is unexpectedly discontinued at any point below the obstacle clearance altitude/height (OCA/H).

**Barrette.** Three or more aeronautical ground lights closely spaced in a transverse line so that from a distance they appear as a short bar of light.

**Calendar.** Discrete temporal reference system that provides the basis for defining temporal position to a resolution of one day (ISO 19108\*).

**Capacitor discharge light.** A lamp in which high-intensity flashes of extremely short duration are produced by the discharge of electricity at high voltage through a gas enclosed in a tube.

**Certified aerodrome.** An aerodrome whose operator has been granted an aerodrome certificate.

**Clearway.** A defined rectangular area on the ground or water under the control of the appropriate authority selected or prepared as a suitable area over which an aeroplane may make a portion of its initial climb to a specified height.

**Cyclic redundancy check (CRC).** A mathematical algorithm applied to the digital expression of data that provides a level of assurance against loss or alteration of data.

**Data quality.** A degree or level of confidence that the data provided meet the requirements of the data user in terms of accuracy, resolution and integrity.

**Datum.** Any quantity or set of quantities that may serve as a reference or basis for the calculation of other quantities (ISO 19104\*).

**De-icing/anti-icing facility.** A facility where frost, ice or

snow is removed (de-icing) from the aeroplane to provide clean surfaces, and/or where clean surfaces of the aeroplane receive protection (anti-icing) against the formation of frost or ice and accumulation of snow or slush for a limited period of time.

Note. — Further guidance is given in the Manual of Aircraft Ground De-icing/Anti-icing Operations (Doc 9640).

**De-icing/anti-icing pad.** An area comprising an inner area for the parking of an aeroplane to receive de-icing/anti-icing treatment and an outer area for the maneuvering of two or more mobile de-icing/anti-icing equipment.

**Declared distances.**

a) Take-off run available (TORA). The length of runway declared available and suitable for the ground run of an aeroplane taking off.

b) Take-off distance available (TODA). The length of the take-off run available plus the length of the clearway, if provided.

\* All ISO Standards are listed at the end of this chapter.

c) Accelerate-stop distance available (ASDA)

The length of the take-off run available plus the length of the stopway, if provided.

d) Landing distance available (LDA). The length of runway which is declared available and suitable for the ground run of an aeroplane landing.

**Dependent parallel approaches.** Simultaneous approaches to parallel or near-parallel instrument runways where radar separation minima between aircraft on adjacent extended runway center lines are prescribed.

**Displaced threshold.** A threshold not located at the extremity of a runway.

**Effective intensity.** The effective intensity of a flashing light is equal to the intensity of a fixed light of the same color which will produce the same visual range under identical conditions of observation.

**Ellipsoid height (Geodetic height).** The height related to the reference ellipsoid, measured along the ellipsoidal outer normal through the point in question.

**Fixed light.** A light having constant luminous intensity when observed from a fixed point.

**Frangible object.** An object of low mass designed to break, distort or yield on impact so as to present the



minimum hazard to aircraft.

Note. — Guidance on design for frangibility is contained in the ICAO Aerodrome Design Manual (Doc 9157), Part 6.

GACA – SD, AS&S. General Authority of Civil Aviation. Safety Department. Airport Standards and Safety Division.

**Geodetic datum.** A minimum set of parameters required to define location and orientation of the local reference system with respect to the global reference system/frame.

**Geoid.** The equipotential surface in the gravity field of the earth which coincides with the undisturbed mean sea level (MSL) extended continuously through the continents.

Note. — The geoid is irregular in shape because of local gravitational disturbances (wind tides, salinity, current, etc.) and the direction of gravity is perpendicular to the geoid and every point.

**Geoid undulation.** The distance of the geoid above (positive) or below (negative) the mathematical reference ellipsoid.

Note. — In respect to the World Geodetic System — 1984 (WGS-84) defined ellipsoid, the difference between the WGS-84 ellipsoidal height and orthometric height represents WGS-84 geoid undulation.

**Gregorian calendar.** Calendar in general use; first introduced in 1582 to define a year that more closely approximates the tropical year than the Julian calendar (ISO 19108\*).

Note. — In the Gregorian calendar, common years have 365 days and leap years 366 days divided into twelve sequential months.

**Hazard beacon.** An aeronautical beacon used to designate a danger to air navigation.

**Heliport.** An aerodrome or a defined area on a structure intended to be used wholly or in part for the arrival, departure and surface movement of helicopters.

**Holding bay.** A defined area where aircraft can be held, or bypassed, to facilitate efficient surface movement of aircraft.

**Holdover time.** The estimated time the anti-icing fluid (treatment) will prevent the formation of ice and frost and the accumulation of snow on the protected (treated) surfaces of an aeroplane.

**Hot spot.** A location on an aerodrome movement area

with a history or potential risk of collision or runway incursion, and where heightened attention by pilots/drivers is necessary

**Human Factors principles.** Principles which apply to aeronautical design, certification, training, operations and maintenance and which seek safe interface between the human and other system components by proper consideration to human performance.

**Human performance.** Human capabilities and limitations which have an impact on the safety and efficiency of aeronautical operations.

**Identification beacon.** An aeronautical beacon emitting a coded signal by means of which a particular point of reference can be identified.

**Independent parallel approaches.** Simultaneous approaches to parallel or near-parallel instrument runways where radar separation minima between aircraft on adjacent extended runway center lines are not prescribed.

**Independent parallel departures.** Simultaneous departures from parallel or near-parallel instrument runways.

**Instrument runway.** One of the following types of runways intended for the operation of aircraft using instrument approach procedures:

- a) *Non-precision approach runway.* A runway served by visual aids and a non-visual aid(s) intended for landing operations following an instrument approach operation type A and a visibility not less than 1000m.
- b) *Precision approach runway, category I.* A runway served by visual aids and non-visual aid(s) intended for landing operations following an instrument approach operation type B with a decision height (DH) not lower than 60 m (200 ft) and either a visibility not less than 800 m or a runway visual range not less than 550 m.
- c) *Precision approach runway, category II.* A runway served by visual aid and non-visual aid(s) intended for landing operations following an instrument approach operation type B with a decision height lower than 60 m (200 ft) but not lower than 30 m (100 ft) and a runway visual range not less than 300 m.
- d) *Precision approach runway, category III.* A runway served by visual aids and non-visual aid(s) intended for landing operations following an instrument approach operation type B to and along the surface of the runway and:
  - intended for operations with a decision height (DH) lower than 30 m (100 ft), or no

- decision height and a runway visual range not less than 200 m.
- intended for operations with a decision height (DH) lower than 15 m (50 ft), or no decision height and a runway visual range less than 200 m but not less than 50 m.
- intended for operations with no decision height (DH) and no runway visual range limitations.

Note 1. — Visual aids need not necessarily be matched to the scale of non-visual aids provided. The criterion for the selection of visual aids is the conditions in which operations are intended to be conducted.

Note 2. — Refer to GACAR Section 6 for instrument approach operation types.

**Integrity (aeronautical data).** A degree of assurance that an aeronautical data and its value has not been lost or altered since the data origination or authorized amendment.

**Integrity classification (aeronautical data).** Classification based upon the potential risk resulting from the use of corrupted data. Aeronautical data is classified as:

- a) routine data: there is a very low probability when using corrupted routine data that the continued safe flight and landing of an aircraft would be severely at risk with the potential for catastrophe;
- b) essential data: there is a low probability when using corrupted essential data that the continued safe flight and landing of an aircraft would be severely at risk with the potential for catastrophe; and
- c) critical data: there is a high probability when using corrupted critical data that the continued safe flight and landing of an aircraft would be severely at risk with the potential for catastrophe

**Intermediate holding position.** A designated position intended for traffic control at which taxiing aircraft and vehicles shall stop and hold until further cleared to proceed, when so instructed by the aerodrome control tower.

**Landing area.** That part of a movement area intended for the landing or take-off of aircraft.

**Landing direction indicator.** A device to indicate visually the direction currently designated for landing and for take-off.

**Laser-beam critical flight zone (LCFZ).** Airspace in the

proximity of an aerodrome but beyond the LFFZ where the irradiance is restricted to a level unlikely to cause glare effects.

**Laser-beam free flight zone (LFFZ).** Airspace in the immediate proximity to the aerodrome where the irradiance is restricted to a level unlikely to cause any visual disruption.

**Laser-beam sensitive flight zone (LSFZ).** Airspace outside, and not necessarily contiguous with, the LFFZ and LCFZ where the irradiance is restricted to a level unlikely to cause flash-blindness or after-image effects.

**Lighting system reliability.** The probability that the complete installation operates within the specified tolerances and that the system is operationally usable.

**Maneuvering area.** That part of an aerodrome to be used for the take-off, landing and taxiing of aircraft, excluding aprons.

**Marker.** An object displayed above ground level in order to indicate an obstacle or delineate a boundary.

**Marking.** A symbol or group of symbols displayed on the surface of the movement area in order to convey aeronautical information.

**Movement area.** That part of an aerodrome to be used for the take-off, landing and taxiing of aircraft, consisting of the maneuvering area and the apron(s).

**Near-parallel runways.** Non-intersecting runways whose extended center lines have an angle of convergence/divergence of 15 degrees or less.

**Non-instrument runway.** A runway intended for the operation of aircraft using visual approach procedures or an instrument approach procedure to a point beyond which the approach may continue in visual meteorological conditions.

Note. — Visual meteorological conditions (VMC) are described on Chapter 3 of GACAR section 2.

**Normal flight zone (NFZ).** Airspace not defined as LFFZ, LCFZ or LSFZ but which must be protected from laser radiation capable of causing biological damage to the eye.

**Obstacle.** All fixed (whether temporary or permanent) and mobile objects, or parts thereof, that are located on an area intended for the surface movement of aircraft or that extend above a defined surface intended to protect aircraft in flight.



CHAPTER 1 - DEFINITIONS

**Obstacle free zone (OFZ).** The airspace above the inner approach surface, inner transitional surfaces, and balked landing surface and that portion of the strip bounded by these surfaces, which is not penetrated by any fixed obstacle other than a low-mass and frangibly mounted one required for air navigation purposes.

**Orthometric height.** Height of a point related to the geoid, generally presented as an MSL elevation.

**Pavement classification number (PCN).** A number expressing the bearing strength of a pavement for unrestricted operations.

**Precision approach runway,**  
See **Instrument runway.**

**Primary runway(s).** Runway(s) used in preference to others whenever conditions permit.

**Protected flight zones.** Airspace specifically designated to mitigate the hazardous effects of laser radiation.

**Road.** An established surface route on the movement area meant for the exclusive use of vehicles.

**Road-holding position.** A designated position at which vehicles may be required to hold.

**Runway.** A defined rectangular area on a land aerodrome prepared for the landing and take-off of aircraft.

**Runway end safety area (RESA).** An area symmetrical about the extended runway center line and adjacent to the end of the strip primarily intended to reduce the risk of damage to an aeroplane undershooting or overrunning the runway.

**Runway guard lights.** A light system intended to caution pilots or vehicle drivers that they are about to enter an active runway.

**Runway-holding position.** A designated position intended to protect a runway, an obstacle limitation surface, or an ILS/ MLS critical/sensitive area at which taxiing aircraft and vehicles shall stop and hold, unless otherwise authorized by the aerodrome control tower.

Note. — In radiotelephony phraseologies, the expression “holding point” is used to designate the runway-holding position.

**Runway strip.** A defined area including the runway and stopway, if provided, intended:

- a) to reduce the risk of damage to aircraft running off a runway; and
- b) to protect aircraft flying over it during take-off or

landing operations.

**Runway turn pad.** A defined area on a land aerodrome adjacent to a runway for the purpose of completing a 180-degree turn on a runway.

**Runway visual range (RVR).** The range over which the pilot of an aircraft on the center line of a runway can see the runway surface markings or the lights delineating the runway or identifying its center line.

**State Safety program.** An integrated set of regulations and activities aimed at improving safety.

**Safety management system (SMS).** A systematic approach to managing safety including the necessary organizational structure, accountabilities, policies and procedures.

**Segregated parallel operations.** Simultaneous operations on parallel or near-parallel instrument runways in which one runway is used exclusively for approaches and the other runway is used exclusively for departures.

**Shoulder.** An area adjacent to the edge of a pavement so prepared as to provide a transition between the pavement and the adjacent surface.

**Sign.**

- a. Fixed message sign. A sign presenting only one message.
- b. Variable message sign. A sign capable of presenting several pre-determined messages or no message, as applicable.

**Signal area.** An area on an aerodrome used for the display of ground signals.

**Slush.** Water-saturated snow which with a heel-and-toe slap down motion against the ground will be displaced with a splatter; specific gravity: 0.5 up to 0.8.

Note. — Combinations of ice, snow and/or standing water may, especially when rain, rain and snow, or snow is falling produce substances with specific gravities in excess of 0.8. These substances, due to their high water/ice content, will have a transparent rather than a cloudy appearance and, at the higher specific gravities, will be readily distinguishable from slush.

**Snow (on the ground).**

- a) Dry snow. Snow which can be blown if loose or, if compacted by hand, will fall apart again upon release; specific gravity: up to but not including 0.35.

b) Wet snow. Snow which, if compacted by hand, will stick together and tend to or form a snowball; specific gravity: 0.35 up to but not including 0.5.

c) Compacted snow. Snow which has been compressed into a solid mass that resists further-r compression and will hold together or break up into lumps if picked up; specific gravity: 0.5 and over.

**Station declination.** An alignment variation between the zero degree radial of a VOR and true north, determined at the time the VOR station is calibrated.

**Stopway.** A defined rectangular area on the ground at the end of take-off run available prepared as a suitable area in which an aircraft can be stopped in the case of an abandoned take off.

**Switch-over time (light).** The time required for the actual intensity of a light measured in a given direction to fall from 50 per cent and recover to 50 per cent during a power supply changeover, when the light is being operated at intensities of 25 per cent or above.

**Take-off runway.** A runway intended for take-off only.

**Taxiway.** A defined path on a land aerodrome established for the taxiing of aircraft and intended to provide a link between one part of the aerodrome and another, including:

c) Aircraft stand taxilane. A portion of an apron designated as a taxiway and intended to provide access to aircraft stands only.

d)

b) Apron taxiway. A portion of a taxiway system located on an apron and intended to provide a through taxi route across the apron.

c) Rapid exit taxiway. A taxiway connected to a runway at an acute angle and designed to allow landing aeroplanes to turn off at higher speeds than are achieved on other exit taxiways thereby minimizing runway occupancy times.

**Taxiway intersection.** A junction of two or more taxiways.

**Taxiway strip.** An area including a taxiway intended to protect an aircraft operating on the taxiway and to reduce the risk of damage to an aircraft accidentally running off the taxiway.

**Threshold.** The beginning of that portion of the runway usable for landing.

**Touchdown zone.** The portion of a runway, beyond the

threshold, where it is intended landing aeroplanes first contact the runway.

**Usability factor.** The percentage of time during which the use of a runway or system of runways is not restricted because of the cross-wind component.

**GACA REGULATIONS - SECTION 14 - AERODROMES  
VOLUME I - AERODROME DESIGN AND OPERATIONS**

**CHAPTER 1 - DEFINITIONS**

Note. — Cross-wind component means the surface wind component at right angles to the runway center line.

TORA  
VMC  
VOR

Take-off run available  
Visual meteorological conditions  
Very high frequency omnidirectional radio range

## 1.4 ABBREVIATIONS

When the following abbreviations are used in this regulation, they shall have the following meanings:

ACAC	Arab Civil Aviation Commission
AMODA	Assistant Minister of Defense and Aviation for Civil Aviation Affairs
ACN	Aircraft classification number
aprx	Approximately
AS&S	Airport Standards and Safety Division
ASDA	Accelerate-stop distance available
ATS	Air traffic services
cd	Candela
C	Degree Celsius
CBR	California bearing ratio
CIE	Commission International de l'Éclairage
cm	Centimeter
DME	Distance measuring equipment
ft	Feet
GACA	General Authority of Civil Aviation
GACAR	General Authority of Civil Aviation Regulation
GM	General Manager
ICAO	International Civil Aviation Organization
ILS	Instrument landing system
IMC	Instrument meteorological conditions
K	Degree Kelvin
kg	Kilogram
km	Kilometer
km/h	Kilometer per hour
kt	Knot
L	Liter
LDA	Landing distance available
m	Meter
max	Maximum
mm	Millimeter
mm	Minimum
MN	Meganewton
MPa	Megapascal
NM	Nautical mile
NU	Not usable
OCA/H	Obstacle clearance altitude/height
OFZ	Obstacle free zone
PCN	Pavement classification number
RESA	Runway end safety area
S&ER	Safety and Economic Regulation
SD	Safety Department
RVR	Runway visual range
TODA	Take-off distance available

### *Symbols*

°	Degree
=	Equals
'	Minute of arc
μ	Friction coefficient
>	Greater than
<	Less than
%	Percentage
±	Plus or minus

**Left blank intentionally**

## CHAPTER 2 - AERODROME DATA

### 2.1 Aeronautical data

2.1.1 Determination and reporting of aerodrome related aeronautical data shall be in accordance with the accuracy and integrity requirements set forth in Tables 1 to 5 contained in Appendix 5 while taking into account the established quality system procedures. Accuracy requirements for aeronautical data are based upon a 95 per cent confidence level and in that respect, three types of positional data shall be identified: surveyed points (e.g. runway threshold), calculated points (mathematical calculations from the known surveyed points of points in space, fixes) and declared points (e.g. flight information region boundary points).

Note. — Specifications governing the quality system are given in GACA Regulation Section – 15 and ICAO Annex 15, Chapter 3.

2.1.2 Aerodrome mapping data shall be made available to the aeronautical information services for aerodromes deemed relevant by States where safety and/or performance-based operations suggest possible benefits.

Note.— Aerodrome mapping databases related provisions are contained in Annex 15 Chapter 11.

2.1.3 Where made available in accordance with 2.1.2, the selection of the aerodrome mapping data features to be collected shall be made with consideration of the intended applications.

Note.— It is intended that the selection of the features to be collected match a defined operational need.

2.1.4 Where made available in accordance with 2.1.2, aerodrome mapping data shall comply with the accuracy and integrity requirements in Appendix 5.

Note.— Aerodrome mapping databases can be provided at one of two levels of quality - fine or medium. These levels and the corresponding numerical requirements are defined in RTCA Document DO272B and European Organization for Civil Aviation Equipment (EUROCAE) Document ED-99B — User Requirements for Aerodrome Mapping Information.

2.1.5 GACA shall ensure that integrity of aeronautical data is maintained throughout the data process from survey/origin to the next intended user. Based on the

applicable integrity classifications, the validation and verification procedures shall:

- a. For routine data: avoid corruption throughout the processing of the data;
- b. For essential data assure corruption does not occur at any stage of the entire process and may include additional processes as needed to address potential risks in the overall system architecture to further assure data integrity at this level; and
- c. For critical data: assure corruption does not occur at any stage of the entire process and include additional integrity assurance procedures to fully mitigate the effects of faults identified by thorough analysis of the overall system architecture as potential data integrity risks.

Note.— Guidance material in respect to the processing of aeronautical data and aeronautical information is contained in RTCA Document DO-200A and European Organization for Civil Aviation Equipment (EUROCAE) Document ED-76A — Standards for Processing Aeronautical Data.

2.1.6 Protection of electronic aeronautical data while stored or in transit shall be totally monitored by the cyclic redundancy check (CRC). To achieve protection of the integrity level of critical and essential aeronautical data as classified in 2.1.2, a 32 or 24 bit CRC algorithm shall apply respectively.

2.1.7 To achieve protection of the integrity level of routine aeronautical data as classified in a 16 bit CRC algorithm should apply.

Note. — Guidance material on the aeronautical data quality requirements (accuracy, resolution, integrity, protection and traceability) is contained in the World Geodetic System — 1984 (WGS-84) Manual (Doc 9674). Supporting material in respect of the provisions of Appendix 5 related to accuracy and integrity of aeronautical data is contained in RTCA Document DO-201A and European Organization for Civil Aviation Equipment (EUROCAE) Document ED-77, entitled Industry Requirements for Aeronautical Information.

2.1.8 Geographical coordinates indicating latitude and longitude shall be determined and reported to the aeronautical information services authority in terms of the World Geodetic System — 1984 (WGS-84) geodetic reference datum, identifying those geographical coordinates which have been transformed into WGS-84 coordinates by mathematical means and whose accuracy of original field work does not meet the requirements in Appendix 5, Table A5-1.

2.1.9 The order of accuracy of the field work shall be

such that the resulting operational navigation data for the phases of flight will be within the maximum deviations, with respect to an appropriate reference frame, as indicated in tables contained in Appendix 5.

2.1.10 In addition to the elevation (referenced to mean sea level) of the specific surveyed ground positions at aerodromes, geoid undulation (referenced to the WGS-84 ellipsoid) for those positions as indicated in Appendix 5, shall be determined and reported to the aeronautical information services authority.

Note 1 — An appropriate reference frame is that which enables WGS-84 to be realized on a given aerodrome and with respect to which all coordinate data are related.

Note 2 — Specifications governing the publication of WGS-84 coordinates are given in GACA Regulation Section - 4 and ICAO Annex 4 - Chapter 2, and GACA Regulation Section - 15 and ICAO Annex 15, Chapter 3.

## 2.2 Aerodrome reference point

2.2.1 An aerodrome reference point shall be established for an aerodrome.

2.2.2 The aerodrome reference point shall be located near the initial or planned geometric center of the aerodrome and shall normally remain where first established.

2.2.3 The position of the aerodrome reference point shall be measured and reported to the aeronautical information services authority in degrees, minutes and seconds.

## 2.3 Aerodrome and runway elevations

2.3.1 The aerodrome elevation and geoid undulation at the aerodrome elevation position shall be measured to the accuracy of one-half meter or foot and reported to the aeronautical information services authority.

2.3.2 For an aerodrome used by international civil aviation for non-precision approaches, the elevation and geoid undulation of each threshold, the elevation of the runway end and any significant high and low intermediate points along the runway shall be measured to the accuracy of one-half meter or foot and reported to the aeronautical information services authority.

2.3.3 For precision approach runway, the elevation and geoid undulation of the threshold, the elevation of the runway end and the highest elevation of the touchdown zone shall be measured to the accuracy of one-quarter meter or foot and reported to the aeronautical information

services authority.

Note. — Geoid undulation must be measured in accordance with the appropriate system of coordinates.

## 2.4 Aerodrome reference temperature

2.4.1 An aerodrome reference temperature shall be determined for an aerodrome in degrees Celsius.

2.4.2 The aerodrome reference temperature should be the monthly mean of the daily maximum temperatures for the hottest month of the year (the hottest month being that which has the highest monthly mean temperature). This temperature should be averaged over a period of years.

## 2.5 Aerodrome dimensions and related information

2.5.1 The following data shall be measured or described, as appropriate, for each facility provided on an aerodrome:

- a) runway — true bearing to one-hundredth of a degree, designation number, length, width, displaced threshold location to the nearest meter or foot, slope, surface type, type of runway and, for a precision approach runway category I, the existence of an obstacle free zone when provided;
- b) strip  
runway end safety area      length, width to the  
stopway      nearest meter or foot,  
   surface type;
- c) taxiway — designation, width, surface type;
- d) apron — surface type, aircraft stands;
- e) the boundaries of the air traffic control service;
- f) clearway — length to the nearest meter or foot, ground profile;
- g) visual aids for approach procedures, marking and lighting of runways, taxiways and aprons, other visual guidance and control aids on taxiways and aprons, including taxi holding positions and stop bars, and location and type of visual docking guidance systems;
- h) location and radio frequency of any VOR aerodrome check-point
- i) location and designation of standard taxi-routes; and
- j) distances to the nearest meter or foot of localizer and glide path elements comprising an instrument landing system (ILS) or azimuth and elevation antenna of microwave landing system (MLS) in relation to the



associated runway extremities.

2.5.2 The geographical coordinates of each threshold shall be measured and reported to the aeronautical information services authority in degrees, minutes, seconds and hundredths of seconds.

2.5.3 The geographical coordinates of appropriate taxiway center line points shall be measured and reported to the aeronautical information services authority in degrees, minutes, seconds and hundredths of seconds.

2.5.4 The geographical coordinates of each aircraft stand shall be measured and reported to the aeronautical information services authority in degrees, minutes, seconds and hundredths of seconds.

2.5.5 The geographical coordinates of obstacles in Area 2 (the part within the aerodrome boundary) and in Area 3 shall be measured and reported to the aeronautical information services authority in degrees, minutes, seconds and tenths of seconds. In addition, the top elevation, type, marking and lighting (if any) of obstacles shall be reported to the aeronautical information services authority.

Note 1 — See GACA Regulation Section - 15 and ICAO Annex 15, Appendix 8, for graphical illustrations of obstacle data collection surfaces and criteria used to identify obstacles in Areas 2 and 3.

Note 2 — Appendix 5 provides requirements for obstacle data determination in Areas 2 and 3.

Note 3 — Implementation of GACA Regulation Section - 15 and ICAO Annex 15, provision 10.6.1.2 concerning the availability, as of 18 November 2010, of obstacle data according to Area 2 and Area 3 specifications would be facilitated by appropriate advanced planning for the collection and processing of such data

## 2.6 Strength of pavements

2.6.1 The bearing strength of a pavement shall be determined.

2.6.2 The bearing strength of a pavement intended for aircraft of apron (ramp) mass greater than 5 700 kg shall be made available using the aircraft classification number — pavement classification number (ACN-PCN) method by reporting all of the following information:

- a) the pavement classification number (PCN);
- b) pavement type for ACN-PCN determination;

c) sub grade strength category;

d) maximum allowable tire pressure category or maximum allowable tire pressure value; and

e) evaluation method.

Note. — If necessary, PCNs may be published to an accuracy of one-tenth of a whole number.

2.6.3 The pavement classification number (PCN) reported shall indicate that an aircraft with an aircraft classification number (ACN) equal to or less than the reported PCN can operate on the pavement subject to any limitation on the tire pressure, or aircraft all-up mass for specified aircraft type(s).

Note. — Different PCNs may be reported if the strength of the pavement is subject to significant seasonal variation.

2.6.4 The ACN of an aircraft shall be determined in accordance with the standard procedures associated with the ACN-PCN method.

Note. — The standard procedures for determining the CAN of an aircraft are given in the ICAO Aerodrome Design Manual, Part 3. For convenience several aircraft types currently in use have been evaluated on rigid and flexible pavements founded on the four sub-grade categories in 2.6.6 b) below and the results tabulated in that manual.

2.6.5 For the purposes of determining the ACN, the behavior of a pavement shall be classified as equivalent to a rigid or flexible construction.

2.6.6 Information on pavement type for ACN-PCN determination, sub grade strength category, maximum allowable tire pressure category and evaluation method shall be reported using the following codes:

### a) **Pavement type for ACN-PCN Code determination:**

Rigid pavement	R
Flexible pavement	F

Note. — If the actual construction is composite or nonstandard, include a note to that effect (see example 2 below).

### b) **Sub-grade strength category Code**

**High strength:** characterized by  $K = 150 \text{ MN}/m^3$  and representing all  $K$  values above  $120 \text{ MN}/m^3$  for rigid pavements, and by  $\text{CBR} = 15$  and

A

representing all CBR values above 13 for flexible pavements.

**Medium strength:** characterized by  $K = 80 \text{ MN}/m^3$  and representing a range in  $K$  of 60 to  $120 \text{ MN}/m^3$  for rigid pavements, and by  $\text{CBR} = 10$  and representing a range in CBR of 8 to 13 for flexible pavements

**Low strength:** characterized by  $K = 40 \text{ MN}/m^3$  and representing a range in  $K$  of 25 to  $60 \text{ MN}/m^3$  for rigid pavements, and by  $\text{CBR} = 6$  and representing a range in CBR of 4 to 8 for flexible pavements

**Ultra low strength:** characterized by  $K = 20 \text{ MN}/m^3$  and representing all  $K$  values below  $25 \text{ MN}/m^3$  for rigid pavements, and by  $\text{CBR} = 3$  and representing all CBR values below 4 for flexible pavements

**c) Maximum allowable tire pressure category:**

**Pressure**

Unlimited : no pressure limit

High : pressure limited to 1.75 MPa

Medium: pressure limited to 1.1.25 MPa

Low: pressure limited to 0.50 MPa.

**Code**

W

X

Y

Z

Using aircraft experience: representing a knowledge of the specific type and mass of aircraft satisfactorily being supported under regular use.

U

Note. — The following examples illustrate how pavement strength data are reported under the ACN-PCN method.

Example 1 — If the bearing strength of a rigid pavement, resting on a medium strength sub-grade, has been assessed by technical evaluation to be PCN 80 and there is no tire pressure limitation, then the reported information would be:

PCN 80 / R / B / W / T

Example 2 — If the bearing strength of a composite pavement, behaving like a flexible pavement and resting on a high strength sub-grade, has been assessed by using aircraft experience to be PCN 50 and the maximum tire pressure allowable is 1.25 MPa, then the reported information would be:

PCN 50 / F / A / Y / U

Note. — Composite construction.

Example 3 — If the bearing strength of a flexible pavement, resting on a medium strength sub-grade, has been assessed by technical evaluation to be PCN 40 and the maximum allowable tire pressure is 0.80 MPa, then the reported information would be:

PCN 40 / F / B / 0.80 MPa / T

Note.— See Note 5 to 10.2.1 where the pavement is used by aircraft with tire pressures in the upper categories.

**d) Evaluation method:**

**Technical evaluation:** representing a specific study of the pavement characteristics and application of pavement behaviour technology.

**Code**

T

**Using aircraft experience:** representing a knowledge of the specific type and mass of aircraft satisfactorily being supported under regular use

U

Example 4 — If a pavement is subject to a B747-400 all-up mass limitation of 390,000 kg, then the reported information would include the following note.

Note. — The reported PCN is subject to a B747-400 all-up mass limitation of 390,000 kg.

2.6.7 Criteria should be established to regulate the use of a pavement by an aircraft with a CAN higher than the PCN reported for that pavement in accordance with 2.6.2 and 2.6.3.

Note.— Attachment A, Section 19 details a simple method for regulating overload operations while the ICAO Aerodrome Design Manual, Part 3 includes the descriptions of more detailed procedures for evaluation of pavements and their suitability for restricted overload operations.

**d) Evaluation method**

Technical evaluation: representing a specific study of the pavement characteristics and application of pavement behavior technology.

**Code**

T



CHAPTER 2 - AERODROME DATA

2.6.8 The bearing strength of a pavement intended for aircraft of apron (ramp) mass equal to or less than 5 700 kg shall be made available by reporting the following information:

- a) maximum allowable aircraft mass; and
- b) maximum allowable tire pressure.

Example: 4,000 kg/0.50 MPa

## 2.7 Pre-flight altimeter check location

2.7.1 One or more pre-flight altimeter check locations shall be established for an aerodrome.

2.7.2 A pre-flight check location should be located on an apron.

Note 1.— Locating a pre-flight altimeter check location on an apron enables an altimeter check to be made prior to obtaining taxi clearance and eliminates the need for stopping for that purpose after leaving the apron.

Note 2 — normally an entire apron can serve as a satisfactory altimeter check location.

2.7.3 The elevation of a pre-flight altimeter check location shall be given as the average elevation, rounded to the nearest meter or foot, of the area on which it is located. The elevation of any portion of a pre-flight altimeter check location shall be within 3 m (10 ft) of the average elevation for that location.

## 2.8 Declared distances

The following distances shall be calculated to the nearest meter or foot for a runway intended for use by international commercial air transport:

- a. takeoff run available;
- b. take-off distance available;
- c. accelerate-stop distance available; and
- d. landing distance available.

Note. — Guidance on calculation of declared distances is given in Attachment A, Section 3.

## 2.9 Condition of the movement area and related facilities

2.9.1 Information on the condition of the movement area and the operational status of related facilities shall be provided to the appropriate aeronautical information service units, and similar information of operational significance to the air traffic services units, to enable

those units to provide the necessary information to arriving and departing aircraft. The information shall be kept up to date and changes in conditions reported without delay.

Note.— Nature, format and conditions of the information to be provided are specified in Annex 15 and PANS-ATM (Doc 4444)

2.9.2 The condition of the movement area and the operational status of related facilities shall be monitored and reports on matters of operational significance affecting aircraft, and aerodrome operations shall be provided in order to take appropriate action, particularly in respect of the following:

- a. construction or maintenance work;
- b. rough or broken surfaces on a runway, a taxiway or an apron;
- c. snow, slush, ice or frost on a runway, a taxiway or an apron;
- d. water on a runway, a taxiway or an apron;
- e. snow banks or drifts adjacent to a runway, a taxiway or an apron;
- f. anti-icing or de-icing liquid chemicals or other contaminants on a runway, taxiway or apron;
- g. other temporary hazards, including parked aircraft;
- h. failure or irregular operation of part or all of the aerodrome visual aids; and
- i. failure of the normal or secondary power supply.

**Note 1.**— Other contaminants may include mud, dust, sand, volcanic ash, oil and rubber. Annex 6, Part 1, Attachment C provides guidance on the description of runway surface conditions. Additional guidance is included in the Airport Services Manual (Doc 9137), Part 2.

**Note 2.** — Particular attention would have to be given to the simultaneous presence of snow, slush, ice, wet ice, snow on ice with anti-icing or de-icing liquid chemicals.

**Note 3.** — See 2.9.9 for a list of winter contaminants to be reported.

2.9.3 To facilitate compliance with 2.9.1 and 2.9.2 inspections of the movement area should be carried out each day at least once where the code number is 1 or 2 and at least twice where the code number is 3 or 4.

Note. — Guidance on carrying out daily inspections of the movement area is given in the ICAO Airport Services Manual, Part 8 and in the ICAO Manual of Surface Movement Guidance and Control Systems (SMGCS).

Note.— Guidance on carrying out daily inspections of the movement area is given in the Airport Services Manual (Doc 9137), Part 8 and in the Manual of Surface Movement Guidance and Control Systems (SMGCS) (Doc 9476).

2.9.3A Personnel assessing and reporting runway surface conditions required in 2.9.2 and 2.9.7 should be trained and competent to meet criteria set by the State.

Note.— Guidance on criteria is included in the Airport Services Manual (Doc 9137), Part 8, Chapter 7.

#### **Water on a runway**

2.9.4 Whenever water is present on a runway, a description of the runway surface conditions should be made available using the following terms:

DAMP — the surface shows a change of color due to moisture.

WET — the surface is soaked but there is no standing water.

STANDING WATER — for aeroplane performance purposes, a runway where more than 25 per cent of the runway surface area (whether in isolated areas or not) within the required length and width being used is covered by water more than 3 mm deep

2.9.5 Information that a runway or portion thereof may be slippery when wet shall be made available.

Note. — The determination of a runway or portion thereof may be slippery when wet is not based solely on the friction measurement obtained using a continuous friction measuring device. Supplementary tools to undertake this assessment are described in the Airport Services Manual (Doc 9137), Part 2.

2.9.6 Notification shall be given to aerodrome users when the friction level of a paved runway or portion thereof is less than that specified by the State in accordance with 10.2.3.

Note.— Guidance on conducting a runway surface friction characteristics evaluation programme that includes determining and expressing the minimum friction level is provided in Attachment A, Section 7.

#### **Snow, slush, ice on a runway**

Note 1. — The intent of these specifications is to satisfy the SNOWTAM and NOTAM promulgation requirements

contained in GACA Regulation Section – 15 and ICAO Annex 15.

Note 2 — Runway surface condition sensors may be used to detect and continuously display current or predicted information on surface conditions such as the presence of moisture, or imminent formation of ice on pavements.

2.9.7 Whenever an operational runway is contaminated by snow, slush, ice, the runway shall be assessed, and reported.

Note. — Guidance on assessment of snow- and ice-covered paved surfaces is provided in Attachment A, Section 6.

2.9.7A Runway surface friction measurements made on a runway that is contaminated by slush, wet snow or wet ice should not be reported unless the reliability of the measurement relevant to its operational use can be assured.

Note.—Contaminant drag on the equipment's measuring wheel, amongst other factors, may cause readings obtained in these conditions to be unreliable.

2.9.8 When friction measurements are taken as part of the assessment, the performance of the friction measuring device on compacted snow or ice-covered surfaces should meet the standard and correlation criteria set or agreed by the State.

Note. — *Guidance* on criteria for, and correlation between, friction measuring devices is included in the Airport Services Manual (Doc 9137), Part 2.

2.9.9 Whenever snow, slush, ice or frost is present and reported, the description of the runway surface condition should use the following terms:

DRY SNOW;  
WET SNOW;  
COMPACTED SNOW;  
WET COMPACTED SNOW;  
SLUSH;  
ICE;  
WET ICE;  
FROST;  
DRY SNOW ON ICE;  
WET SNOW ON ICE;  
CHEMICALLY TREATED.  
SANDED.

and should include, where applicable, the assessment of contaminant depth.

### 2.10 Disabled aircraft removal

Note. — See 9.3 for information on disabled aircraft removal services.

2.10.1 The telephone/telex number(s) of the office of the aerodrome coordinator of operations for the removal of an aircraft disabled on or adjacent to the movement area should be made available, on request, to aircraft operators.

2.10.2 Information concerning the capability to remove an aircraft disabled on or adjacent to the movement area should be made available. Note. — The capability to remove a disabled aircraft may be expressed in terms of the largest type of aircraft which the aerodrome is equipped to remove.

### 2.11 Rescue and fire fighting

Note. — See 9.2 for information on rescue and fire fighting services.

2.11.1 Information concerning the level of protection provided at an aerodrome for aircraft rescue and fire fighting purposes shall be made available.

2.11.2 The level of protection normally available at an aerodrome should be expressed in terms of the category of the rescue and fire fighting services as described in 9.2 and in accordance with the types and amounts of extinguishing agents normally available at the aerodrome.

2.11.3 Changes in the level of protection normally available at an aerodrome for rescue and fire fighting shall be notified to the appropriate air traffic services units and aeronautical information units to enable those units to provide the necessary information to arriving and departing aircraft. When such a change has been corrected, the above units shall be advised accordingly.

Note. — Changes in the level of protection from that change in the category of the rescue and fire fighting service from the category normally available at the aerodrome, could result from a change in the availability of extinguishing agents, equipment to deliver the agents or personnel to operate the equipment, etc.

2.11.4 A significant change should be expressed in terms of the new category of the rescue and fire fighting service available at the aerodrome.

### 2.12 Visual approach slope indicator

### systems

The following information concerning a visual approach slope indicator system installation shall be made available:

- associated runway designation number;
- type of system according to 5.3.5.2. For an AT-VASIS, PAPI or APAPI installation, the side of the runway on which the lights are installed, i.e. left or right, shall be given;
- where the axis of the system is not parallel to the runway center line, the angle of displacement and the direction of displacement, i.e. left or right shall be indicated;
- nominal approach slope angle(s). For a T-VASIS or an AT-VASIS this shall be angle  $\theta$  according to the formula in Figure 5-17 and for a PAPI and an APAPI this shall be angle  $(B + C) \div 2$  and  $(A + B) \div 2$ , respectively as in Figure 5-19; and
- minimum eye height(s) over the threshold of the on-slope signal(s). For a T-VASIS or an AT-VASIS this shall be the lowest height at which only the wing bar(s) are visible; however, the additional heights at which the wing bar(s) plus one, two or three fly down light units come into view may also be reported if such information would be of benefit to aircraft using the approach. For a PAPI this shall be the setting angle of the third unit from the runway minus  $2'$ , i.e. angle B minus  $2'$ , and for an APAPI this shall be the setting angle of the unit farther from the runway minus  $2'$ , i.e. angle a minus  $2'$ .

### 2.13 Coordination between aeronautical information services and aerodrome authorities

2.13.1 To ensure that aeronautical information services units obtain information to enable them to provide up-to-date pre-flight information and to meet the need for in-flight information, arrangements shall be made between aeronautical information services and aerodrome authorities responsible for aerodrome services to report to the responsible aeronautical information services unit, with a minimum of delay:

- information on the status of certification of aerodromes and aerodrome conditions (ref. 1.4, 2.9, 2.10, 2.11 and 2.12);
- the operational status of associated facilities, services and navigation aids within their area of responsibility;

- c. any other information considered to be of operational significance.

2.13.2 Before introducing changes to the air navigation system, due account shall be taken by the services responsible for such changes of the time needed by the aeronautical information service for the preparation, production and issue of relevant material for promulgation. To ensure timely provision of the information to the aeronautical information service, close coordination between those services concerned is therefore required.

**Left blank intentionally**

2.13.3 Of a particular importance are changes to aeronautical information that affect charts and/or computer based navigation systems which qualify to be notified by the aeronautical information regulation and control (AIRAC) system, as specified in GACA Regulation Section – 15 and ICAO Annex 15, Chapter 6 and Appendix 4. The predetermined, internationally agreed AIRAC effective dates in addition to 14 days postage time shall be observed by the responsible aerodrome services when submitting the raw information/data to aeronautical information services.

2.13.4 The aerodrome services responsible for the provision of raw aeronautical information/data to the aeronautical information services shall do that while taking into account accuracy and integrity requirements for aeronautical data as specified in Appendix 5 to this Section.

Note 1 — Specifications for the issue of a NOTAM and SNOWTAM are contained in GACA Regulation Section – 15 and ICAO Annex 15, Chapter 5 and Appendices 6 and 2, respectively.

Note 2 — AIRAC information is distributed by the AIS at least 42 days in advance of the AIRAC effective dates with the objective of reaching recipients at least 28 days in advance of the effective date.

Note 3 — The schedule of the predetermined internationally agreed AIRAC common effective dates at intervals of 28 days, including 6 November 1997 and guidance for the AIRAC use are contained in the ICAO Aeronautical Information Services Manual (Doc 8126, Chapter 2).

## CHAPTER 3 - PHYSICAL CHARACTERISTICS

### 3.1 RUNWAYS

#### Number and orientation of runways

Introductory Note.— Many factors affect the determination of the orientation, siting and number of runways.

One important factor is the usability factor, as determined by the wind distribution, which is specified hereunder. Another important factor is the alignment of the runway to facilitate the provision of approaches conforming to the approach surface specifications of Chapter 4. In Attachment A, Section 1, information is given concerning these and other factors.

When a new instrument runway is being located, particular attention needs to be given to areas over which aeroplanes will be required to fly when following instrument approach and missed approach procedures, so as to ensure that obstacles in these areas or other factors will not restrict the operation of the aeroplanes for which the runway is intended.

3.1.1 The number and orientation of runways at an aerodrome should be such that the usability factor of the aerodrome is not less than 95 per cent for the aeroplanes that the aerodrome is intended to serve.

3.1.2 The siting and orientation of runways at an aerodrome should, where possible, be such that the arrival and departure tracks minimize interference with areas approved for residential use and other noise sensitive areas close to the aerodrome in order to avoid future noise problems.

Note.— Guidance on how to address noise problems is provided in the ICAO Airport Planning Manual, Part 2, and in Guidance on the Balanced Approach to Aircraft Noise Management (Doc 9829).

#### 3.1.3 Choice of maximum permissible cross-wind components

In the application of 3.1.1 it should be assumed that landing or take-off of aeroplanes is, in normal circumstances, precluded when the cross-wind component exceeds:

— 37 km/h (20 kt) in the case of aeroplanes whose reference field length is 1 500 m or over, except that when poor runway braking action owing to an insufficient

longitudinal coefficient of friction is experienced with some frequency, a cross-wind component not exceeding 24 km/h (13 kt) should be assumed;

— 24 km/h (13 kt) in the case of aeroplanes whose reference field length is 1 200 m or up to but not including 1 500 m; and

— 19 km/h (10 kt) in the case of aeroplanes whose reference field length is less than 1 200 m.

Note.— In Attachment A, Section 1, guidance is given on factors affecting the calculation of the estimate of the usability factor and allowances which may have to be made to take account of the effect of unusual circumstances.

#### 3.1.4 Data to be used

The selection of data to be used for the calculation of the usability factor should be based on reliable wind distribution statistics that extend over as long a period as possible, preferably of not less than five years. The observations used should be made at least eight times daily and spaced at equal intervals of time.

Note.— These winds are mean winds. Reference to the need for some allowance for gusty conditions is made in Attachment A, Section 1.

#### Location of threshold

3.1.5 A threshold should normally be located at the extremity of a runway unless operational considerations justify the choice of another location.

Note.— Guidance on the siting of the threshold is given in Attachment A, Section 10.

3.1.6 When it is necessary to displace a threshold, either permanently or temporarily, from its normal location, account should be taken of the various factors which may have a bearing on the location of the threshold. Where this displacement is due to an unserviceable runway condition, a cleared and graded area of at least 60 m in length should be available between the unserviceable area and the displaced threshold. Additional distance should also be provided to meet the requirements of the runway end safety area as appropriate.

Note.— Guidance on factors which may be considered in the determination of the location of a displaced threshold is given in Attachment A, Section 10



## **Actual length of runways**

### **3.1.7 Primary runway**

Except as provided in 3.1.9, the actual runway length to be provided for a primary runway should be adequate to meet the operational requirements of the aeroplanes for which the runway is intended and should be not less than the longest length determined by applying the corrections for local conditions to the operations and performance characteristics of the relevant aeroplanes.

Note 1.— This specification does not necessarily mean providing for operations by the critical aeroplane at its maximum mass.

Note 2.— Both take-off and landing requirements need to be considered when determining the length of runway to be provided and the need for operations to be conducted in both directions of the runway.

Note 3.— Local conditions that may need to be considered include elevation, temperature, runway slope, humidity and the runway surface characteristics.

Note 4.— When performance data on aeroplanes for which the runway is intended are not known, guidance on the determination of the actual length of a primary runway by application of general correction factors is given in the ICAO Aerodrome Design Manual, Part 1.

### **3.1.8 Secondary runway**

The length of a secondary runway should be determined similarly to primary runways except that it needs only to be adequate for those aeroplanes which require to use that secondary runway in addition to the other runway or runways in order to obtain a usability factor of at least 95 per cent.

### **3.1.9 Runways with stopways or clearways**

Where a runway is associated with a stopway or clearway, an actual runway length less than that resulting from application of 3.1.7 or 3.1.8, as appropriate, may be considered satisfactory, but in such a case any combination of runway, stopway and clearway provided should permit compliance with the operational requirements for take-off and landing of the aeroplanes the runway is intended to serve.

Note.— Guidance on use of stopways and clearways is given in Attachment A, Section 2.

### **Width of runways**

3.1.10 The width of a runway should be not less than the appropriate dimension specified in the following tabulation:

Code number	Code letter					
	A	B	C	D	E	F
1 <sup>a</sup>	18 m	18 m	23 m	—	—	—
2 <sup>a</sup>	23 m	23 m	30 m	—	—	—
3	30 m	30 m	30 m	45 m	—	—
4	—	—	45 m	45 m	45 m	60 m

- a) The width of a precision approach runway should be not less than 30 m where the code number is 1 or 2.

Note 1.— The combinations of code numbers and letters for which widths are specified have been developed for typical aeroplane characteristics.

Note 2.— Factors affecting runway width are given in the ICAO Aerodrome Design Manual, Part 1.

### **Minimum distance between parallel runways**

3.1.11 Where parallel non-instrument runways are intended for simultaneous use, the minimum distance between their center lines should be:

- 210 m where the higher code number is 3 or 4;
- 150 m where the higher code number is 2; and
- 120 m where the higher code number is 1.

Note.— Procedures for wake turbulence categorization of aircraft and wake turbulence separation minima are contained in the Procedures for Air Navigation Services — Air Traffic Management (PANS-ATM), Doc 4444, Chapter 4, 4.9 and Chapter 5, 5.8, respectively.

3.1.12 Where parallel instrument runways are intended for simultaneous use subject to conditions specified in the PANS-ATM (Doc 4444) and the PANS-OPS (Doc 8168), Volume I, the minimum distance between their center lines should be:

- 1 035 m for independent parallel approaches;
- 915 m for dependent parallel approaches;
- 760 m for independent parallel departures;
- 760 m for segregated parallel operations;

### **Slopes on runways**

#### **3.1.13 Longitudinal slopes**

The slope computed by dividing the difference between the maximum and minimum elevation along the runway center line by the runway length should not exceed:

- 1 per cent where the code number is 3 or 4; and
- 2 per cent where the code number is 1 or 2.

3.1.14 Along no portion of a runway should the longitudinal slope exceed:

- 1.25 per cent where the code number is 4, except that for the first and last quarter of the length of the runway the longitudinal slope should not exceed 0.8 per cent;
- 1.5 per cent where the code number is 3, except that for the first and last quarter of the length of a precision approach runway category II or III the longitudinal slope should not exceed 0.8 per cent; and
- 2 per cent where the code number is 1 or 2.

### 3.1.15 longitudinal slope changes

Where slope changes cannot be avoided, a slope change between two consecutive slopes should not exceed:

- 1.5 per cent where the code number is 3 or 4; and
- 2 per cent where the code number is 1 or 2.

Note.— Guidance on slope changes before a runway is given in Attachment A, Section 4.

3.1.16 The transition from one slope to another should be accomplished by a curved surface with a rate of change not exceeding:

- 0.1 per cent per 30 m (minimum radius of curvature of 30 000 m) where the code number is 4;
- 0.2 per cent per 30 m (minimum radius of curvature of 15 000 m) where the code number is 3; and
- 0.4 per cent per 30 m (minimum radius of curvature of 7 500 m) where the code number is 1 or 2.

### 3.1.17 Sight distance

]

Where slope changes cannot be avoided, they should be such that there will be an unobstructed line of sight from:

- any point 3 m above a runway to all other points 3 m above the runway within a distance of at least half the length of the runway where the code letter is C, D, E or F.
- any point 2 m above a runway to all other points 2 m above the runway within a distance of at least half the length of the runway where the code letter is B; and
- any point 1.5 m above a runway to all other points 1.5 m above the runway within a distance of at least half the length of the runway where the code letter is A.

Note.— Consideration will have to be given to providing an unobstructed line of sight over the entire length of a

single runway where a full-length parallel taxiway is not available.

Where an aerodrome has intersecting runways, additional criteria on the line of sight of the intersection area would need to be considered for operational safety. See the ICAO Aerodrome Design Manual, Part 1.

### 3.1.18 Distance between slope changes

Undulations or appreciable changes in slopes located close together along a runway should be avoided. The distance between the points of intersection of two successive curves should not be less than:

- a) the sum of the absolute numerical values of the corresponding slope changes multiplied by the appropriate value as follows:

- 30 000 m where the code number is 4;
- 15 000 m where the code number is 3; and
- 5 000 m where the code number is 1 or 2; or

- b) 45 m; whichever is greater.

Note.— Guidance on implementing this specification is given in Attachment A, Section 4.

### 3.1.19 Transverse slopes

To promote the most rapid drainage of water, the runway surface should, if practicable, be cambered except where a single crossfall from high to low in the direction of the wind most frequently associated with rain would ensure rapid drainage. The transverse slope should ideally be:

- 1.5 per cent where the code letter is C, D, E or F; and
- 2 per cent where the code letter is A or B;

but in any event should not exceed 1.5 per cent or 2 per cent, as applicable, nor be less than 1 per cent except at runway or taxiway intersections where flatter slopes may be necessary.

For a cambered surface the transverse slope on each side of the center line should be symmetrical.

Note.— On wet runways with cross-wind conditions the problem of aquaplaning from poor drainage is apt to be accentuated. In Attachment A, Section 7, information is given concerning this problem and other relevant factors.

### 3.1.20 The transverse slope

The transverse slope should be substantially the same throughout the length of a runway except at an intersection with another runway or a taxiway where an



even transition should be provided taking account of the need for adequate drainage.

Note.— Guidance on transverse slope is given in the ICAO Aerodrome Design Manual, Part 3.

### Strength of runways

3.1.21 A runway should be capable of withstanding the traffic of aeroplanes the runway is intended to serve.

### Surface of runways

3.1.22 The surface of a runway shall be constructed without irregularities that would impair the runway surface in friction characteristics or otherwise adversely affect the take-off or landing of an aeroplane.

Note 1.— Surface irregularities may adversely affect the take-off or landing of an aeroplane by causing excessive bouncing, pitching, vibration, or other difficulties in the control of an aeroplane.

Note 2. — Guidance on design tolerances and other information is given in Attachment A, Section 5. Additional guidance is included in the ICAO Aerodrome Design Manual, Part 3.

3.1.23 A paved runway shall be so constructed or resurfaced as to provide surface friction characteristics at or above the minimum friction level set by GACA.

3.1.23A The surface of a paved runway should be evaluated when constructed or resurfaced to determine that the surface friction characteristics achieve the design objectives.

**Note.**— Guidance on surface friction characteristics of a new or resurfaced runway is given in Attachment A, Section 7. Additional guidance is included in the Airport Services Manual, Part 2.

3.1.24 Measurements of the surface friction characteristics of a new or resurfaced paved runway should be made with a continuous friction measuring device using self-wetting features.

Note.— Guidance on surface friction characteristics of new runway surfaces is given in Attachment A, Section 7. Additional guidance is included in the ICAO Airport Services Manual (Doc 9137), Part 2.

3.1.25 The average surface texture depth of a new surface should be not less than 1.0 mm.

Note 1.— Macrotexture and microtexture are taken into consideration in order to provide the required surface

friction characteristics Guidance on surface design is given in Attachment A, Section 8

Note 2.— Guidance on methods used to measure surface texture is given in the ICAO Airport Services Manual (Doc 9137), Part 2.

Note 3.— Guidance on design and methods for improving surface texture is given in the Aerodrome design Manual (Doc 9157), Part 3

3.1.26 When the surface is grooved or scored, the grooves or scorings should be either perpendicular to the runway center line or parallel to non perpendicular transverse joints, where applicable.

Note.— Guidance on methods for improving the runway surface texture is given in the Aerodrome Design Manual (Doc 9157), Part 3.

## 3.2 Runway shoulders

### General

Note.— Guidance on characteristics and treatment of runway shoulders is given in Attachment A, Section 8, and in the ICAO Aerodrome Design Manual, Part 1.

3.2.1. Runway shoulders should be provided for a runway where the code letter is D or E, and the runway width is less than 60 m.

3.2.2 Runway shoulders should be provided for a runway where the code letter is F.

### Width of runway shoulders

3.2.3 The runway shoulders should extend symmetrically on each side of the runway so that the overall width of the runway and its shoulders is not less than:

- a) 60 m where the code letter is D or E; and
- b) 75 m where the code letter is F.

### Slopes on runway shoulders

3.2.4 The surface of the shoulder that abuts the runway should be flush with the surface of the runway and its transverse slope should not exceed 2.5 per cent.

### Strength of runway shoulders

3.2.5 A runway shoulder should be prepared or constructed so as to be capable, in the event of an aeroplane running off the runway, of supporting the aeroplane without inducing structural damage to the aeroplane and of supporting ground vehicles which may

operate on the shoulder.

Note. — Guidance on strength of runway shoulders is given in the ICAO Aerodrome Design Manual (Doc 9157), Part 1.

### 3.3 Runway turn pads

3.3.1 Where the end of a runway is not served by a taxiway or a taxiway turnaround and where the code letter is D,E, or F a runway turn pad shall be provided to facilitate a 180-degree turn of aeroplane ( See figure 3-1).

3.3.2 Where the end of a runway is served by a taxiway or a taxiway turnaround and where the code letter is A,B, or C a runway turn pad should be provided to facilitate a 180-degree turn of aeroplane.

Note -1 Such areas may also be useful if provided along a runway to reduce runway taxiing time and distance for aeroplanes which may not require the full length of the runway.

Note -2 Guidance on the design of the runway pads is available in the ICAO Aerodrome Design Manual , Part I Guidance on taxiway turnaround as an alternate facility is available ICAO Aerodrome Design Manual , Part II.

3.3.3 The runway turnaround pad may be located on either the right or left side of the runway and adjoining the runway pavement of both ends of the runway and at some intermediate locations where deemed necessary.

Note – The intention of the turn would be facilitated by locating the turn pad on the left side of the runway, since the left seat is the normal position of pilot in command.

3.3.4 The intersection angel of the runway turn pad with runway should not exceed 30 degrees. :

3.3.5 The nose wheel steering angel to be used in the design of the runway turn pad should not exceed 45 degrees

3.3.6 The design of a runway turn pad shall be such that, when the cockpit of the aeroplane for which the turn pad is intended remains over the turn pad marking , the clearance distance between any wheel of the aeroplane landing gear and the edge of the turn pad shall be not less than that given by the following tabulation :

Code letter	Clearance
A	1.5 m
B	2.25 m
C	3 m if the turn pad is intended to be

used by aeroplanes with a wheel base equal to or greater than 18 m;  
4 m if the turn pad is intended to used by aeroplanes with a wheel base equal to or greater than 18m.

D	4.5 m
E	4.5 m
F	4.5 m

Note Wheel base means the distance from the nose gear to the geometric center of the main gear

3.3.7 Where severe weather conditions and resultant lowering of surface friction characteristics prevail, a larger wheel – to edge clearance of 6 m should be provided where the code letter is E or F.

#### **Slopes on runway turn pads**

3.3.8 The longitudinal and transverse slopes on a runway turn pad should be sufficient to prevent of the accumulation of water on the surface and facilitate rapid drainage of surface water. The slopes should be the same of those adjacent runway pavement surfaces.

3.3.9 The strength of the runway turn pad should be at least equal to that adjoining runway which it serves, due consideration being given to the fact that the turn pad will be subjected slow – moving traffic making hard turns and consequent higher stresses on the pavement.

Note – Where a runway turn pad is provided with flexible pavement, the surface would need to be capable of withstanding the horizontal shear forces exerted by the main gear tires during turning maneuvers.

#### **Surface of runway turn pads**

3.3.10 The surface of a runway turn pad should not have surface irregularities that may cause damage to an aeroplane using the turn pad.

3.3.11 The surface of the turn pads should be so constructed or resurfaced as to provide surface friction characteristics- at least equal to that of the adjoining runway.

#### **Shoulders for runway turn pads**

3.3.12 The runway turn pads should be provided with shoulders of such width as the necessary to prevent surface erosion by the jet blast of the most demanding aeroplane for which the turn pad is intended, and any possible foreign object damage to the aeroplane engines.

3.3.13 The strength of the runway turn pads should be capable of withstanding the occasional passage of the aeroplane it is

designed to serve without inducing structural damage to the aeroplane and to the supporting ground vehicles that may operate on the shoulders.




Figure 3-1. Typical turn pad layout

### 3.4 Runway strips

#### General

3.4.1 A runway and any associated stopways shall be included in a strip.

#### Length of runway strips

3.4.2 A strip shall extend before the threshold and beyond the end of the runway or stopway for a distance of at least:

- a) 60 m where the code number is 2, 3 or 4;
- b) 60 m where the code number is 1 and the runway is non instrument one; and
- c) 30 m where the code number is 1 and the runway is a non-instrument one.

#### Width of runway strips

3.4.3 A strip including a precision approach runway shall, wherever practicable, extend laterally to a distance of at least:

- a) 150 m where the code number is 3 or 4; and
- b) 75 m where the code number is 1 or 2;

on each side of the center line of the runway and its extended center line throughout the length of the strip

3.4.4 A strip including a non-precision approach runway should extend laterally to a distance of at least:

- a) 150 m where the code number is 3 or 4; and
- b) 75 m where the code number is 1 or 2;

on each side of the center line of the runway and its extended center line throughout the length of the strip

3.4.5 A strip including a non-instrument runway should extend on each side of the center line of the runway and its extended center line throughout the length of the strip, to a distance of at least:

- a) 75 m where the code number is 3 or 4;
- b) 40 m where the code number is 2; and
- c) 30 m where the code number is 1

#### Objects on runway strips

Note. — See 9.9 for information regarding siting and construction of equipment and installations on runway strips.

3.4.6 An object situated on a runway strip which may endanger aeroplanes should be regarded as an obstacle and should, as far as practicable, be removed.

3.4.7 No fixed object, other than visual aids required for air navigation or those required for aircraft safety purposes and which must be sited on the runway strip, and satisfying the relevant frangibility requirement in Chapter 5, shall be permitted on a runway strip:

- a) within 77.5 m of the runway center line of a precision approach runway category I, II or III where the code number is 4 and the code letter is F; or
- b) within 60 m of the runway center line of a precision approach runway category I, II or III where the code number is 3 or 4; or
- c) within 45 m of the runway center line of a precision approach runway category I where the code number is 1 or 2.

No mobile object shall be permitted on this part of the runway strip during the use of the runway for landing or take-off.

#### Grading of runway strips

3.4.8 That portion of a strip of an instrument runway within a distance of at least:

- a) 75 m where the code number is 3 or 4; and
- b) 40 m where the code number is 1 or 2;

from the center line of the runway and its extended center line should provide a graded area for aeroplanes which the runway is intended to serve in the event of an aeroplane running off the runway.

Note. — Guidance on grading of a greater area of a strip including a precision approach runway where the code number is 3 or 4 is given in Attachment A, Section 8.

3.4.9 That portion of a strip of a non-instrument runway within a distance of at least:

- a) 75 m where the code number is 3 or 4;
- b) 40 m where the code number is 2; and
- c) 30 m where the code number is 1;

from the center line of the runway and its extended center line should provide a graded area for aeroplanes which

the runway is intended to serve in the event of an aeroplane running off the runway.

3.4.10 The surface of that portion of a strip that abuts a runway, shoulder or stopway shall be flush with the surface of the runway, shoulder or stopway.

3.4.11 That portion of a strip to at least 30 m before a threshold should be prepared against blast erosion in order to protect a landing aeroplane from the danger of an exposed edge.

3.4.12 Where the areas in 3.4.11 have paved surfaces, they should be able to withstand the occasional passage of the critical aeroplane for runway pavement design.

Note. — The area adjacent to the end of a runway may be referred to as a blast pad.

#### Slopes on runway strips

##### 3.4.13 Longitudinal slopes

A longitudinal slope along that portion of a strip to be graded should not exceed:

- a) 1.5 per cent where the code number is 4;
- b) 1.75 per cent where the code number is 3; and
- c) 2 per cent where the code number is 1 or 2.

##### 3.4.14 Slope changes

Slope changes on that portion of a strip to be graded should be as gradual as practicable and abrupt changes or sudden reversals of longitudinal slopes avoided.

##### 3.4.15 Transverse slopes

Transverse slopes on that portion of a strip to be graded should be adequate to prevent the accumulation of water on the surface but should not exceed:

- a) 2.5 per cent where the code number is 3 or 4; and
- b) 3 per cent where the code number is 1 or 2;

except that to facilitate drainage the slope for the first 3 m outward from the runway, shoulder or stopway edge should be negative as measured in the direction away from the runway and may be as great as 5 per cent.

3.4.16 The transverse slopes of any portion of a strip beyond that to be graded should not exceed an upward

slope of 5 per cent as measured in the direction away from the runway.

#### **Strength of runway strips**

3.4.17 That portion of a strip of an instrument runway within a distance of at least:

- a) 75 m where the code number is 3 or 4; and
- b) 40 m where the code number is 1 or 2;

from the center line of the runway and its extended center line should be so prepared or constructed as to minimize hazards arising from differences in load bearing capacity to aeroplanes which the runway is intended to serve in the event of an aeroplane running off the runway.

Note. — Guidance on preparation of runway strips is given in the ICAO Aerodrome Design Manual, Part 1.

3.4.18 That portion of a strip containing a non-instrument runway within a distance of at least:

- a) 75 m where the code number is 3 or 4;
- b) 40 m where the code number is 2; and
- c) 30 m where the code number is 1;

from the center line of the runway and its extended center line should be so prepared or constructed as to minimize hazards arising from differences in load bearing capacity to aeroplanes which the runway is intended to serve in the event of an aeroplane running off the runway.

### **3.5 Runway end safety areas**

#### **General**

3.5.1 A runway end safety area shall be provided at each end of a runway strip where:

- the code number is 3 or 4; and
- the code number is 1 or 2 and the runway is an instrument one.

Note. — Guidance on runway end safety areas is given in Attachment A, Section 10.

3.5.2 A runway end safety area should be provided at each end of a runway strip where the code number is 1 or 2 and the runway is a non-instrument one.

#### **Dimensions of runway end safety areas**

3.5.3 A runway end safety area should, as far as practicable, extend from the end of a runway strip to a

distance of at least 90 m where:

- the code number is 3 or 4; and
- the code number is 1 or 2 and the runway is an instrument one.

If an arresting system is installed, the above length may be reduced, based on the design specification of the system, subject to acceptance by the State.

Note. — Guidance on arresting systems is given in Attachment A, Section 10.

3.5.4 The width of a runway end safety area shall be at least twice that of the associated runway.

- a) 240 m where the code number is 3 or 4; and the runway is an instrument one; or a reduced length when an arresting system is installed
- b) 120 m where the code number is 1 or 2 or a reduced length when an arresting system is installed; and ;
- c) 30 m where the code number is 1 or 2 and the runway is a non-instrument one.

3.5.5 The width of a runway end safety area should, wherever practicable, be equal to that of the graded portion of the associated runway strip.

3.5.6 The width of a runway end safety area should, wherever practicable, be equal to that of the graded portion of the associated runway strip.

#### **Objects on runway end safety areas**

Note. — See 9.9 for information regarding siting and construction of equipment and installations on runway end safety areas.

3.5.7 An object situated on a runway end safety area which may endanger aeroplanes should be regarded as an obstacle and should, as far as practicable, be removed.

#### **Clearing and grading of runway end safety areas**

3.5.8 A runway end safety area should provide a cleared and graded area for aeroplane which the runway is intended to serve in the event of an aeroplane undershooting or overrunning the runway.

Note. — The surface of the ground in the runway end safety area does not need to be prepared to the same quality as the runway strip. See, however, 3.4.11.

#### **Slopes on runway end safety areas**



### 3.5.9 General

The slopes of a runway end safety area should be such that no part of the runway end safety area penetrates the approach or take-off climb surface.

### 3.5.10 Longitudinal slopes

The longitudinal slopes of a runway end safety area should not exceed a downward slope of 5 per cent. Longitudinal slope changes should be as gradual as practicable and abrupt changes or sudden reversals of slopes avoided.

### 3.5.11 Transverse slopes

The transverse slopes of a runway end safety area should not exceed an upward or downward slope of 5 per cent. Transitions between differing slopes should be as gradual as practicable.

### Strength of runway end safety areas

3.5.12 A runway end safety area should be so prepared or constructed as to reduce the risk of damage to an aeroplane undershooting or overrunning the runway, enhance aeroplane deceleration and facilitate the movement of rescue and fire fighting vehicles as required in 9.2.26 to 9.2.28.

Note. — Guidance on strength of a runway end safety area is given in the ICAO Aerodrome Design Manual, Part 1.

## 3.6 Clearways

Note. — The inclusion of detailed specifications for clearways in this section is not intended to imply that a clearway has to be provided. Attachment A, Section 2 provides information on the use of clearways.

### Location of clearways

3.6.1 The origin of a clearway should be at the end of the take-off run available.

3.6.2 The length of a clearway should not exceed half the length of the take-off run available.

### Width of clearways

3.6.3 A clearway should extend laterally to a distance of at least 75 m on each side of the extended center line of the runway.

### Slopes on clearways

3.6.4 The ground in a clearway should not project above a plane having an upward slope of 1.25 per cent, the lower limit of this plane being a horizontal line which:

- is perpendicular to the vertical plane containing the runway center line; and
- passes through a point located on the runway center line at the end of the take-off run available.

Note. — Because of transverse or longitudinal slopes on a runway, shoulder or strip, in certain cases the lower limit of the clearway plane specified above may be below the corresponding elevation of the runway, shoulder or strip. It is not intended that these surfaces be graded to conform with the lower limit of the clearway plane nor is it intended that terrain or objects which are above the clearway plane beyond the end of the strip but below the level of the strip be removed unless it is considered they may endanger aeroplanes.

3.6.5 Abrupt upward changes in slope should be avoided when the slope on the ground in a clearway is relatively small or when the mean slope is upward. In such situations, in that portion of the clearway within a distance of 22.5 m or half the runway width whichever is greater on each side of the extended center line, the slopes, slope changes and the transition from runway to clearway should generally conform to those of the runway with which the clearway is associated.

### Objects on clearways

Note. — See 9.9 for information regarding siting and construction of equipment and installations on clearways.

3.6.6 An object situated on a clearway which may endanger aeroplanes in the air should be regarded as an obstacle and should be removed.

## 3.7 Stopways

Note. — The inclusion of detailed specifications for stopways in this section is not intended to imply that a stopway has to be provided. Attachment A, Section 2 provides information on the use of stopways.

### Width of stopways

3.7.1 A stopway shall have the same width as the runway with which it is associated.

### Slopes on stopways

3.7.2 Slopes and changes in slope on a stopway, and the



transition from a runway to a stopway, should comply with the specifications of 3.1.12 to 3.1.18 for the runway with which the stopway is associated except that:

- a) the limitation in 3.1.13 of a 0.8 per cent slope for the first and last quarter of the length of a runway need not be applied to the stopway; and
- b) at the junction of the stopway and runway and along the stopway the maximum rate of slope change may be 0.3 per cent per 30 m (minimum radius of curvature of 10,000 m) for a runway where the code number is 3 or 4.

### **Strength of stopways**

3.7.3 A stopway should be prepared or constructed so as to be capable, in the event of an abandoned take-off, of supporting the aeroplane which the stopway is intended to serve without inducing structural damage to the aeroplane.

Note. — Attachment A, Section 2 presents guidance relative to the support capability of a stopway.

### **Surface of stopways**

3.7.4 The surface of a paved stopway shall be so constructed or resurfaced as to provide surface friction characteristics at or above those of the associated runway.

## **3.8 Radio altimeter operating area**

### **General**

3.8.1 A radio altimeter operating area should be established in the pre-threshold area of a precision approach runway.

### **Length of the area**

3.8.2 A radio altimeter operating area should extend before the threshold for a distance of at least 300 m.

### **Width of the area**

3.8.3 A radio altimeter operating area should extend laterally, on each side of the extended center line of the runway, to a distance of 60 m, except that, when special circumstances so warrant, the distance may be reduced to no less than 30 m if an aeronautical study indicates that such reduction would not affect the safety of operations of aircraft.

### **Longitudinal slope changes**

3.8.4 On a radio altimeter operating area, slope changes should be avoided or kept to a minimum. Where slope changes cannot be avoided, the slope changes should be as gradual as practicable and abrupt changes or sudden reversals of slopes avoided. The rate of change between two consecutive slopes should not exceed 2 per cent per 30 m.

Note.— Guidance on radio altimeter operating area is given in Attachment A, Section 4.3 and in the ICAO Manual of All- Weather Operations, (Doc 9365), Section 5.2. Guidance on the use of radio altimeter is given in the PANS-OPS, Volume II, Part III, Chapter 21.

## **3.9 Taxiways**

Note. — Unless otherwise indicated the requirements in this section are applicable to all types of taxiways.

### **General**

3.9.1 Taxiways should be provided to permit the safe and expeditious surface movement of aircraft.

Note. — Guidance on layout of taxiways is given in the ICAO Aerodrome Design Manual, Part 2.

3.9.2 Sufficient entrance and exit taxiways for a runway should be provided to expedite the movement of aeroplanes to and from the runway and provision of rapid exit taxiways considered when traffic volumes are high.

Note. — Where the end of a runway is not served by a taxiway, it may be necessary to provide additional pavement at the end of the runway for the turning of aeroplanes. Such areas may also be useful along the runway to reduce taxiing time and distance for some aeroplanes.

3.9.3 The design of a taxiway should be such that, when the cockpit of the aeroplane for which the taxiway is intended remains over the taxiway center line markings, the clearance distance between the outer main wheel of the aeroplane and the edge of the taxiway should be not less than that given by the following tabulation:

Code letter	Clearance
A	1.5 m
B	2.25 m
C	3 m if the taxiway is intended to be used by aeroplanes with a wheel base less than 18 m; 4.5 m if the taxiway is intended to be used by aeroplanes with a wheel base equal to or greater than 18 m.

D	4.5 m
E	4.5 m
F	4.5 m

Note 1 — Wheel base means the distance from the nose gear to the geometric center of the main gear.

Note 2 — Where the code letter is F and the traffic density is high, a wheel-to-edge clearance greater than 4.5 m may be provided to permit higher taxiing speeds.

3.9.4 As of 20 November 2008, the design of a taxiway shall be such that, when the cockpit of the aeroplane for which the taxiway is intended remains over the taxiway center line markings, the clearance distance between the outer main wheel of the aeroplane and the edge of the taxiway shall be not less than that given by the following tabulation:

Code letter	Clearance
A	1.5 m
B	2.25 m
C	3 m if the taxiway is intended to be used by aeroplanes with a wheel base less than 18 m; 4.5 m if the taxiway is intended to be used by aeroplanes with a wheel base equal to or greater than 18 m.
D	4.5 m
E	4.5 m
F	4.5 m

Note 1.— Wheel base means the distance from the nose gear to the geometric center of the main gear.

Note 2.— Where the code letter is F and the traffic density is high, a wheel-to-edge clearance greater than 4.5 m may be provided to permit higher taxiing speeds.

Note 3.— This provision applies to taxiways first put into service on or after 20 November 2008.

#### **Width of taxiways**

3.9.5 A straight portion of a taxiway should have a width of not less than that given by the following tabulation:

Code letter	Taxiway width
A	7.5 m
B	10.5 m
C	15 m if the taxiway is intended to be used by aeroplanes with a wheel base less than 18 m;

D	18 m if the taxiway is intended to be used by aeroplanes with a wheel base equal to or greater than 18 m 18 m if the taxiway is intended to be used by aeroplanes with an outer main gear wheel span of less than 9 m; 23 m if the taxiway is intended to be used by aeroplanes with an outer main gear wheel span equal to or greater than 9 m
E	23 m
F	25 m

Note. — Guidance on width of taxiways is given in the ICAO Aerodrome Design Manual (Doc 9157), Part 2.

#### **Taxiway curves**

3.9.6 Changes in direction of taxiways should be as few and small as possible. The radii of the curves should be compatible with the maneuvering capability and normal taxiing speeds of the aeroplanes for which the taxiway is intended. The design of the curve should be such that, when the cockpit of the aeroplane remains over the taxiway center line markings, the clearance distance between the outer main wheels of the aeroplane and the edge of the taxiway should not be less than those specified in 3.9.3.

Note 1.— An example of widening taxiways to achieve the wheel clearance specified is illustrated in Figure 3-2. Guidance on the values of suitable dimensions is given in the Aerodrome Design Manual (Doc 9157), Part 2.

Note 2.— The location of taxiway center line markings and lights is specified in 5.2.8.4 and 5.3.16.11.

Note 3.— Compound curves may reduce or eliminate the need for extra taxiway width.

#### **Junctions and intersections**

3.9.7 To facilitate the movement of aeroplanes, fillets should be provided at junctions and intersections of taxiways with runways, aprons and other taxiways. The design of the fillets should ensure that the minimum wheel clearances specified in 3.9.3 are maintained when aeroplanes are maneuvering through the junctions or intersections.

Note.— Consideration will have to be given to the aeroplane datum length when designing fillets. Guidance on the design of fillets and the definition of the term

airplane datum length are given in the ICAO Aerodrome Design Manual (Doc 9157), Part 2.

### **Taxiway minimum separation distances**

3.9.8 The separation distance between the center line of a taxiway and the center line of a runway, the center line of a parallel taxiway or an object should not be less than the appropriate dimension specified in Table 3-1, except that it may be permissible to operate with lower separation distances at an existing aerodrome if an aeronautical study indicates that such lower separation distances would not adversely affect the safety or significantly affect the regularity of operations of aeroplanes.

Note 1.— Guidance on factors which may be considered in the aeronautical study is given in the ICAO Aerodrome Design Manual, Part 2.

Note 2.— ILS and MLS installations may also influence the location of taxiways due to interferences to ILS and MLS signals by a taxiing or stopped aircraft. Information on critical and sensitive areas surrounding ILS and MLS installations is contained in GACA Regulation Section 10 and ICAO Annex 10, Volume I, Attachments C and G (respectively).

Note 3.— The separation distances of Table 3-1, column 10, do not necessarily provide the capability of making a normal turn from one taxiway to another parallel taxiway. Guidance for this condition is given in the ICAO Aerodrome Design Manual, Part 2.

Note 4.— The separation distance between the center line of an aircraft stand taxiway and an object shown in Table 3-1, column 12, may need to be increased when jet exhaust wake velocity may cause hazardous conditions for ground servicing.

### **Slopes on taxiways**

#### **3.9.9 Longitudinal slopes**

The longitudinal slope of a taxiway should not exceed:

- a) 1.5 per cent where the code letter is C, D, E or F; and
- b) 3 per cent where the code letter is A or B.

#### **3.9.10 Longitudinal slope changes**

Where slope changes on a taxiway cannot be avoided, the transition from one slope to another slope should be accomplished by a curved surface with a rate of change not exceeding:

- a) 1 per cent per 30 m (minimum radius of curvature of 3,000 m) where the code letter is C, D, E or F; and
- b) 1 per cent per 25 m (minimum radius of curvature of 2 500 m) where the code letter is A or B.

#### **3.9.11 Sight distance**

Where a change in slope on a taxiway cannot be avoided, the change should be such that, from any point:

- 3 m above the taxiway, it will be possible to see the whole surface of the taxiway for a distance of at least 300 m from that point, where the code letter is C, D, E or F;
- 2 m above the taxiway, it will be possible to see the whole surface of the taxiway for a distance of at least 200 m from that point, where the code letter is B; and
- 1.5 m above the taxiway, it will be possible to see the whole surface of the taxiway for a distance of at least 150 m from that point, where the code letter is A.

#### **3.9.12 Transverse slopes**

The transverse slopes of a taxiway should be sufficient to prevent the accumulation of water on the surface of the taxiway but should not exceed:

- a) 1.5 per cent where the code letter is C, D, E or F; and
- b) -2 per cent where the code letter is A or B.

Note. — See 3.12.4 regarding transverse slopes on an aircraft stand taxiway.

#### **Strength of taxiways**

3.9.13 The strength of a taxiway should be at least equal to that of the runway it serves, due consideration being given to the fact that a taxiway will be subjected to a greater density of traffic and, as a result of slow moving and stationary aeroplanes, to higher stresses than the runway it serves.

Note. — Guidance on the relation of the strength of taxiways to the strength of runways is given in the ICAO Aerodrome Design Manual, Part 3.

#### **Surface of taxiways**

3.9.14 The surface of a taxiway should not have irregularities that cause damage to aeroplane structures.

3.9.15 The surface of a paved taxiway should be so

constructed or resurfaced as to provide suitable surface friction characteristics.

Note. — Suitable surface friction characteristics are those surface properties required on taxiways that assure safe operation of aeroplanes.

### Rapid exit taxiways

Note. — The following specifications detail requirements particular to rapid exit taxiways. See Figure 3-2. General requirements for taxiways also apply to this type of taxiway. Guidance on the provision, location and design of rapid exit taxiways is included in the ICAO Aerodrome Design Manual, Part 2.

3.9.16 A rapid exit taxiway should be designed with a radius of turn-off curve of at least:

- 550 m where the code number is 3 or 4; and
- 275 m where the code number is 1 or 2; to enable exit speeds under wet conditions of:
- 93 km/h where the code number is 3 or 4; and
- 65 km/h where the code number is 1 or 2

Note. — The locations of rapid exit taxiways along a runway are based on several criteria described in the

ICAO Aerodrome Design Manual, Part 2, in addition to different speed criteria.

3.9.17 The radius of the fillet on the inside of the curve at a rapid exit taxiway should be sufficient to provide a widened taxiway throat in order to facilitate early recognition of the entrance and turn-off onto the taxiway.

3.8.18 A rapid exit taxiway should include a straight distance after the turn-off curve sufficient for an exiting aircraft to come to a full stop clear of any intersecting taxiway.

3.9.19 The intersection angle of a rapid exit taxiway with the runway should not be greater than 45° nor less than 25° and preferably should be 30°




Figure 3-2. Taxiway curve

**GACA REGULATIONS - SECTION 14 - AERODROMES  
VOLUME I – AERODROME DESIGN AND OPERATIONS**


**CHAPTER 2 - AERODROME DATA**

Table 3-1. Taxiway minimum separation distances


Code letter	Distance between taxiway centre line and runway centre line (metres)								Taxiway centre line to taxiway centre line (metres)	Taxiway, other than aircraft stand taxilane, centre line to object (metres)	Aircraft stand taxilane centre line to object (metres)
	Instrument runways				Non-instrument runways						
	Code number				Code number						
	1	2	3	4	1	2	3	4			
(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)	(10)	(11)	(12)
A	82.5	82.5	—	—	37.5	47.5	—	—	23.75	16.25	12
B	87	87	—	—	42	52	—	—	33.5	21.5	16.5
C	—	—	168	—	—	—	93	—	44	26	24.5
D	—	—	176	176	—	—	101	101	66.5	40.5	36
E	—	—	—	182.5	—	—	—	107.5	80	47.5	42.5
F	—	—	—	190	—	—	—	115	97.5	57.5	50.5

*Note 1.— The separation distances shown in columns (2) to (9) represent ordinary combinations of runways and taxiways. The basis for development of these distances is given in the Aerodrome Design Manual, Part 2.*

*Note 2.— The distances in columns (2) to (9) do not guarantee sufficient clearance behind a holding aeroplane to permit the passing of another aeroplane on a parallel taxiway. See the Aerodrome Design Manual, Part 2.*



## CHAPTER 3 - PHYSICAL CHARACTERISTICS



**Figure 3-3. Rapid Exit Taxiway**



### **Taxiways on bridges**

3.9.20 The width of that portion of a taxiway bridge capable of supporting aeroplanes, as measured perpendicularly to the taxiway center line, shall not be less than the width of the graded area of the strip provided for that taxiway, unless a proven method of lateral restraint is provided which shall not be hazardous for aeroplanes for which the taxiway is intended.

3.9.21 Access should be provided to allow rescue and fire fighting vehicles to intervene in both directions within the specified response time to the largest aeroplane for which the taxiway bridge is intended.

Note. — If aeroplane engines overhang the bridge structure, protection of adjacent areas below the bridge from engine blast may be required.

3.9.22 A bridge should be constructed on a straight section of the taxiway with a straight section on both ends of the bridge to facilitate the alignment of aeroplanes approaching the bridge.

### **3.10 Taxiway shoulders**

Note. — Guidance on characteristics of taxiway shoulders and on shoulder treatment is given in the ICAO Aerodrome Design Manual, Part 2.

3.10.1 Straight portions of a taxiway where the code letter is C, D, E or F should be provided with shoulders which extend symmetrically on each side of the taxiway so that the overall width of the taxiway and its shoulders on straight portions is not less than:

- a) 60 m where the code letter is F;
- b) 44 m where the code letter is E;
- c) 38 m where the code letter is D; and
- d) 25 m where the code letter is C

On taxiway curves and on junctions or intersections where increased pavement is provided, the shoulder width should be not less than that on the adjacent straight portions of the taxiway.

3.10.2 When a taxiway is intended to be used by turbine-engined aeroplanes, the surface of the taxiway shoulder should be so prepared as to resist erosion and the ingestion of the surface material by aeroplane engines.

### **3.11 Taxiway strips**

Note. — Guidance on characteristics of taxiway strips is given in the ICAO Aerodrome Design Manual, Part 2.

#### **General**

3.11.1 A taxiway, other than an aircraft stand taxilane, shall be included in a strip.

#### **Width of taxiway strips**

3.11.2 A taxiway strip should extend symmetrically on each side of the center line of the taxiway throughout the length of the taxiway to at least the distance from the center line given in Table 3-1, column 11.

#### **Objects on taxiway strips**

Note. — See 9.9 for information regarding siting and construction of equipment and installations on taxiway strips.

3.11.3 The taxiway strip should provide an area clear of objects which may endanger taxiing aeroplanes.

Note. — Consideration will have to be given to the location and design of drains on a taxiway strip to prevent damage to an aeroplane accidentally running off a taxiway. Suitably designed drain covers may be required.

#### **Grading of taxiway strips**

3.11.4 The center portion of a taxiway strip should provide a graded area to a distance from the center line of the taxiway of at least:

- a) 11 m where the code letter is A;
- b) 12.5 m where the code letter is B or C;
- c) 19 m where the code letter is D;
- d) 22 m where the code letter is E; and
- e) 30 m where the code letter is F.

#### **Slopes on taxiway strips**

3.11.5 The surface of the strip should be flush at the edge of the taxiway or shoulder, if provided, and the graded portion should not have an upward transverse slope exceeding:

- a) 2.5 per cent for strips where the code letter is C, D, E or F; and
- b) 3 per cent for strips of taxiways where the code letter is A or B;

the upward slope being measured with reference to the transverse slope of the adjacent taxiway surface and not the horizontal. The downward transverse slope should not exceed 5 per cent measured with reference to the horizontal.

3.11.6 The transverse slopes on any portion of a taxiway strip beyond that to be graded should not exceed an

upward or downward slope of 5 per cent as measured in the direction away from the taxiway.

**3.12 Holding bays, runway-holding positions, intermediate holding positions and road-holding positions**

**General**

3.12.1 Holding bay(s) should be provided when the traffic density is medium or heavy.

3.12.2 A runway-holding position or positions shall be established:

- a) on the taxiway, at the intersection of a taxiway and a runway; and
- b) at an intersection of a runway with another runway when the former runway is part of a standard taxi-route.

3.12.3 A runway-holding position shall be established on a taxiway if the location or alignment of the taxiway is such that a taxiing aircraft or vehicle can infringe an obstacle limitation surface or interfere with the operation of radio navigation aids.

3.12.4 An intermediate holding position should be established on a taxiway at any point other than a runway-holding position where it is desirable to define a specific holding limit.

3.12.5 A road-holding position shall be established at an intersection of a road with a runway.

**Location**

3.12.6 The distance between a holding bay, runway-holding position established at a taxiway/runway intersection or road-holding position and the center line of a runway shall be in accordance with Table 3-2 and, in the case of a precision approach runway, such that a holding aircraft or vehicle will not interfere with the operation of radio navigation aids.

3.12.7 At elevations greater than 700 m (2 300 ft) the distance of 90 m specified in Table 3-2 for a precision approach runway code number 4 should be increased as follows:

- a) up to an elevation of 2,000 m (6,600 ft); 1 m for every 100 m (330 ft) in excess of 700 m (2,300 ft);
- b) elevation in excess of 2,000 m (6,600 ft) and up to 4,000 m (13,320 ft); 13 m plus 1.5 m for every 100 m (330 ft) in excess of 2,000 m (6,600 ft); and
- c) elevation in excess of 4,000 m (13,320 ft) and up to 5,000 m (16,650 ft); 43 m plus 2 m for every 100 m (330 ft) in excess of 4,000 m (13,320 ft).

3.12.8 If a holding bay, runway holding position or road-holding position for a precision approach runway code number 4 is at a greater elevation compared to the threshold, the distance of 90 m or 107.5 m, as appropriate, specified in Table 3-2 should be further increased 5 m for every meter the bay or position is higher than the threshold.

3.12.9 The location of a runway-holding position established in accordance with 3.12.3 shall be such that a holding aircraft or vehicle will not infringe the obstacle free zone, approach surface, take-off climb surface or ILS/MLS critical/sensitive area or interfere with the operation of radio navigation aids.

**Left blank intentionally**

**GACA REGULATIONS - SECTION 14 - AERODROMES  
VOLUME I – AERODROME DESIGN AND OPERATIONS**

**CHAPTER 3 - PHYSICAL CHARACTERISTICS**

Table 3-2. Minimum distance from the runway centre line  
to a holding bay, runway-holding position or road-holding position

Type of runway	Code number			
	1	2	3	4
Non-instrument	30 m	40 m	75 m	75 m
Non-precision approach	40 m	40 m	75 m	75 m
Precision approach category I	60 m <sup>b</sup>	60 m <sup>b</sup>	90 m <sup>a,b</sup>	90 m <sup>a,b,c</sup>
Precision approach categories II and III	–	–	90 m <sup>a,b</sup>	90 m <sup>a,b,c</sup>
Take-off runway	30 m	40 m	75 m	75 m


- a. If a holding bay, runway-holding position or road-holding position is at a lower elevation compared to the threshold, the distance may be decreased 5 m for every metre the bay or holding position is lower than the threshold, contingent upon not infringing the inner transitional surface.
- b. This distance may need to be increased to avoid interference with radio navigation aids, particularly the glide path and localizer facilities. Information on critical and sensitive areas of ILS and MLS is contained in Annex 10, Volume I, Attachments C and G, respectively (see also 3.12.6).

*Note 1.— The distance of 90 m for code number 3 or 4 is based on an aircraft with a tail height of 20 m, a distance from the nose to the highest part of the tail of 52.7 m and a nose height of 10 m holding at an angle of 45° or more with respect to the runway centre line, being clear of the obstacle free zone and not accountable for the calculation of OCA/H.*

*Note 2.— The distance of 60 m for code number 2 is based on an aircraft with a tail height of 8 m, a distance from the nose to the highest part of the tail of 24.6 m and a nose height of 5.2 m holding at an angle of 45° or more with respect to the runway centre line, being clear of the obstacle free zone.*

- c. Where the code letter is F, this distance should be 107.5 m.

*Note.— The distance of 107.5 m for code number 4 where the code letter is F is based on an aircraft with a tail height of 24 m, a distance from the nose to the highest part of the tail of 62.2 m and a nose height of 10 m holding at an angle of 45° or more with respect to the runway centre line, being clear of the obstacle free zone.*



### 3.13 Aprons

#### General

3.13.1 Aprons should be provided where necessary to permit the on- and off-loading of passengers, cargo or mail as well as the servicing of aircraft without interfering with the aerodrome traffic.

#### Size of aprons

3.13.2 The total apron area should be adequate to permit expeditious handling of the aerodrome traffic at its maximum anticipated density.

#### Strength of aprons

3.13.3 Each part of an apron should be capable of withstanding the traffic of the aircraft it is intended to serve, due consideration being given to the fact that some portions of the apron will be subjected to a higher density of traffic and, as a result of slow moving or stationary aircraft, to higher stresses than a runway.

#### Slopes on aprons

3.13.4 Slopes on an apron, including those on an aircraft stand taxilane, should be sufficient to prevent accumulation of water on the surface of the apron but should be kept as level as drainage requirements permit.

3.13.5 On an aircraft stand the maximum slope should not exceed 1 per cent.

#### Clearance distances on aircraft stands

3.13.6 An aircraft stand should provide the following minimum clearances between an aircraft using the stand and any adjacent building, aircraft on another stand and other objects:

Code letter	Clearance
A	3 m
B	3 m
C	4.5 m
D	7.5 m
E	7.5 m
F	7.5 m

When special circumstances so warrant, these clearances may be reduced at a nose –in aircraft stand, where the code letter is D, E, or F:

- a) between the terminal, including the any fixed passenger bridge, and the nose of an aircraft.

- b) Over any portion of the stand provided with azimuth guidance by a visual docking guidance system.

Note – On aprons, consideration also has to be given to the provision of service roads and to maneuvering and storage area for ground equipment ( see the ICAO Aerodrome Design Manual Part 2, for guidance on storage of ground equipment).

### 3.14 Isolated aircraft parking positions

3.14.1 An isolated aircraft parking position shall be designated or the aerodrome control tower shall be advised of an area or areas suitable for the parking of an aircraft which is known or believed to be the subject of unlawful interference, or which for other reasons needs isolation from normal aerodrome activities.

3.14.2 The isolated aircraft position should be located at the maximum distance practicable and any case never less than 100 m from other parking positions, buildings or public areas, etc. Care should be taken to ensure that the position is not located over underground utilities such as gas and aviation fuel and, to the extent feasible, electrical or communication cables.

### 3.15 De-icing / anti- icing facilities

Note – Safe and efficient aeroplane operations are of primary importance in the development of an aeroplane de-icing/ anti-icing facilities. For further guidance, see the ICAO Manual on Aircraft Ground De-icing/anti- icing Operations ( Doc 9640).

#### General

3.15.1 Aeroplane de-icing /anti-icing facilities should be provided at an aeroplane where icing conditions are expected to occur.

3.15.2 De-icing/anti-icing facilities should be provided either at aircraft stands or at specific stands or at specified remote areas along the taxiway leading to the runway meant for take-off, provided that adequate drainage arrangements for the collection and safe disposal of excess de-icing/ anti-icing fluids are available to prevent ground water contamination. The effect of volume of traffic and departure flow rates should also be considered.

Note – 1 One of the primary factors influencing location of de-icing/anti- icing facility is to ensure that the holdover time of the anti-icing treatment is still in effect at the end of taxiing and when take-off clearance of the treated aeroplane is given.

Note – 2 Remote facilities component for changing weather conditions when icing conditions or blowing snow are expected to occur along taxi route taken by the aeroplane to the runway ment for takeoff

3.15.3 The remote de-icing/anti-icing facility should be located to be clear of the obstacle limitation surface specified in chapter 4, not cause interference to radio navigation aids and to be clearly visible from the air traffic control tower for clearing the treated aeroplane

3.15.4 The remote de-icing/anti-icing facility should be so located as to provide for the expeditious traffic flow, perhaps with a bypass configuration, and not require unusual taxiing maneuvering into out of the pads.

Note – The jet blasts effects caused by a moving aeroplane on other aeroplane receiving the anti-icing treatment or taxiing behind will have to be taken into account to prevent degradation of the treatment.

#### Size and number of de-icing/anti-icing pads

Note – An aeroplane de-icing/anti-icing pad consist of

- a) An inner area for parking of an aeroplane to be treated, and
- b) An outer area for movement of two or more mobile de-icing/ anti-icing equipment.

3.15.5 The size of a de-icing/ anti-icing pad should be equal to the parking area required by the most demanding aeroplane in a given category with at least 3.8 m clear paved area all around the aeroplane for the movement of the de-icing/ anti-icing vehicles.

Note – Where more than one de-icing/anti-icing pad is provided, consideration will have to be given to providing de-icing/anti-icing vehicle movement areas of adjacent pads that do not overlap, but are exclusive for each pad. Consideration will also need to be given to bypassing of the area by other aeroplanes with the clearance specified in 3.15.9 and .3.15.10.

3.15.6 The number of de-icing/anti-icing pads required should determined based on the meteorological conditions, the type of aeroplanes to be treated an capacity of the dispensing equipment used, and the departure flow rates.

Note – See the ICAO Aerodrome Design Manual, Part 2.

#### Slopes of de-icing/anti-icing pads

3.15.7 The de-icing/anti-icing pads should be provided with suitable slopes to ensure satisfactory drainage of the area and to permit collection of all excess de-icing/anti-icing fluid running off an aeroplane. The maximum longitudinal slopes should be as little as practicable and the transverse slope should not exceed 1 per cent.

#### Strength of the de-icing/anti-icing pads

3.15.8 The de-icing/anti-icing pad should be capable of withstanding the traffic of the aircraft is intended to serve, due consideration being given to the fact that the de-icing/anti-icing pad ( like an apron ) will be subjected to a higher density of traffic and, as a result of slow moving or stationary aircraft, to higher stresses than a runway.

3.15.9. A de-icing/anti-icing pad should provide the minimum clearances specified in 3.13.6.for aircraft stands. If the pad layout is such as to include bypass configuration, the minimum separation distances specified in Table 3-1, column 12, should be provided.

3.15.10 Where the de-icing/anti-icing facility is located adjoining a regular taxiway, the taxiway minimum separation distance specified in Table 3-1, column 11, should be provided .(See Figure 3-4).

Note – The excess de-icing/anti-icing fluid running off an aeroplane poses the risk of contamination of ground water in addition to affecting the pavement surface friction characteristics.

3.15.11 Where de-icing/anti-icing activities are carried out, the surface drainage should be planned to collect the run off separately, preventing its mixing with the normal surface run-off so that it does not pollute the ground water.

**Left blank intentionally**







Figure 3-4. Minimum separation distance on a de-icing/anti-icing facility



## **CHAPTER 4 - OBSTACLE RESTRICTION AND REMOVAL**

Note 1.— The objectives of the specifications in this chapter are to define the airspace around aerodromes to be maintained free from obstacles so as to permit the intended aeroplane operations at the aerodromes to be conducted safely and to prevent the aerodromes from becoming unusable by the growth of obstacles around the aerodromes. This is achieved by establishing a series of obstacle limitation surfaces that define the limits to which objects may project into the airspace.

Note 2.— Objects which penetrate the obstacle limitation surfaces contained in this chapter may in certain circumstances cause an increase in the obstacle clearance altitude/height for an instrument approach procedure or any associated visual circling procedure or have other operational impact on flight procedure design. Criteria for flight procedure design are contained in Procedures for Air Navigation Services – Aircraft Operations (PANS-OPS, Doc 8168).

Note 3.— The establishment of, and requirements for, an obstacle protection surface for visual approach slope indicator systems are specified in 5.3.5.41 to 5.3.5.45.

### **4.1 Obstacle limitation surfaces**

Note.— See Figure 4-1.

#### **Outer horizontal surface**

Note.— Guidance on the need to provide an outer horizontal surface and its characteristics is contained in the ICAO Airport Services Manual (Doc 9137), Part 6.

#### **Conical surface**

4.1.1 Description.— Conical surface. A surface sloping upwards and outwards from the periphery of the inner horizontal surface.

4.1.2 Characteristics. The limits of the conical surface shall comprise:

- a) a lower edge coincident with the periphery of the inner horizontal surface; and
- b) an upper edge located at a specified height above the

inner horizontal surface.

4.1.3 The slope of the conical surface shall be measured in a vertical plane perpendicular to the periphery of the inner horizontal surface.

#### **Inner horizontal surface**

4.1.4 Description. Inner horizontal surface. A surface located in a horizontal plane above an aerodrome and its environs.

4.1.5 Characteristics. The radius or outer limits of the inner horizontal surface shall be measured from a reference point or points established for such purpose.

Note.— The shape of the inner horizontal surface need not necessarily be circular. Guidance on determining the extent of the inner horizontal surface is contained in the ICAO Airport Services Manual (Doc 9137), Part 6.

4.1.6 The height of the inner horizontal surface shall be measured above an elevation datum established for such purpose.

Note.— Guidance on determining the elevation datum is contained in the ICAO Airport Services Manual (Doc 9137), Part 6.

#### **Approach surface**


4.1.7 Description. Approach surface. An inclined plane or combination of planes preceding the threshold.

4.1.8 Characteristics. The limits of the approach surface shall comprise:

- a) an inner edge of specified length, horizontal and perpendicular to the extended center line of the runway and located at a specified distance before the threshold;
- b) two sides originating at the ends of the inner edge and diverging uniformly at a specified rate from the extended center line of the runway;
- c) an outer edge parallel to the inner edge; and
- d) The above surfaces shall be varied when lateral offset, offset or curved approaches are utilized, specifically, two sides originating at the ends of the inner edge and diverging uniformly at a specified rate from the extended center line of the lateral offset, offset or curved ground track.

4.1.9 The elevation of the inner edge shall be equal to the elevation of the mid-point of the threshold.

4.1.10 The slope(s) of the approach surface shall be measured in the vertical plane containing the center line of the runway and shall continue containing the center line of any lateral offset or curved ground track.



**Figure 4-1. Obstacle limitation surfaces**

### Inner approach surface

4.1.11 Description.— Inner approach surface. A rectangular portion of the approach surface immediately preceding the threshold.

4.1.12 Characteristics.— The limits of the inner approach surface shall comprise:

- a) an inner edge coincident with the location of the inner edge of the approach surface but of its own specified length;
- b) two sides originating at the ends of the inner edge and extending parallel to the vertical plane containing the center line of the runway; and
- c) an outer edge parallel to the inner edge.

### Transitional surface

4.1.13 Description.— Transitional surface. A complex surface along the side of the strip and part of the side of the approach surface, that slopes upwards and outwards to the inner horizontal surface.

4.1.14 Characteristics.— The limits of a transitional surface shall comprise:

- a) a lower edge beginning at the intersection of the side of the approach surface with the inner horizontal surface and extending down the side of the approach surface to the inner edge of the approach surface and from there along the length of the strip parallel to the runway center line; and
- b) an upper edge located in the plane of the inner horizontal surface.

4.1.15 The elevation of a point on the lower edge shall be:

- a) along the side of the approach surface — equal to the elevation of the approach surface at that point; and
- b) along the strip — equal to the elevation of the nearest point on the center line of the runway or its extension.

Note.— As a result of b) the transitional surface along the strip will be curved if the runway profile is curved, or a plane if the runway profile is a straight line. The intersection of the transitional surface with the inner horizontal surface will also be a curved or a straight line depending on the runway profile.

4.1.16 The slope of the transitional surface shall be measured in a vertical plane at right angles to the center line of the runway.

### Inner transitional surface

Note.— It is intended that the inner transitional surface be the controlling obstacle limitation surface for navigation aids, aircraft and other vehicles that must be near the runway and which is not to be penetrated except for frangible objects. The transitional surface described in 4.1.13 is intended to remain as the controlling obstacle limitation surface for buildings, etc.

4.1.17 Description. Inner transitional surface. A surface similar to the transitional surface but closer to the runway.

4.1.18 Characteristics. The limits of an inner transitional surface shall comprise:

- a) a lower edge beginning at the end of the inner approach surface and extending down the side of the inner approach surface to the inner edge of that surface, from there along the strip parallel to the runway center line to the inner edge of the balked landing surface and from there up the side of the balked landing surface to the point where the side intersects the inner horizontal surface; and
- b) an upper edge located in the plane of the inner horizontal surface.

4.1.19 The elevation of a point on the lower edge shall be:

- a) along the side of the inner approach surface and balked landing surface — equal to the elevation of the particular surface at that point; and
- b) along the strip — equal to the elevation of the nearest point on the center line of the runway or its extension.

Note.— As a result of b) the inner transitional surface along the strip will be curved if the runway profile is curved or a plane if the runway profile is a straight line. The intersection of the inner transitional surface with the inner horizontal surface will also be a curved or straight line depending on the runway profile.

4.1.20 The slope of the inner transitional surface shall be measured in a vertical plane at right angles to the center line of the runway.




Figure 4-2. Inner approach, inner transitional and balked landing obstacle limitation surfaces



## Balked landing surface

4.1.21 Description. Balked landing surface. An inclined plane located at a specified distance after the threshold, extending between the inner transitional surface.

4.1.22 Characteristics. The limits of the balked landing surface shall comprise:

- a) an inner edge horizontal and perpendicular to the center line of the runway and located at a specified distance after the threshold;
- b) two sides originating at the ends of the inner edge and diverging uniformly at a specified rate from the vertical plane containing the center line of the runway; and
- c) an outer edge parallel to the inner edge and located in the plane of the inner horizontal surface.

4.1.23 The elevation of the inner edge shall be equal to the elevation of the runway center line at the location of the inner edge.

4.1.24 The slope of the balked landing surface shall be measured in the vertical plane containing the center line of the runway.

## Take-off climb surface

4.1.25 Description. Take-off climb surface. An inclined plane or other specified surface beyond the end of a runway or clearway.

4.1.26 Characteristics. The limits of the take-off climb surface shall comprise:

- a) an inner edge horizontal and perpendicular to the center line of the runway and located either at a specified distance beyond the end of the runway or at the end of the clearway when such is provided and its length exceeds the specified distance;
- b) two sides originating at the ends of the inner edge, diverging uniformly at a specified rate from the take-off track to a specified final width and continuing thereafter at that width for the remainder of the length of the takeoff climb surface; and
- c) an outer edge horizontal and perpendicular to the specified take-off track.

4.1.27 The elevation of the inner edge shall be equal to the highest point on the extended runway center line between the end of the runway and the inner edge, except that when a clearway is provided the elevation shall be equal to the highest point on the ground on the center line of the clearway.

4.1.28 In the case of a straight take-off flight path, the slope of the take-off climb surface shall be measured in the vertical plane containing the center line of the runway.

4.1.29 In the case of a take-off flight path involving a turn, the take-off climb surface shall be a complex surface containing the horizontal normals to its center line, and the slope of the center line shall be the same as that for a straight take-off flight path.

## 4.2 Obstacle limitation requirements

Note.— The requirements for obstacle limitation surfaces are specified on the basis of the intended use of a runway, i.e. take-off or landing and type of approach, and are intended to be applied when such use is made of the runway. In cases where operations are conducted to or from both directions of a runway, then the function of certain surfaces may be nullified because of more stringent requirements of another lower surface.

### Non-instrument runways

4.2.1 The following obstacle limitation surfaces shall be established for a non-instrument runway:

- conical surface;
- inner horizontal surface;
- approach surface; and
- transitional surfaces.

4.2.2 The heights and slopes of the surfaces shall not be greater than, and their other dimensions not less than, those specified in Table 4-1.

4.2.3 New objects or extensions of existing objects shall not be permitted above an approach or transitional surface except when, in the opinion of the appropriate authority, the new object or extension would be shielded by an existing immovable object.

Note.— Circumstances in which the shielding principle may reasonably be applied are described in the ICAO Airport Services Manual (Doc 9137), Part 6.

4.2.4 New objects or extensions of existing objects should not be permitted above the conical surface or inner horizontal surface except when, in the opinion of the appropriate authority, the object would be shielded by an existing immovable object, or after aeronautical study it is determined that the object would not adversely affect the safety or significantly affect the regularity of operations of aeroplanes.

4.2.5 Existing objects above any of the surfaces required by 4.2.1 should as far as practicable be removed except when, in the opinion of the appropriate authority, the object is shielded by an existing immovable object, or after aeronautical study it is determined that the object

would not adversely affect the safety or significantly affect the regularity of operations of aeroplanes.

Note.— Because of transverse or longitudinal slopes on a strip, in certain cases the inner edge or portions of the inner edge of the approach surface may be below the corresponding elevation of the strip. It is not intended that the strip be graded to conform with the inner edge of the approach surface, nor is it intended that terrain or objects which are above the approach surface beyond the end of the strip, but below the level of the strip, be removed unless it is considered they may endanger aeroplanes.

4.2.6 In considering proposed construction, account should be taken of the possible future development of an instrument runway and consequent requirement for more stringent obstacle limitation surfaces.

### Non-precision approach runways

4.2.7 The following obstacle limitation surfaces shall be established for a non-precision approach runway:

- conical surface;
- inner horizontal surface;
- approach surface; and
- transitional surfaces.

4.2.8 The heights and slopes of the surfaces shall not be greater than, and their other dimensions not less than, those specified in Table 4-1, except in the case of the horizontal section of the approach surface (see 4.2.9).

4.2.9 The approach surface shall be horizontal beyond the point at which the 2.5 per cent slope intersects:

- a. a horizontal plane 150 m above the threshold elevation; or
- b. the horizontal plane passing through the top of any object that governs the obstacle clearance altitude/height (OCA/H); whichever is the higher.

4.2.10 New objects or extensions of existing objects shall not be permitted above an approach surface within 3000m of the inner edge or above a transitional surface except when, in the opinion of the appropriate authority, the new object or extension would be shielded by an existing immovable object.

Note.— Circumstances in which the shielding principle may reasonably be applied are described in the ICAO Airport Services Manual, Part 6.

4.2.11 New objects or extensions of existing objects should not be permitted above the approach surface beyond 3 000 m from the inner edge, the conical surface or inner horizontal surface except when, in the opinion of the appropriate authority, the object would be shielded by an existing immovable object, or after aeronautical study it is determined that the object would not adversely affect the safety or significantly affect the regularity of operations of aeroplanes.

4.2.12 Existing objects above any of the surfaces required by 4.2.7 should as far as practicable be removed except when, in the opinion of the appropriate authority, the object is shielded by an existing immovable object, or after aeronautical study it is determined that the object would not adversely affect the safety or significantly affect the regularity of operations of aeroplanes.

Note.— Because of transverse or longitudinal slopes on a strip, in certain cases the inner edge or portions of the inner edge of the approach surface may be below the corresponding elevation of the strip. It is not intended that the strip be graded to conform with the inner edge of the approach surface, nor is it intended that terrain or objects which are above the approach surface beyond the end of the strip, but below the level of the strip, be removed unless it is considered they may endanger aeroplanes.

### Precision approach runways

Note 1.— See 9.9 for information regarding siting of equipment and installations on operational areas.

Note 2.— Guidance on obstacle limitation surfaces for precision approach runways is given in the ICAO Airport Services Manual, Part 6.

4.2.13 The following obstacle limitation surfaces shall be established for a precision approach runway category I:

- conical surface;
- inner horizontal surface;
- approach surface; and
- transitional surfaces.

4.2.14 The following obstacle limitation surfaces should be established for a precision approach runway category I:

- inner approach surface;
- inner transitional surfaces; and
- balked landing surface.

Table 4-1. Dimensions and slopes of obstacle limitation surfaces — Approach runways

## APPROACH RUNWAYS

Surface and dimensions <sup>a</sup>	RUNWAY CLASSIFICATION									
	Non-instrument				Non-precision approach			Precision approach category		
	Code number				Code number			I		II or III
	1	2	3	4	1,2	3	4	Code number	3,4	Code number
(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)	(10)	(11)
<b>CONICAL</b>										
Slope	5%	5%	5%	5%	5%	5%	5%	5%	5%	5%
Height	35 m	55 m	75 m	100 m	60 m	75 m	100 m	60 m	100 m	100 m
<b>INNER HORIZONTAL</b>										
Height	45 m	45 m	45 m	45 m	45 m	45 m	45 m	45 m	45 m	45 m
Radius	2 000 m	2 500 m	4 000 m	4 000 m	3 500 m	4 000 m	4 000 m	3 500 m	4 000 m	4 000 m
<b>INNER APPROACH</b>										
Width	—	—	—	—	—	—	—	90 m	120 m <sup>e</sup>	120 m <sup>e</sup>
Distance from threshold	—	—	—	—	—	—	—	60 m	60 m	60 m
Length	—	—	—	—	—	—	—	900 m	900 m	900 m
Slope	—	—	—	—	—	—	—	2.5%	2%	2%
<b>APPROACH</b>										
Length of inner edge	60 m	80 m	150 m	150 m	150 m	300 m	300 m	150 m	300 m	300 m
Distance from threshold	30 m	60 m	60 m	60 m	60 m	60 m	60 m	60 m	60 m	60 m
Divergence (each side)	10%	10%	10%	10%	15%	15%	15%	15%	15%	15%
<b>First section</b>										
Length	1 600 m	2 500 m	3 000 m	3 000 m	2 500 m	3 000 m	3 000 m	3 000 m	3 000 m	3 000 m
Slope	5%	4%	3.33%	2.5%	3.33%	2%	2%	2.5%	2%	2%
<b>Second section</b>										
Length	—	—	—	—	—	3 600 m <sup>b</sup>	3 600 m <sup>b</sup>	12 000 m	3 600 m <sup>b</sup>	3 600 m <sup>b</sup>
Slope	—	—	—	—	—	2.5%	2.5%	3%	2.5%	2.5%
<b>Horizontal section</b>										
Length	—	—	—	—	—	8 400 m <sup>b</sup>	8 400 m <sup>b</sup>	—	8 400 m <sup>b</sup>	8 400 m <sup>b</sup>
Total length	—	—	—	—	—	15 000 m	15 000 m	15 000 m	15 000 m	15 000 m
<b>TRANSITIONAL</b>										
Slope	20%	20%	14.3%	14.3%	20%	14.3%	14.3%	14.3%	14.3%	14.3%
<b>INNER TRANSITIONAL</b>										
Slope	—	—	—	—	—	—	—	40%	33.3%	33.3%
<b>BALKED LANDING SURFACE</b>										
Length of inner edge	—	—	—	—	—	—	—	90 m	120 m <sup>e</sup>	120 m <sup>e</sup>
Distance from threshold	—	—	—	—	—	—	—	<sup>c</sup>	1 800 m <sup>d</sup>	1 800 m <sup>d</sup>
Divergence (each side)	—	—	—	—	—	—	—	10%	10%	10%
Slope	—	—	—	—	—	—	—	4%	3.33%	3.33%
<p>a. All dimensions are measured horizontally unless specified otherwise.</p> <p>b. Variable length (see 4.2.9 or 4.2.17).</p> <p>c. Distance to the end of strip.</p> <p>d. Or end of runway whichever is less.</p> <p>e. Where the code letter is F (Column (3) of Table 1-1), the width is increased to 155 m. For information on code letter F aeroplanes equipped with digital avionics that provide steering commands to maintain an established track during the go-around manoeuvre, see Circular 301 — <i>New Larger Aeroplanes — Infringement of the Obstacle Free Zone: Operational Measures and Aeronautical Study</i>.</p>										

4.2.15 The following obstacle limitation surfaces shall be established for a precision approach runway category II or III:

- conical surface;
- inner horizontal surface;
- approach surface and inner approach surface;
- transitional surfaces;
- inner transitional surfaces; and
- balked landing surface.

4.2.16 The heights and slopes of the surfaces shall not be greater than, and their other dimensions not less than, those specified in Table 4-1, except in the case of the horizontal section of the approach surface (see 4.2.17).

4.2.17 The approach surface shall be horizontal beyond the point at which the 2.5 per cent slope intersects:

- a) a horizontal plane 150 m above the threshold elevation; or
  - b) the horizontal plane passing through the top of any object that governs the obstacle clearance limit;
- whichever is the higher.

4.2.18 Fixed objects shall not be permitted above the inner approach surface, the inner transitional surface or the balked landing surface, except for frangible objects which because of their function must be located on the strip. Mobile objects shall not be permitted above these surfaces during the use of the runway for landing.

4.2.19 New objects or extensions of existing objects shall not be permitted above an approach surface or a transitional surface except when, in the opinion of the appropriate authority, the new object or extension would be shielded by an existing immovable object.

Note.— Circumstances in which the shielding principle may reasonably be applied are described in the ICAO Airport Services Manual, Part 6.

4.2.20 New objects or extensions of existing objects should not be permitted above the conical surface and the inner horizontal surface except when, in the opinion of the appropriate authority, an object would be shielded by an existing immovable object, or after aeronautical study it is determined that the object would not adversely affect the safety or significantly affect the regularity of operations of aeroplanes.

4.2.21 Existing objects above an approach surface, a transitional surface, the conical surface and inner horizontal surface should as far as practicable be removed except when, in the opinion of the GACA SD, an object is shielded by an existing immovable object, or after aeronautical study it is determined that the object would

not adversely affect the safety or significantly affect the regularity of operations of aeroplanes.

Note.— Because of transverse or longitudinal slopes on a strip, in certain cases the inner edge or portions of the inner edge of the approach surface may be below the corresponding elevation of the strip. It is not intended that the strip be graded to conform with the inner edge of the approach surface, nor is it intended that terrain or objects which are above the approach surface beyond the end of the strip, but below the level of the strip, be removed unless it is considered they may endanger aeroplanes.

#### **Runways meant for take-off**

4.2.22 The following obstacle limitation surface shall be established for a runway meant for take-off:

— take-off climb surface.

4.2.23 The dimensions of the surface shall be not less than the dimensions specified in Table 4-2, except that a lesser length may be adopted for the take-off climb surface where such lesser length would be consistent with procedural measures adopted to govern the outward flight of aeroplanes.

4.2.24 The operational characteristics of aeroplanes for which the runway is intended should be examined to see if it is desirable to reduce the slope specified in Table 4-2 when critical operating conditions are to be catered to. If the specified slope is reduced, corresponding adjustment in the length of take-off climb surface should be made so as to provide protection to a height of 300 m.

Note.— When local conditions differ widely from sea level standard atmospheric conditions, it may be advisable for the slope specified in Table 4-2 to be reduced. The degree of this reduction depends on the divergence between local conditions and sea level standard atmospheric conditions, and on the performance characteristics and operational requirements of the aeroplanes for which the runway is intended.

4.2.25 New objects or extensions of existing objects shall not be permitted above a take-off climb surface except when, in the opinion of the appropriate authority, the new object or extension would be shielded by an existing immovable object.

Note.— Circumstances in which the shielding principle may reasonably be applied are described in the ICAO Airport Services Manual, Part 6.

4.2.26 If no object reaches the 2 per cent (1:50) take-off climb surface, new objects should be limited to preserve the existing obstacle free surface or a surface down to a slope of 1.6 per cent (1:62.5).

4.2.27 Existing objects that extend above a take-off climb surface should as far as practicable be removed except when, in the opinion of the appropriate authority, an object is shielded by an existing immovable object, or after aeronautical study it is determined that the object would not adversely affect the safety or significantly affect the regularity of operations of aeroplanes.

Note.— Because of transverse slopes on a strip or clearway, in certain cases portions of the inner edge of the take-off climb surface may be below the corresponding elevation of the strip or clearway. It is not intended that the strip or clearway be graded to conform with the inner edge of the take-off climb surface, nor is it intended that terrain or objects which are above the take-off climb surface beyond the end of the strip or clearway, but below the level of the strip or clearway, be removed unless it is considered they may endanger aeroplanes. Similar considerations apply at the junction of a clearway and strip where differences in transverse slopes exist.

### 4.3 Objects outside the obstacle limitation surfaces

4.3.1 Arrangements should be made to enable the appropriate authority to be consulted concerning proposed construction beyond the limits of the obstacle limitation surfaces that extend above a height established by that authority, in order to permit an aeronautical study of the effect of such construction on the operation of aeroplanes.

4.3.2 In areas beyond the limits of the obstacle limitation surfaces, at least those objects which extend to a height of 150 m or more above ground elevation should be regarded as obstacles, unless a special aeronautical study indicates that they do not constitute a hazard to aeroplanes.

Note.— This study may have regard to the nature of operations concerned and may distinguish between day and night operations.

### 4.4 Other objects

4.4.1 Objects which do not project through the approach surface but which would nevertheless adversely affect the optimum siting or performance of visual or non-visual aids should, as far as practicable, be removed.

4.4.2 Anything which may, in the opinion of the appropriate authority after aeronautical study, endanger aeroplanes on the movement area or in the air within the limits of the inner horizontal and conical surfaces should be regarded as an obstacle and should be removed in so far as practicable.

Note.— In certain circumstances, objects that do not project above any of the surfaces enumerated in 4.1 may constitute a hazard to aeroplanes as, for example, where there are one or more isolated objects in the vicinity of an aerodrome.

**Left blank intentionally**




Table 4-2. Dimensions and slopes of obstacle limitation surfaces

## RUNWAYS MEANT FOR TAKE-OFF

Surface and dimensions <sup>a</sup>	Code number		
	1	2	3 or 4
(1)	(2)	(3)	(4)
<b>TAKE-OFF CLIMB</b>			
Length of inner edge	60 m	80 m	180 m
Distance from runway end <sup>b</sup>	30 m	60 m	60 m
Divergence (each side)	10%	10%	12.5%
Final width	380 m	580 m	1 200 m 1 800 m <sup>c</sup>
Length	1 600 m	2 500 m	15 000 m
Slope	5%	4%	2% <sup>d</sup>

a. All dimensions are measured horizontally unless specified otherwise.  
b. The take-off climb surface starts at the end of the clearway if the clearway length exceeds the specified distance.  
c. 1 800 m when the intended track includes changes of heading greater than 15° for operations conducted in IMC, VMC by night.  
d. See 4.2.24 and 4.2.26.



## CHAPTER 5 - VISUAL AIDS FOR NAVIGATION

### 5.1 Indicators and signaling devices

#### 5.1.1 Wind direction indicators

##### Application

5.1.1.1 An aerodrome shall be equipped with at least one wind direction indicator.

##### Location

5.1.1.2 A wind direction indicator shall be located so as to be visible from aircraft in flight or on the movement area and in such a way as to be free from the effects of air disturbances caused by nearby objects.

##### Characteristics

5.1.1.3 The wind direction indicator should be in the form of a truncated cone made of fabric and should have a length of not less than 3.6 m and a diameter, at the larger end, of not less than 0.9 m. It should be constructed so that it gives a clear indication of the direction of the surface wind and a general indication of the wind speed. The color or colors should be so selected as to make the wind direction indicator clearly visible and understandable from a height of at least 300 m, having regard to background. Where practicable, a single color, preferably white or orange, should be used. Where a combination of two colors is required to give adequate conspicuity against changing backgrounds, they should preferably be orange and white, red and white, or black and white, and should be arranged in five alternate bands, the first and last bands being the darker color.

5.1.1.4 The location of at least one wind direction indicator should be marked by a circular band 15 m in diameter and 1.2 m wide. The band should be centered about the wind direction indicator support and should be in a color chosen to give adequate conspicuity, preferably white.

5.1.1.5 Provision should be made for illuminating at least one wind indicator at an aerodrome intended for use at night.

#### 5.1.2 Landing direction indicator

##### Location

5.1.2.1 Where provided, a landing direction indicator shall be located in a conspicuous place on the aerodrome.

##### Characteristics

5.1.2.2 The landing direction indicator should be in the form of a “T”.

5.1.2.3 The shape and minimum dimensions of a landing “T” shall be as shown in Figure 5-1. The color of the landing “T” shall be either white or orange, the choice being dependent on the color that contrasts best with the background against which the indicator will be viewed. Where required for use at night the landing “T” shall either be illuminated or outlined by white lights.

#### 5.1.3 Signaling lamp

##### Application

5.1.3.1 A signaling lamp shall be provided at a controlled aerodrome in the aerodrome control tower.

##### Characteristics

5.1.3.2 A signaling lamp should be capable of producing red, green and white signals, and of:




Figure 5-1 Landing direction indicator

- a) being aimed manually at any target as required;
- b) giving a signal in any one color followed by a signal in either of the two other colors; and
- c) transmitting a message in any one of the three colors by Morse Code up to a speed of at least four words per minute. When selecting the green light, use should be made of the restricted boundary of green as specified in Appendix 1, 2.1.2.

5.1.3.3 The beam spread should be not less than 1° or greater than 3°, with negligible light beyond 3°. When the signaling lamp is intended for use in the daytime the intensity of the colored light should be not less than 6,000 cd.

#### 5.1.4 Signal panels and signal area

Note. — The inclusion of detailed specifications for a signal area in this section is not intended to imply that one has to be provided. Attachment A, Section 15 provides guidance on the need to provide ground signals. GACA Regulation Section 2 and ICAO Annex 2, Appendix 1 specifies the shape, color and use of visual ground signals. The ICAO Aerodrome Design Manual, Part 4 provides guidance on their design.

#### **Location of signal area**

5.1.4.1 The signal area should be located so as to be visible for all angles of azimuth above an angle of 10° above the horizontal when viewed from a height of 300 m.

#### **Characteristics of signal area**

5.1.4.2 The signal area shall be an even horizontal surface at least 9 m square.

5.1.4.3 The color of the signal area should be chosen to contrast with the colors of the signal panels used, and it should be surrounded by a white border not less than 0.3 m wide.

### **5.2 Markings**

#### **5.2.1 General**

##### **Interruption of runway markings**

5.2.1.1 At an intersection of two (or more) runways the markings of the more important runway, except for the runway side stripe marking, shall be displayed and the markings of the other runway(s) shall be interrupted. The runway side stripe marking of the more important runway may be either continued across the intersection or interrupted.

5.2.1.2 The order of importance of runways for the display of runway markings should be as follows:

- 1st — precision approach runway;
- 2nd — non-precision approach runway; and
- 3rd — non-instrument runway

5.2.1.3 At an intersection of a runway and taxiway the markings of the runway shall be displayed and the markings of the taxiway interrupted, except that runway side stripe markings may be interrupted.

Note. — See 5.2.8.5 regarding the manner of connecting runway and taxiway center line markings.

#### **Color and conspicuity**

5.2.1.4 Runway markings shall be white.

Note 1 — It has been found that, on runway surfaces of

light color, the conspicuity of white markings can be improved by outlining them in black.

Note 2 — It is preferable that the risk of uneven friction characteristics on markings be reduced in so far as practicable by the use of a suitable kind of paint.

Note 3 — Markings may consist of solid areas or a series of longitudinal stripes providing an effect equivalent to the solid areas.

5.2.1.5 Taxiway markings and aircraft stand markings shall be yellow.

5.2.1.6 Apron safety lines shall be of a conspicuous color which shall contrast with that used for aircraft stand markings.

5.2.1.7 At aerodromes where operations take place at night, pavement markings should be made with reflective materials designed to enhance the visibility of the markings.

Note. — Guidance on reflective materials is given in the ICAO Aerodrome Design Manual, Part 4

#### **Unpaved taxiways**

5.2.1.8 An unpaved taxiway should be provided, so far as practicable, with the markings prescribed for paved taxiways.

#### **5.2.2 Runway designation marking**

##### **Application**

5.2.2.1 A runway designation marking shall be provided at the thresholds of a paved runway.

5.2.2.2 A runway designation marking should be provided, so far as practicable, at the thresholds of an unpaved runway.

##### **Location**

5.2.2.3 A runway designation marking shall be located at a threshold as shown in Figure 5-2 as appropriate

Note. — If the runway threshold is displaced from the extremity of the runway, a sign showing the designation of the runway may be provided for aeroplanes taking off.

##### **Characteristics**

5.2.2.4 A runway designation marking shall consist of a two-digit number and on parallel runways shall be supplemented with a letter. On a single runway, dual parallel runways and triple parallel runways the two-digit number shall be the whole number nearest the one-tenth of the magnetic North when viewed from the direction of approach. On four or more parallel runways, one set of adjacent runways shall be numbered to the nearest one-

**A – General and all precision approach runways**

Precision approach category I and non-precision approach runways 0.45 m mnm

Precision approach category II and III runways 0.9 m mnm

$\ell'$

20 m

30 m

50 m mnm

12 m

9 m mnm

12 m

30 m

6 m mnm

$\alpha$

20

$\alpha$

**B – Parallel runways**

$\ell'$

20 m

30 m

50 m mnm

12 m

9 m mnm

6 m mnm

9 m mnm

12 m

30 m

6 m mnm

$\alpha$

20

$\alpha$

**C – Optional pattern**

Non-precision approach runways 0.45 m mnm

Non-instrument runways 0.3 m mnm

30 m

20 m

30 m

30 m

30 m

30 m

6 m mnm


22.5 m

$\alpha$

$\alpha$

$\alpha = 1.8 \text{ m aprx.}$

**Figure 5-2 Runway designation, centre line and threshold markings**



Note.—All units are expressed in metres.

Figure 5-3 Form and proportions of numbers and letters for runway designation markings



5.2.2.5 In the case of parallel runways, each runway designation number shall be supplemented by a letter as follows, in the order shown from left to right when viewed from the direction of approach:

- a) for two parallel runways: “L” “R”;
- b) for three parallel runways: “L” “C” “R”;
- c) for four parallel runways: “L” “R” “L” “R”;
- d) for five parallel runways: “L” “C” “R” “L” “R” or “L” “R” “L” “C” “R”; and
- e) for six parallel runways: “L” “C” “R” “L” “C” “R”.

5.2.2.6 The numbers and letters shall be in the form and proportion shown in Figure 5-3. The dimensions shall be not less than those shown in Figure 5-3, but where the numbers are incorporated in the threshold marking, larger dimensions shall be used in order to fill adequately the gap between the stripes of the threshold marking.

### 5.2.3 Runway center line marking

#### Application

5.2.3.1 A runway center line marking shall be provided on a paved runway.

#### Location

5.2.3.2 A runway center line marking shall be located along the center line of the runway between the runway designation markings as shown in Figure 5-2, except when interrupted in compliance with 5.2.1.1.

#### Characteristics

5.2.3.3 A runway center line marking shall consist of a line of uniformly spaced stripes and gaps. The length of a stripe plus a gap shall be not less than 50 m or more than 75 m. The length of each stripe shall be at least equal to the length of the gap or 30 m, whichever is greater.

5.2.3.4 The width of the stripes shall be not less than:

- a) 0.90 m on precision approach category II and III runways;
- b) 0.45 m on non-precision approach runways where the code number is 3 or 4, and precision approach category I runways; and
- c) 0.30 m on non-precision approach runways where the code number is 1 or 2, and on non-instrument runways.

### 5.2.4 Threshold marking

#### Application

5.2.4.1 A threshold marking shall be provided at the threshold of a paved instrument runway, and of a paved non instrument runway where the code number is 3 or 4 and the runway is intended for use by international commercial air transport.

5.2.4.2 A threshold marking should be provided at the threshold of a paved non-instrument runway where the code number is 3 or 4 and the runway is intended for use by other than international commercial air transport.

5.2.4.3 A threshold marking should be provided, so far as practicable, at the thresholds of an unpaved runway.

Note. — The ICAO Aerodrome Design Manual, Part 4, shows a form of marking which has been found satisfactory for the marking of downward slopes immediately before the threshold.

#### Location

5.2.4.4 The stripes of the threshold marking shall commence 6 m from the threshold.

#### Characteristics

5.2.4.5 A runway threshold marking shall consist of a pattern of longitudinal stripes of uniform dimensions disposed symmetrically about the center line of a runway as shown in Figure 5-2 (A) and (B) for a runway width of 45 m. The number of stripes shall be in accordance with the runway width as follows:

Runway width	Number of stripes
18 m	4
23 m	6
30 m	8
45 m	12
60 m	16

except that on non-precision approach and non-instrument runways 45 m or greater in width, they may be as shown in Figure 5-2 (C).

5.2.4.6 The stripes shall extend laterally to within 3 m of the edge of a runway or to a distance of 27 m on either side of a runway center line, whichever results in the smaller lateral distance. Where a runway designation marking is placed within a threshold marking there shall be a minimum of three stripes on each side of the center line of the runway. Where a runway designation marking is placed above a threshold marking, the stripes shall be continued across the runway. The stripes shall be at least 30 m long and approximately 1.80 m wide with a spacing of approximately 1.80 m between them except that, where the stripes are continued across a runway, a double spacing shall be used to separate the two stripes nearest the center line of the runway, and in the case where the designation marking is included within the threshold marking this spacing shall be 22.5 m.

#### Transverse stripe

5.2.4.7 Where a threshold is displaced from the extremity of a runway or where the extremity of a runway is not square with the runway center line, a transverse stripe as shown in Figure 5-4 (B) should be added to the threshold marking.

5.2.4.8 A transverse stripe shall be not less than 1.80 m wide.

#### Arrows

5.2.4.9 Where a runway threshold is permanently displaced, arrows conforming to Figure 5-4 (B) shall be provided on the portion of the runway before the displaced threshold.

5.2.4.10 When a runway threshold is temporarily displaced from the normal position, it shall be marked as shown in Figure 5-4 (A) or 5-4 (B) and all markings prior to the displaced threshold shall be obscured except the runway center line marking, which shall be converted to arrows.

Note 1 — In the case where a threshold is temporarily displaced for only a short period of time, it has been found satisfactory to use markers in the form and color of a displaced threshold marking rather than attempting to paint this marking on the runway.

Note 2 — When the runway before a displaced threshold is unfit for the surface movement of aircraft, closed markings, as described in 7.1.4, are required to be provided.

#### 5.2.5 Aiming point marking

##### Application

5.2.5.1 The provisions of Sections 5.2.5 and 5.2.6 shall not require the replacement of existing markings before 1 January 2005.

5.2.5.2 An aiming point marking shall be provided at each approach end of a paved instrument runway where the code number is 2, 3 or 4.

5.2.5.3 An aiming point marking should be provided at each approach end of:

- a) a paved non-instrument runway where the code number is 3 or 4,
- b) a paved instrument runway where the code number is 1,

when additional conspicuity of the aiming point is desirable.

##### Location

5.2.5.4 The aiming point marking shall commence no closer to the threshold than the distance indicated in the appropriate column of Table 5-1, except that, on a runway equipped with a visual approach slope indicator system, the beginning of the marking shall be coincident with the visual approach slope origin.

5.2.5.5 An aiming point marking shall consist of two conspicuous stripes. The dimensions of the stripes and the

lateral spacing between their inner sides shall be in accordance with the provisions of the appropriate column of Table 5-1. Where a touchdown zone marking is provided, the lateral spacing between the markings shall be the same as that of the touchdown zone marking.

#### 5.2.6 Touchdown zone marking

##### Application


5.2.6.1 A touchdown zone marking shall be provided in the touchdown zone of a paved precision approach runway where the code number is 2, 3 or 4.

5.2.6.2 A touchdown zone marking should be provided in the touchdown zone of a paved non-precision approach or non-instrument runway where the code number is 3 or 4 and additional conspicuity of the touchdown zone is desirable.

##### Location and characteristics

5.2.6.3 A touchdown zone marking shall consist of pairs of rectangular markings symmetrically disposed about the runway center line with the number of such pairs related to the landing distance available and, where the marking is to be displayed at both the approach directions of a runway, the distance between the thresholds, as follows:

Landing distance available or the distance between thresholds	Pair(s) of markings
less than 900 m	1
900 m up to but not including 1200m	2
1 200 m up to but not including 1 500 m	3
1 500 m up to but not including 2 400 m	4
2 400 m or more	6



**Figure 5-4 Displaced threshold markings**




Figure 5-5 Aiming point and touchdown zone markings (illustrated for a runway with a length of 2499 m or more)

**PATTERN A:**  
4 lines and  
3 spaces at  
0.15 m each

**PATTERN B:**  
2 lines at  
0.3 m each  
1 space at  
0.6 m

**INTERMEDIATE HOLDING  
POSITION MARKING**

0.15 m, 0.3 m, 0.6 m, 0.9 m, 1.05 m, 1.20 m, 60 mm, 20

See 5.2.10.1  
and 3.12.2



5.2.6.4 A touchdown zone marking shall conform to either of the two patterns shown in Figure 5-5. For the pattern shown in Figure 5-5 (A), the markings shall be not less than 22.5 m long and 3 m wide. For the pattern shown in Figure 5-5 (B), each stripe of each marking shall be not less than 22.5 m long and 1.8 m wide with spacing of 1.5 m between adjacent stripes. The lateral spacing between the inner sides of the rectangles shall be equal to that of the aiming point marking where provided. Where an aiming point marking is not provided, the lateral spacing between the inner sides of the rectangles shall correspond to the lateral spacing specified for the aiming point marking in Table 5-1 (columns 2, 3, 4 or 5, as appropriate). The pairs of markings shall be provided at longitudinal intervals of 150 m beginning from the threshold except that pairs of touchdown zone markings coincident with or located within 50 m of an aiming point marking shall be deleted from the pattern.

5.2.6.5 On a non-precision approach runway where the code number is 2, an additional pair of touchdown zone marking stripes should be provided 150 m beyond the beginning of the aiming point marking.

## 5.2.7 Runway side stripe marking

### Application

5.2.7.1 A runway side stripe marking shall be provided between the thresholds of a paved runway where there is a lack of contrast between the runway edges and the shoulders or the surrounding terrain

5.2.7.2 A runway side stripe marking should be provided on a precision approach runway irrespective of the contrast between the runway edges and the shoulders or the surrounding terrain.

### Location

5.2.7.3 A runway side stripe marking should consist of two stripes, one placed along each edge of the runway with the outer edge of each stripe approximately on the edge of the runway, except that, where the runway is greater than 60 m in width, the stripes should be located 30 m from the runway center line.

### Characteristics

5.2.7.4 A runway side stripe should have an overall width of at least 0.9 m on runways 30 m or more in width and at least 0.45 m on narrower runways.

## 5.2.8 Taxiway center line marking

### Application

5.2.8.1 Taxiway center line marking shall be provided on a paved taxiway, de-icing/anti-icing facility and apron where the code number is 3 or 4 in such a way as to provide continuous guidance between the runway center line and aircraft stands.

5.2.8.2 Taxiway center line marking should be provided on a paved taxiway, de-icing/anti-icing facility and apron where the code number is 1 or 2 in such a way as to provide continuous guidance between the runway center line and aircraft stands.

5.2.8.3 Taxiway centre line marking shall be provided on a paved runway when the runway is part of a standard taxi-route and:

- a) there is no runway centre line marking; or
- b) where the taxiway centre line is not coincident with the runway centre line.

5.2.8.4 Where it is necessary to denote the proximity of a runway-holding position, enhanced taxiway centre line marking should be provided.

Note.— The provision of enhanced taxiway centre line marking may form part of runway incursion prevention measures.

5.2.8.5 Where provided, enhanced taxiway centre line marking shall be installed at each taxiway/runway intersection.

### Location

5.2.8.6 On a straight section of a taxiway the taxiway center line marking should be located along the taxiway center line. On a taxiway curve the marking should continue from the straight portion of the taxiway at a constant distance from the outside edge of the curve.

Note. — See 3.8.5 and Figure 3-1.

5.2.8.7 At an intersection of a taxiway with a runway where the taxiway serves as an exit from the runway, the taxiway centre line marking should be curved into the runway centre line marking as shown in Figures 5-6 and 5-25. The taxiway centre line marking should be extended parallel to the runway centre line marking for a distance of at least 60 m beyond the point of tangency where the code number is 3 or 4, and for a distance of at least 30 m where the code number is 1 or 2.

Note.— See 3.9.6 and Figure 3-2.

5.2.8.8 Where taxiway center line marking is provided on a runway in accordance with 5.2.8.3, the marking should be located on the center line of the designated taxiway.

5.2.8.9 Where provided:

- 1) An enhanced taxiway centre line marking shall extend from the runway-holding position Pattern A (as defined in Figure 5-6, Taxiway markings) to a distance of up to 47m in the direction of travel away from the runway. See Figure 5-7(a).

- 2) If the enhanced taxiway centre line marking intersects another runway-holding position marking, such as for a precision approach category II or III runway, that is located within 47m of the first runway-holding position marking, the enhanced taxiway centre line marking shall be interrupted 0.9m prior to and after the intersected runway-holding position marking. The enhanced taxiway centre line marking shall continue beyond the intersected runway-holding position marking for at least 3 dashed line segments or 47m from start to finish, whichever is greater. See Figure 5-7(b).
- 3) If the enhanced taxiway centre line marking continues through a taxiway/taxiway intersection that is located within 47m of the runway-holding position marking, the enhanced taxiway centre line marking shall be interrupted 1.5m prior to and after the point where the intersected taxiway centre line crosses the enhanced taxiway centre line. The enhanced taxiway centre line marking shall continue beyond the taxiway/taxiway intersection for at least 3 dashed line segments or 47m from start to finish, whichever is greater. See Figure 5-7(c).
- 4) Where two taxiway centre lines converge at or before the runway-holding position marking, the

inner dashed line shall not be less than 3m in length. See Figure 5-7(d).

- 5) Where there are two opposing runway-holding position markings and the distance between the markings is less than 94m, the enhanced taxiway centre line markings shall extend over this entire distance. The enhanced taxiway centre line markings shall not extend beyond either runway-holding position marking. See Figure 5-7(e)

### Characteristics


5.2.8.10 A taxiway center line marking shall be at least 15 cm in width and continuous in length except where it intersects with a runway-holding position marking or an intermediate holding position marking as shown in Figure 5-6.


5.2.8.11 Enhanced taxiway centre line marking shall be as shown in Figure 5-6A.

### 5.2.9 Runway turn pad marking

#### Application

5.2.9.1 Where a runway turn pad is provided, a runway turn pad marking shall be provided for continuous guidance to enable an aeroplane to complete a 180-degree turn and align with the runway center line.





**Figure 5-7 Enhanced Taxiway Center Line Marking**

## **Location**

5.2.9.2 The runway turn pad marking should be curved from the runway center line into the turn pad. The radius of the curve should be compatible with the maneuvering capability and normal taxiing speeds of the aeroplanes for which the runway turn pad is intended. The intersection angle of the runway turn pad marking with the runway center line should not be greater than 30 degrees.

5.2.9.3 The runway turn pad marking should be extended parallel to the runway center line marking for a distance of at least 60 m beyond the point of tangency where the code number is 3 or 4, and for a distance of at least 30 m where the code number is 1 or 2.

5.2.9.4 A runway turn pad marking should guide the aeroplane in such a way as to allow a straight portion of taxiing before the point where a 180-degree turn is to be made. The straight portion of the runway turn pad marking should be parallel to the outer edge of the runway turn pad.

5.2.9.5 The design of the curve allowing the aeroplane to negotiate a 180-degree turn should be based on a nose wheel steering angle not exceeding 45 degrees.

5.2.9.6 The design of the turn pad marking should be such that, when the cockpit of the aeroplane remains over the runway turn pad marking, the clearance distance between any wheel of the aeroplane landing gear and the edge of the runway turn pad should be not less than those specified in 3.3.6.

Note.— For ease of maneuvering, consideration may be given to providing a larger wheel-to-edge clearance for codes E and F aeroplanes. See 3.3.7.

## **Characteristics**

5.2.9.7 A runway turn pad marking shall be at least 15 cm in width and continuous in length.

## **5.2.10 Runway-holding position marking**

### **Application and location**

5.2.10.1 A runway-holding position marking shall be displayed along a runway-holding position.

Note.— See 5.4.2 concerning the provision of signs at runway-holding positions.

### **Characteristics**

5.2.10.2 At an intersection of a taxiway and a noninstrument, non-precision approach or take-off runway, the runway-holding position marking shall be as shown in Figure 5-6, pattern A.

5.2.10.3 Where a single runway-holding position is provided at an intersection of a taxiway and a precision approach category I, II or III runway, the runway-holding

position marking shall be as shown in Figure 5-6, pattern A. Where two or three runway-holding positions are provided at such an intersection, the runway-holding position marking closer (closest) to the runway shall be as shown in Figure 5-6, pattern A and the markings farther from the runway shall be as shown in Figure 5-6, pattern B.

5.2.10.4 The runway-holding position marking displayed at a runway-holding position established in accordance with 3.12.3 shall be as shown in Figure 5-6, pattern A.

5.2.10.5 Where increased conspicuity of the runway-holding position is required, the runway-holding position marking should be as shown in Figure 5-8, pattern A or pattern B, as appropriate.

5.2.10.6 Where a pattern B runway-holding position marking is located on an area where it would exceed 60 m in length, the term “CAT II” or “CAT III” as appropriate should be marked on the surface at the ends of the runway-holding position marking and at equal intervals of 45 m maximum between successive marks. The letters should be not less than 1.8 m high and should be placed not more than 0.9 m beyond the holding position marking.

5.2.10.7 The runway-holding position marking displayed at a runway/runway intersection shall be perpendicular to the center line of the runway forming part of the standard taxi-route. The pattern of the marking shall be as shown in Figure 5-8, pattern A.

## **5.2.11 Intermediate holding position marking**

### **Application and location**

5.2.11.1 An intermediate holding position marking should be displayed along an intermediate holding position.

5.2.11.2 An intermediate holding position marking should be displayed at the exit boundary of a remote de-icing/anti-icing facility adjoining a taxiway.

5.2.11.3 Where an intermediate holding position marking is displayed at an intersection of two paved taxiways, it shall be located across the taxiway at sufficient distance from the near edge of the intersecting taxiway to ensure safe clearance between taxiing aircraft. It shall be coincident with a stop bar or intermediate holding position lights, where provided.

5.2.11.4 The distance between an intermediate holding position marking at the exit boundary of a remote de-icing/ anti-icing facility and the center line of the adjoining taxiway shall not be less than the dimension specified in Table 3-1, column 11.

### **Characteristics**

5.2.11.5 An intermediate holding position marking shall consist of a single broken line as shown in Figure 5-6.

## **5.2.12 VOR aerodrome check-point marking**

### **Application**

5.2.12.1 When a VOR aerodrome check-point is established, it shall be indicated by a VOR aerodrome check-point marking and sign.

Note.— See 5.4.4 for VOR aerodrome check-point sign.

### **5.2.12.2 Site selection**

Note.— Guidance on the selection of sites for VOR aerodrome check-points is given in GACA Regulation Section 10 and ICAO Annex 10, Volume I, Attachment E.

### **Location**

5.2.12.3 A VOR aerodrome check-point marking shall be centered on the spot at which an aircraft is to be parked to receive the correct VOR signal.

### **Characteristics**

5.2.12.4 A VOR aerodrome check-point marking shall consist of a circle 6 m in diameter and have a line width of 15 cm (see Figure 5-9 (A)).

5.2.12.5 When it is preferable for an aircraft to be aligned in a specific direction, a line should be provided that passes through the center of the circle on the desired azimuth. The line should extend 6 m outside the circle in the desired direction of heading and terminate in an arrowhead. The width of the line should be 15 cm (see Figure 5-9 (B)).

5.2.12.6 A VOR aerodrome checkpoint marking should preferably be white in color but should differ from the color used for the taxiway markings.

Note.— To provide contrast, markings may be bordered with black.

## **5.2.13 Aircraft stand markings**

Note.— Guidance on the layout of aircraft stand markings is contained in the ICAO Aerodrome Design Manual, Part 4.

### **Application**

5.2.13.1 Aircraft stand markings should be provided for designated parking positions on a paved apron and on a de-icing/anti-icing facility.

### **Location**

5.2.13.2 Aircraft stand markings on a paved apron and on a de-icing/anti-icing facility should be located so as to provide the clearances specified in 3.13.6 and in 3.15.9 respectively, when the nose wheel follows the stand marking.

### **Characteristics**

5.2.13.3 Aircraft stand markings should include such elements as stand identification, lead-in line, turn bar, turning line, alignment bar, stop line and lead-out line, as are required by the parking configuration and to complement other parking aids.

5.2.13.4 An aircraft stand identification (letter and/or number) should be included in the lead-in line a short distance after the beginning of the lead-in line. The height of the identification should be adequate to be readable from the cockpit of aircraft using the stand.

5.2.13.5 Where two sets of aircraft stand markings are superimposed on each other in order to permit more flexible use of the apron and it is difficult to identify which stand marking should be followed, or safety would be impaired if the wrong marking was followed, then identification of the aircraft for which each set of markings is intended should be added to the stand identification.

Note.— Example: 2A-B747, 2B-F28.

5.2.13.6 Lead-in, turning and lead-out lines should normally be continuous in length and have a width of not less than 15 cm. Where one or more sets of stand markings are superimposed on a stand marking, the lines should be continuous for the most demanding aircraft and broken for other aircraft.

5.2.13.7 The curved portions of lead-in, turning and lead-out lines should have radii appropriate to the most demanding aircraft type for which the markings are intended.

5.2.13.8 Where it is intended that an aircraft proceed in one direction only, arrows pointing in the direction to be followed should be added as part of the lead-in and lead-out lines.

5.2.13.9 A turn bar should be located at right angles to the lead-in line, abeam the left pilot position at the point of initiation of any intended turn. It should have a length and width of not less than 6 m and 15 cm, respectively, and include an arrowhead to indicate the direction of turn.

Note.— The distances to be maintained between the turn bar and the lead-in line may vary according to different aircraft types, taking into account the pilot's field of view.

5.2.13.10 If more than one turn bar and/or stop line is required, they should be coded.

5.2.13.11 An alignment bar should be placed so as to be coincident with the extended center line of the aircraft in the specified parking position and visible to the pilot during the final part of the parking maneuver. It should have a width of not less than 15 cm.

5.2.13.12 A stop line should be located at right angles to the alignment bar, abeam the left pilot position at the intended point of stop. It should have a length and width of not less than 6 m and 15 cm, respectively.

Note.— The distances to be maintained between the stop line and the lead-in line may vary according to different aircraft types, taking into account the pilot's field of view




Figure 5-8. Runway-holding position markings




Figure 5-9. VOR aerodrome check-point marking



### 5.2.14 Apron safety lines

Note.— Guidance on apron safety lines is contained in the ICAO Aerodrome Design Manual, Part 4.

#### Application

5.2.14.1 Apron safety lines should be provided on a paved apron as required by the parking configurations and ground facilities.

#### Location

5.2.14.2 Apron safety lines shall be located so as to define the areas intended for use by ground vehicles and other aircraft servicing equipment, etc., to provide safe separation from aircraft.

#### Characteristics

5.2.14.3 Apron safety lines should include such elements as wing tip clearance lines and service road boundary lines as required by the parking configurations and ground facilities.

5.2.14.4 An apron safety line should be continuous in length and at least 10 cm in width.

### 5.2.15 Road-holding position marking

#### Application

5.2.15.1 A road-holding position marking shall be provided at all road entrances to a runway.

#### Location

5.2.15.2 The road-holding position marking shall be located across the road at the holding position.

#### Characteristics

5.2.15.3 The road-holding position marking shall be in accordance with the local road traffic regulations.

### 5.2.16 Mandatory instruction marking

Note.— Guidance on mandatory instruction marking is given in the ICAO Aerodrome Design Manual, Part 4.

#### Application

5.2.16.1 Where it is impracticable to install a mandatory instruction sign in accordance with 5.4.2.1, a mandatory instruction marking shall be provided on the surface of the pavement.

5.2.16.2 Where operationally required, such as on taxiways exceeding 60 m in width, or to assist in the prevention of a runway incursion, a mandatory instruction sign should be supplemented by a mandatory instruction marking.

5.2.16.3 The mandatory instruction marking on taxiways, where the code letter is A, B, C, or D, shall be located across the taxiway equally placed about the taxiway

centerline and on the holding side of the runway-holding position marking as shown in Figure 5-10 (a). The distance between the nearest edge of the marking and the runway holding position marking or the taxiway centre line marking shall be not less than 1 m.

#### Location

5.2.16.4 The mandatory instruction marking, on taxiways, where the code letter is E or F, shall be located on both sides of the taxiway center line marking and on the holding side of the runway-holding position marking as shown in Figure 5-10 (b). The distance between the nearest edge of the marking and the runway holding position marking or the taxiway center line marking shall be not less than 1 m.

5.2.16.5 Except where operationally required, a mandatory instruction marking should not be located on a runway.

5.2.16.6 A mandatory instruction marking shall consist of an inscription in white on a red background. Except for a NO ENTRY marking, the inscription shall provide information identical to that of the associated mandatory instruction sign.

5.2.16.7 A NO ENTRY marking shall consist of an inscription in white reading NO ENTRY on a red background.

5.2.16.8 Where there is insufficient contrast between the marking and the pavement surface, the mandatory instruction marking shall include an appropriate border, preferably white or black.

5.2.16.9 The character height should be 4 m. for inscriptions where the code letter is C, D, E or F, and 2 m where the code letter is A or B. The inscriptions should be in the form and proportions shown in Appendix 3.

5.2.16.10 The background should be rectangular and extend a minimum of 0.5 m laterally and vertically beyond the extremities of the inscription.

### 5.2.17 Information marking


Note.— Guidance on information marking is contained in the ICAO Aerodrome Design Manual (Doc 9157), Part 4.

#### Application

5.2.17.1 Where an information sign would normally be installed and is impractical to install, as determined by the appropriate authority, an information marking shall be displayed on the surface of the pavement.

5.2.17.2 Where operationally required an information sign should be supplemented by an information marking.

5.2.17.3 An information (location/ direction) marking should be displayed prior to and following complex taxiway intersections and where operational experience has indicated the addition of a taxiway location marking could assist flight crew ground navigation.



**Figure 5-10. Mandatory instruction marking**

5.2.17.4 An information (location) marking should be displayed on the pavement surface at regular intervals along taxiways of great length.

#### **Location**

5.2.17.5 The information marking should be displayed across the surface of the taxiway or apron where necessary and positioned so as to be legible from the cockpit of an approaching aircraft.

#### **Characteristics**

5.2.17.6 An information marking shall consist of:

- a. an inscription in yellow upon a black background, when it replaces or supplements a location sign; and

- b. an inscription in black upon a yellow background, when it replaces or supplements a direction or destination sign.

5.2.17.7 Where there is insufficient contrast between the marking background and the pavement surface, the marking shall include:

- a) a black border where the inscriptions are in black; and
- b) a yellow border where the inscriptions are in yellow.

5.2.17.8 The character height should be 4 m. The inscriptions should be in the form and proportions shown in Appendix 3.

## 5.3 Lights

### 5.3.1 General

#### Lights which may endanger the safety of aircraft

5.3.1.1 A non-aeronautical ground light near an aerodrome which might endanger the safety of aircraft shall be extinguished, screened or otherwise modified so as to eliminate the source of danger.

#### Laser emissions which may endanger the safety of aircraft

5.3.1.2 To protect the safety of aircraft against the hazardous effects of laser emitters, the following protected zones should be established around aerodromes:

- a laser-beam free flight zone (LFFZ)
- a laser-beam critical flight zone (LCFZ)
- a laser-beam sensitive flight zone (LSFZ).

Note 1.— Figures 5-11, 5-12 and 5-13 may be used to determine the exposure levels and distances that adequately protect flight operations.

Note 2.— The restrictions on the use of laser beams in the three protected flight zones, LFFZ, LCFZ and LSFZ, refer to visible laser beams only. Laser emitters operated by the authorities in a manner compatible with flight safety are excluded. In all navigable air space, the irradiance level of any laser beam, visible or invisible, is expected to be less than or equal to the maximum permissible exposure (MPE) unless such emission has been notified to the authority and permission obtained.

Note 3.— The protected flight zones are established in order to mitigate the risk of operating laser emitters in the vicinity of aerodromes.


Note 4.— Further guidance on how to protect flight operations from the hazardous effects of laser emitters is contained in the ICAO Manual on Laser Emitters and Flight Safety (Doc 9815).

Note 5.— See also GACA Regulation Section 11 and ICAO Annex 11 — Air Traffic Services, Chapter 2.


#### Lights which may cause confusion

5.3.1.3 A non-aeronautical ground light which, by reason of its intensity, configuration or color, might prevent, or cause confusion in, the clear interpretation of aeronautical ground lights should be extinguished, screened or otherwise modified so as to eliminate such a possibility. In particular, attention should be directed to a non-aeronautical ground light visible from the air within the areas described hereunder:


- a) Instrument runway — code number 4: within the areas before the threshold and beyond the end of the runway extending at least 4 500 m in length from the threshold and runway end and 750 m either side of the extended runway center line in width.
- b) Instrument runway — code number 2 or 3: as in a), except that the length should be at least 3 000 m.
- c) Instrument runway — code number 1; and non-instrument runway: within the approach area.



**Figure 5-11. Protected flight zone**



**Figure 5-12. Multiple runway laser-beam free flight zone**



**Figure 5-13. Protected flight zones with indication of maximum irradiance levels for visible laser beams**

## **Aeronautical ground lights which may cause confusion to mariners**

Note.— In the case of aeronautical ground lights near navigable waters, consideration needs to be given to ensuring that the lights do not cause confusion to mariners.

### **Light fixtures and supporting structures**

Note.— See 9.9 for information regarding siting of equipment and installations on operational areas, and the ICAO Aerodrome Design Manual (Doc 9157), Part 6 or guidance on frangibility of light fixtures and supporting structures.

### **Elevated approach lights**

5.3.1.4 Elevated approach lights and their supporting structures shall be frangible except that, in that portion of the approach lighting system beyond 300 m from the threshold:

- a) where the height of a supporting structure exceeds 12 m, the frangibility requirement shall apply to the top 12 m only; and
- b) where a supporting structure is surrounded by nonfrangible objects, only that part of the structure that extends above the surrounding objects shall be frangible.

5.3.1.5 The provisions of 5.3.1.4 shall not require the replacement of existing installations before 1 January 2005.

5.3.1.6 When an approach light fixture or supporting structure is not in itself sufficiently conspicuous, it shall be suitably marked

### **Elevated lights**

5.3.1.7 Elevated runway, stopway and taxiway lights shall be frangible. Their height shall be sufficiently low to preserve clearance for propellers and for the engine pods of jet aircraft.

### **Surface lights**

5.3.1.8 Light fixtures inset in the surface of runways, stopways, taxiways and aprons shall be so designed and fitted as to withstand being run over by the wheels of an aircraft without damage either to the aircraft or to the lights themselves.

5.3.1.9 The temperature produced by conduction or radiation at the interface between an installed inset light and an aircraft tire should not exceed 160°C during a 10-minute period of exposure.

Note.— Guidance on measuring the temperature of inset lights is given in the ICAO Aerodrome Design Manual, Part 4.

### **Light intensity and control**

Note.— In dusk or poor visibility conditions by day, lighting can be more effective than marking. For lights to be effective in such conditions or in poor visibility by night, they must be of adequate intensity. To obtain the required intensity, it will usually be necessary to make the light directional, in which case the arcs over which the light shows will have to be adequate and so orientated as to meet the operational requirements. The runway lighting system will have to be considered as a whole, to ensure that the relative light intensities are suitably matched to the same end. (See Attachment A, GACA Regulation Section 14, and the ICAO Aerodrome Design Manual, Part 4.)

5.3.1.10 The intensity of runway lighting shall be adequate for the minimum conditions of visibility and ambient light in which use of the runway is intended, and compatible with that of the nearest section of the approach lighting system when provided.

Note.— While the lights of an approach lighting system may be of higher intensity than the runway lighting, it is good practice to avoid abrupt changes in intensity as these could give a pilot a false impression that the visibility is changing during approach.

5.3.1.11 Where a high-intensity lighting system is provided, a suitable intensity control shall be incorporated to allow for adjustment of the light intensity to meet the prevailing conditions. Separate intensity controls or other suitable methods shall be provided to ensure that the following systems, when installed, can be operated at compatible intensities:

- approach lighting system;
- runway edge lights;
- runway threshold lights;
- runway end lights;
- runway center line lights;
- runway touchdown zone lights; and
- taxiway center line lights.

5.3.1.12 On the perimeter of and within the ellipse defining the main beam in Appendix 2, Figures A2-1 to A2-10, the maximum light intensity value shall not be greater than three times the minimum light intensity value measured in accordance with Appendix 2, collective notes for Figures A2-1 to A2-11, Note 2.

5.3.1.13 On the perimeter of and within the rectangle defining the main beam in Appendix 2, Figures A2-12 to A2-20, the maximum light intensity value shall not be greater than three times the minimum light intensity value



measured in accordance with Appendix 2, collective notes for Figures A2-12 to A2-21, Note 2.

### 5.3.2 Emergency lighting

#### Application

5.3.2.1 At an aerodrome provided with runway lighting and without a secondary power supply, sufficient emergency lights should be conveniently available for installation on at least the primary runway in the event of failure of the normal lighting system.

Note.— Emergency lighting may also be useful to mark obstacles or delineate taxiways and apron areas.

#### Location

5.3.2.2 When installed on a runway the emergency lights should, as a minimum, conform to the configuration required for a non-instrument runway.

#### Characteristics

5.3.2.3 The color of the emergency lights should conform to the color requirements for runway lighting, except that, where the provision of colored lights at the threshold and the runway end is not practicable, all lights may be variable white or as close to variable white as practicable.

### 5.3.3 Aeronautical beacons

#### Application

5.3.3.1 Where operationally necessary an aerodrome beacon or an identification beacon shall be provided at each aerodrome intended for use at night.

5.3.3.2 The operational requirement shall be determined having regard to the requirements of the air traffic using the aerodrome, the conspicuity of the aerodrome features in relation to its surroundings and the installation of other visual and non-visual aids useful in locating the aerodrome.

#### Aerodrome beacon

5.3.3.3 An aerodrome beacon shall be provided at an aerodrome intended for use at night if one or more of the following conditions exist:

- a) aircraft navigate predominantly by visual means;
- b) reduced visibilities are frequent; or
- c) it is difficult to locate the aerodrome from the air due to surrounding lights or terrain.

#### Location

5.3.3.4 The aerodrome beacon shall be located on or adjacent to the aerodrome in an area of low ambient background lighting.

5.3.3.5 The location of the beacon should be such that the beacon is not shielded by objects in significant directions and does not dazzle a pilot approaching to land.

#### Characteristics

5.3.3.6 The aerodrome beacon shall show either colored flashes alternating with white flashes, or white flashes only. The frequency of total flashes shall be from 20 to 30 per minute. Where used, the colored flashes emitted by beacons at land aerodromes shall be green and colored flashes emitted by beacons at water aerodromes shall be yellow. In the case of a combined water and land aerodrome, colored flashes, if used, shall have the color characteristics of whichever section of the aerodrome is designated as the principal facility.

5.3.3.7 The light from the beacon shall show at all angles of azimuth. The vertical light distribution shall extend upwards from an elevation of not more than 1° to an elevation determined by the appropriate authority to be sufficient to provide guidance at the maximum elevation at which the beacon is intended to be used and the effective intensity of the flash shall be not less than 2 000 cd.

Note.— At locations where a high ambient background lighting level cannot be avoided, the effective intensity of the flash may be required to be increased by a factor up to a value of 10.

#### Identification beacon

#### Application

5.3.3.8 An identification beacon shall be provided at an aerodrome which is intended for use at night and cannot be easily identified from the air by other means.

#### Location

5.3.3.9 The identification beacon shall be located on the aerodrome in an area of low ambient background lighting.

5.3.3.10 The location of the beacon should be such that the beacon is not shielded by objects in significant directions and does not dazzle a pilot approaching to land.

#### Characteristics

5.3.3.11 An identification beacon at a land aerodrome shall show at all angles of azimuth. The vertical light distribution shall extend upwards from an elevation of not more than 1° to an elevation determined by the appropriate authority to be sufficient to provide guidance at the maximum elevation at which the beacon is intended to be used and the effective intensity of the flash shall be not less than 2 000 cd.

Note.— At locations where a high ambient background lighting level cannot be avoided, the effective intensity of the flash may be required to be increased by a factor up to a value of 10.

5.3.3.12 An identification beacon shall show flashing green at a land aerodrome and flashing-yellow at a water aerodrome.

5.3.3.13 The identification characters shall be transmitted in the International Morse Code.

5.3.3.14 The speed of transmission should be between six and eight words per minute, the corresponding range of duration of the Morse dots being from 0.15 to 0.2 seconds per dot.

### 5.3.4 Approach lighting systems

Note.— It is intended that existing lighting systems not conforming to the specifications in 5.3.4.21, 5.3.4.39, 5.3.9.10, 5.3.10.10, 5.3.10.11, 5.3.11.5, 5.3.12.8, 5.3.13.6 and 5.3.16.8 be replaced not later than 1 January 2005.

#### Application

##### 5.3.4.1 Application

###### A.— Non-instrument runway

Where physically practicable, a simple approach lighting system as specified in 5.3.4.2 to 5.3.4.9 should be provided to serve a non-instrument runway where the code number is 3 or 4 and intended for use at night, except when the runway is used only in conditions of good visibility, and sufficient guidance is provided by other visual aids.

Note.— A simple approach lighting system can also provide visual guidance by day.

###### B.— Non-precision approach runway

Where physically practicable, a simple approach lighting system as specified in 5.3.4.2 to 5.3.4.9 shall be provided to serve a non-precision approach runway, except when the runway is used only in conditions of good visibility or sufficient guidance is provided by other visual aids.

Note.— It is advisable to give consideration to the installation of a precision approach category I lighting system or to the addition of a runway lead-in lighting system.

###### C.— Precision approach runway category I

Where physically practicable, a precision approach category I lighting system as specified in 5.3.4.10 to 5.3.4.21 shall be provided to serve a precision approach runway category I.

###### D.— Precision approach runway categories II and III

A precision approach category II and III lighting system as specified in 5.3.4.22 to 5.3.4.39 shall be provided to serve a precision approach runway category II or III.

#### Simple approach lighting system Location

5.3.4.2 A simple approach lighting system shall consist of a row of lights on the extended center line of the runway extending, whenever possible, over a distance of not less than 420 m from the threshold with a row of lights forming a crossbar 18 m or 30 m in length at a distance of 300 m from the threshold.

5.3.4.3 The lights forming the crossbar shall be as nearly as practicable in a horizontal straight line at right angles to, and bisected by, the line of the center line lights. The lights of the crossbar shall be spaced so as to produce a linear effect, except that, when a crossbar of 30 m is used, gaps may be left on each side of the center line. These gaps shall be kept to a minimum to meet local requirements and each shall not exceed 6 m.

Note 1.— Spacings for the crossbar lights between 1 m and 4 m are in use. Gaps on each side of the center line may improve directional guidance when approaches are made with a lateral error, and facilitate the movement of rescue and fire fighting vehicles.

Note 2.— See Attachment A, Section 11 for guidance on installation tolerances.

5.3.4.4 The lights forming the center line shall be placed at longitudinal intervals of 60 m, except that, when it is desired to improve the guidance, an interval of 30 m may be used. The innermost light shall be located either 60 m or 30 m from the threshold, depending on the longitudinal interval selected for the center line lights.

5.3.4.5 If it is not physically possible to provide a center line extending for a distance of 420 m from the threshold, it should be extended to 300 m so as to include the crossbar. If this is not possible, the center line lights should be extended as far as practicable, and each center line light should then consist of a barrette at least 3 m in length. Subject to the approach system having a crossbar at 300 m from the threshold, an additional crossbar may be provided at 150 m from the threshold.

5.3.4.6 The system shall lie as nearly as practicable in the horizontal plane passing through the threshold, provided that:

- a) no object other than an ILS or MLS azimuth antenna shall protrude through the plane of the approach lights within a distance of 60 m from the center line of the system; and
- b) no light other than a light located within the central part of a crossbar or a center line barrette (not their extremities) shall be screened from an approaching aircraft. Any ILS or MLS azimuth antenna protruding through the plane of the lights shall be treated as an obstacle and marked and lighted accordingly.

### Characteristics

5.3.4.7 The lights of a simple approach lighting system shall be fixed lights and the color of the lights shall be such as to ensure that the system is readily distinguishable from other aeronautical ground lights, and from extraneous lighting if present. Each center line light shall consist of either:

- a) a single source; or
- b) a barrette at least 3 m in length.

Note 1.— When the barrette as in b) is composed of lights approximating to point sources, a spacing of 1.5 m between adjacent lights in the barrette has been found satisfactory.

Note 2.— It may be advisable to use barrettes 4 m in length if it is anticipated that the simple approach lighting system will be developed into a precision approach lighting system.

Note 3.— At locations where identification of the simple approach lighting system is difficult at night due to surrounding lights, sequence flashing lights installed in the outer portion of the system may resolve this problem.

5.3.4.8 Where provided for a noninstrument runway, the lights should show at all angles in azimuth necessary to a pilot on base leg and final approach. The intensity of the lights should be adequate for all conditions of visibility and ambient light for which the system has been provided.

5.3.4.9 Where provided for a nonprecision approach runway, the lights should show at all angles in azimuth necessary to the pilot of an aircraft which on final approach does not deviate by an abnormal amount from the path defined by the non-visual aid. The lights should be designed to provide guidance during both day and night in the most adverse conditions of visibility and ambient light for which it is intended that the system should remain usable.

### Precision approach category I lighting system Location

5.3.4.10 A precision approach category I lighting system shall consist of a row of lights on the extended center line of the runway extending, wherever possible, over a distance of 900 m from the runway threshold with a row of lights forming a crossbar 30 m in length at a distance of 300 m from the runway threshold.

Note.— The installation of an approach lighting system of less than 900 m in length may result in operational limitations on the use of the runway. See Attachment A, Section 11.

5.3.4.11 The lights forming the crossbar shall be as nearly as practicable in a horizontal straight line at right angles

to, and bisected by, the line of the center line lights. The lights of the crossbar shall be spaced so as to produce a linear effect, except that gaps may be left on each side of the center line. These gaps shall be kept to a minimum to meet local requirements and each shall not exceed 6 m.

Note 1.— Spacings for the crossbar lights between 1 m and 4 m are in use. Gaps on each side of the center line may improve directional guidance when approaches are made with a lateral error, and facilitate the movement of rescue and fire fighting vehicles.

Note 2.— See Attachment A, Section 11 for guidance on installation tolerances.

5.3.4.12 The lights forming the center line shall be placed at longitudinal intervals of 30 m with the innermost light located 30 m from the threshold.

5.3.4.13 The system shall lie as nearly as practicable in the horizontal plane passing through the threshold, provided that:

- a) no object other than an ILS or MLS azimuth antenna shall protrude through the plane of the approach lights within a distance of 60 m from the center line of the system; and
- b) no light other than a light located within the central part of a crossbar or a center line barrette (not their extremities) shall be screened from an approaching aircraft. Any ILS or MLS azimuth antenna protruding through the plane of the lights shall be treated as an obstacle and marked and lighted accordingly.

### Characteristics

5.3.4.14 The center line and crossbar lights of a precision approach category I lighting system shall be fixed lights showing variable white. Each center line light position shall consist of either:

- a) a single light source in the innermost 300 m of the center line, two light sources in the central 300 m of the center line and three light sources in the outer 300 m of the center line to provide distance information; or
- b) a barrette.

5.3.4.15 Where the serviceability level of the approach lights specified as a maintenance objective in 10.4.10 can be demonstrated, each center line light position may consist of either:

- a. a single light source; or
- b. a barrette.

5.3.4.16 The barrettes shall be at least 4 m in length. When barrettes are composed of lights approximating to

point sources, the lights shall be uniformly spaced at intervals of not more than 1.5 m.

5.3.4.17 If the center line consists of barrettes as described in 5.3.4.14 b) or 5.3.4.15 b), each barrette should be supplemented by a capacitor discharge light, except where such lighting is considered unnecessary taking into account the characteristics of the system and the nature of the meteorological conditions.

5.3.4.18 Each capacitor discharge light as described in 5.3.4.17 shall be flashed twice a second in sequence, beginning with the outermost light and progressing toward the threshold to the innermost light of the system. The design of the electrical circuit shall be such that these lights can be operated independently of the other lights of the approach lighting system.

5.3.4.19 If the center line consists of lights as described in 5.3.4.14 a) or 5.3.4.15 a), additional crossbars of lights to the crossbar provided at 300 m from the threshold shall be provided at 150 m, 450 m, 600 m and 750 m from the threshold. The lights forming each crossbar shall be as nearly as practicable in a horizontal straight line at right angles to, and bisected by, the line of the center line lights. The lights shall be spaced so as to produce a linear effect, except that gaps may be left on each side of the center line. These gaps shall be kept to a minimum to meet local requirements and each shall not exceed 6 m.

Note.— See Attachment A, Section 11 for detailed configuration.

5.3.4.20 Where the additional crossbars described in 5.3.4.19 are incorporated in the system, the outer ends of the crossbars shall lie on two straight lines that either are parallel to the line of the center line lights or converge to meet the runway center line 300 m from threshold.

5.3.4.21 The lights shall be in accordance with the specifications of Appendix 2, Figure A2-1.

Note.— The flight path envelopes used in the design of these lights are given in Attachment A, Figure A-4.

## Precision approach category II and III lighting system

### Location

5.3.4.22 The approach lighting system shall consist of a row of lights on the extended center line of the runway, extending, wherever possible, over a distance of 900 m from the runway threshold. In addition, the system shall have two side rows of lights, extending 270 m from the threshold, and two crossbars, one at 150 m and one at 300 m from the threshold, all as shown in Figure 5-13. Where the serviceability level of the approach lights specified as maintenance objectives in 10.4.7 can be demonstrated, the system may have two side rows of lights, extending 240 m from the threshold, and two crossbars, one at 150 m and one at 300 m from the threshold, all as shown in Figure 5-14.

Note.— The length of 900 m is based on providing guidance for operations under category I, II and III conditions. Reduced lengths may support category II and III operations but may impose limitations on category I operations. See Attachment A, Section 11.

5.3.4.23 The lights forming the center line shall be placed at longitudinal intervals of 30 m with the innermost lights located 30 m from the threshold.

5.3.4.24 The lights forming the side rows shall be placed on each side of the center line, at a longitudinal spacing equal to that of the center line lights and with the first light located 30 m from the threshold. Where the serviceability level of the approach lights specified as maintenance objectives in 10.4.7 can be demonstrated, lights forming the side rows may be placed on each side of the center line, at a longitudinal spacing of 60 m with the first light located 60 m from the threshold.

The lateral spacing (or gauge) between the innermost lights of the side rows shall be not less than 18 m nor more than 22.5 m, and preferably 18 m, but in any event shall be equal to that of the touchdown zone lights.





Figure 5-14. Inner 300m approach and runway lighting for precision approach runways categories II and III





**Figure 5-15. Inner 300m approach and runway lighting for precision approach runways categories II and III where the serviceability levels for the lights specified as maintenance objectives in Chapter 10 can be demonstrated**



5.3.4.25 The crossbar provided at 150 m from the threshold shall fill in the gaps between the center line and side row lights.

5.3.4.26 The crossbar provided at 300 m from the threshold shall extend on both sides of the center line lights to a distance of 15 m from the center line.

5.3.4.27 If the center line beyond a distance of 300 m from the threshold consists of lights as described in 5.3.4.31 b) or 5.3.4.32 b), additional crossbars of lights shall be provided at 450 m, 600 m and 750 m from the threshold.

5.3.4.28 Where the additional crossbars described in 5.3.4.27 are incorporated in the system, the outer ends of these crossbars shall lie on two straight lines that either are parallel to the center line or converge to meet the runway center line 300 m from the threshold.

5.3.4.29 The system shall lie as nearly as practicable in the horizontal plane passing through the threshold, provided that:

- a) no object other than an ILS or MLS azimuth antenna shall protrude through the plane of the approach lights within a distance of 60 m from the center line of the system; and
- b) no light other than a light located within the central part of a crossbar or a center line barrette (not their extremities) shall be screened from an approaching aircraft. Any ILS or MLS azimuth antenna protruding through the plane of the lights shall be treated as an obstacle and marked and lighted accordingly.

#### Characteristics

5.3.4.30 The center line of a precision approach category II and III lighting system for the first 300 m from the threshold shall consist of barrettes showing variable white, except that, where the threshold is displaced 300 m or more, the center line may consist of single light sources showing variable white.

Where the serviceability level of the approach lights specified as maintenance objectives in 10.4.7 can be demonstrated, the center line of a precision approach category II and III lighting system for the first 300 m from the threshold may consist of either:

- a) barrettes, where the center line beyond 300 m from the threshold consists of barrettes as described in 5.3.4.32 a); or
- b) alternate single light sources and barrettes, where the center line beyond 300 m from the threshold consists of single light sources as described in 5.3.4.32 b), with the innermost single light source located 30 m and the innermost barrette located 60 m from the threshold; or c) single light sources

where the threshold is displaced 300 m or more; all of which shall show variable white.

5.3.4.31 Beyond 300 m from the threshold each center line light position shall consist of either:

- a) a barrette as used on the inner 300 m; or
- b) two light sources in the central 300 m of the center line and three light sources in the outer 300 m of the center line; all of which shall show variable white.

5.3.4.32 Where the serviceability level of the approach lights specified as maintenance objectives in 10.4.7 can be demonstrated, beyond 300 m from the threshold each center line light position may consist of either:

- a) a barrette; or
- b) a single light source; all of which shall show variable white.

5.3.4.33 The barrettes shall be at least 4 m in length. When barrettes are composed of lights approximating to point sources, the lights shall be uniformly spaced at intervals of not more than 1.5 m.

5.3.4.34 If the center line beyond 300 m from the threshold consists of barrettes as described in 5.3.4.31 a) or 5.3.4.32 a), each barrette beyond 300 m should be supplemented by a capacitor discharge light, except where such lighting is considered unnecessary taking into account the characteristics of the system and the nature of the meteorological conditions.

5.3.4.35 Each capacitor discharge light shall be flashed twice a second in sequence, beginning with the outermost light and progressing toward the threshold to the innermost light of the system. The design of the electrical circuit shall be such that these lights can be operated independently of the other lights of the approach lighting system.

5.3.4.36 The side row shall consist of barrettes showing red. The length of a side row barrette and the spacing of its lights shall be equal to those of the touchdown zone light barrettes.

5.3.4.37 The lights forming the crossbars shall be fixed lights showing variable white. The lights shall be uniformly spaced at intervals of not more than 2.7 m.

5.3.4.38 The intensity of the red lights shall be compatible with the intensity of the white lights.

5.3.4.39 The lights shall be in accordance with the specifications of Appendix 2, Figures A2-1 and A2-2.

Note.— The flight path envelopes used in the design of these lights are given in Attachment A, Figure A-4.

### 5.3.5 Visual approach slope indicator systems

#### Application

5.3.5.1 A visual approach slope indicator system shall be provided to serve the approach to a runway whether or not the runway is served by other visual approach aids or by non visual aids, where one or more of the following conditions exist:

- a) the runway is used by turbojet or other aeroplanes with similar approach guidance requirements;
- b) the pilot of any type of aeroplane may have difficulty in judging the approach due to:
  1. inadequate visual guidance such as is experienced during an approach over water or featureless terrain by day or in the absence of sufficient extraneous lights in the approach area by night, or
  2. misleading information such as is produced by deceptive surrounding terrain or runway slopes;
- c) the presence of objects in the approach area may involve serious hazard if an aeroplane descends below the normal approach path, particularly if there are no non-visual or other visual aids to give warning of such objects;
- d) physical conditions at either end of the runway present a serious hazard in the event of an aeroplane undershooting or overrunning the runway; and
- e) terrain or prevalent meteorological conditions are such that the aeroplane may be subjected to unusual turbulence during approach.

Note.— Guidance on the priority of installation of visual approach slope indicator systems is contained in Attachment A, Section 12.

5.3.5.2 The standard visual approach slope indicator systems shall consist of the following:

- a) T-VASIS and AT-VASIS conforming to the specifications contained in 5.3.5.6 to 5.3.5.22 inclusive;
- b) PAPI and APAPI systems conforming to the specifications contained in 5.3.5.23 to 5.3.5.40 inclusive;

as shown in Figure 5-15.

5.3.5.3 PAPI, T-VASIS or AT-VASIS shall be provided where the code number is 3 or 4 when one or more of the conditions specified in 5.3.5.1 exist.

5.3.5.4 PAPI or APAPI shall be provided where the code number is 1 or 2 when one or more of the conditions specified in 5.3.5.1 exist.

5.3.5.5 Where a runway threshold is temporarily displaced from the normal position and one or more of the

conditions specified in 5.3.5.1 exist, a PAPI should be provided except that where the code number is 1 or 2 an APAPI may be provided.

#### T-VASIS and AT-VASIS


#### Description

5.3.5.6 The T-VASIS shall consist of twenty light units symmetrically disposed about the runway center line in the form of two wing bars of four light units each, with bisecting longitudinal lines of six lights, as shown in Figure 5-16.

5.3.5.7 The AT-VASIS shall consist of ten light units arranged on one side of the runway in the form of a single wing bar of four light units with a bisecting longitudinal line of six lights.

5.3.5.8 The light units shall be constructed and arranged in such a manner that the pilot of an aeroplane during an approach will:

- a) when above the approach slope, see the wing bar(s) white, and one, two or three fly-down lights, the more flydown lights being visible the higher the pilot is above the approach slope;
- b) when on the approach slope, see the wing bar(s) white; and
- c) when below the approach slope, see the wing bar(s) and one, two or three fly-up lights white, the more fly-up lights being visible the lower the pilot is below the approach slope; and when well below the approach slope, see the wing bar(s) and the three fly-up lights red. When on or above the approach slope, no light shall be visible from the fly-up light units; when on or below the approach slope, no light shall be visible from the fly-down light units.



**Figure 5-16 Visual approach slope indicator systems**

## Siting

5.3.5.9 The light units shall be located as shown in Figure 5-16, subject to the installation tolerances given therein.

Note.— The siting of T-VASIS will provide, for a 3° slope and a nominal eye height over the threshold of 15 m (see 5.3.5.6 and 5.3.5.19), a pilot's eye height over threshold of 13 m to 17 m when only the wing bar lights are visible. If increased eye height at the threshold is required (to provide adequate wheel clearance), then the approaches may be flown with one or more fly-down lights visible. The pilot's eye height over the threshold is then of the following order:

Wing bar lights and one fly-down light visible	17 m to 22 m
Wing bar lights and two fly-down lights visible	22 m to 28 m
Wing bar lights and three fly-down lights visible	28 m to 54 m

### Characteristics of the light units

5.3.5.10 The systems shall be suitable for both day and night operations.

5.3.5.11 The light distribution of the beam of each light unit shall be of fan shape showing over a wide arc in azimuth in the approach direction. The wing bar light units shall produce a beam of white light from 1°54' vertical angle up to 6° vertical angle and a beam of red light from 0° to 1°54' vertical angle. The fly-down light units shall produce a white beam extending from an elevation of 6° down to approximately the approach slope, where it shall have a sharp cut-off. The fly-up light units shall produce a white beam from approximately the approach slope down to 1°54' vertical angle and a red beam below a 1°54' vertical angle. The angle of the top of the red beam in the wing bar units and fly-up units may be increased to comply with 5.3.5.21.

5.3.5.12 The light intensity distribution of the fly-down, wing bar and fly-up light units shall be as shown in Appendix 2, Figure A2-22.

5.3.5.13 The color transition from red to white in the vertical plane shall be such as to appear to an observer, at a distance of not less than 300 m, to occur over a vertical angle of not more than 15'.

5.3.5.14 At full intensity the red light shall have a Y coordinate not exceeding 0.320.

5.3.5.15 A suitable intensity control shall be provided to allow adjustments to meet the prevailing conditions and to avoid dazzling the pilot during approach and landing.

5.3.5.16 The light units forming the wing bars, or the light units forming a fly-down or a fly-up matched pair, shall be mounted so as to appear to the pilot of an approaching aeroplane to be substantially in a horizontal line. The light units shall be mounted as low as possible and shall be frangible.

5.3.5.17 The light units shall be so designed that deposits of condensation, dirt, etc., on optically transmitting or reflecting surfaces shall interfere to the least possible extent with the light signals and shall in no way affect the elevation of the beams or the contrast between the red and white signals. The construction of the light units shall be such as to minimize the probability of the slots being wholly or partially blocked by snow or ice where these conditions are likely to be encountered.


### Approach slope and elevation setting of light beams

5.3.5.18 The approach slope shall be appropriate for use by the aeroplanes using the approach.

5.3.5.19 When the runway on which a T-VASIS is provided is equipped with an ILS and/or MLS, the siting and elevations of the light units shall be such that the visual approach slope conforms as closely as possible with the glide path of the ILS and/or the minimum glide path of the MLS, as appropriate.


5.3.5.20 The elevation of the beams of the wing bar light units on both sides of the runway shall be the same. The elevation of the top of the beam of the fly-up light unit nearest to each wing bar, and that of the bottom of the beam of the flydown light unit nearest to each wing bar, shall be equal and shall correspond to the approach slope. The cut-off angle of the top of the beams of successive fly-up light units shall decrease by 5' of arc in angle of elevation at each successive unit away from the wing bar. The cut-in angle of the bottom of the beam of the fly-down light units shall increase by 7' of arc at each successive unit away from the wing bar (see Figure 5-17).

5.3.5.21 The elevation setting of the top of the red light beams of the wing bar and fly-up light units shall be such that, during an approach, the pilot of an aeroplane to whom the wing bar and three fly-up light units are visible would clear all objects in the approach area by a safe margin if any such light did not appear red.



**Figure 5-17 Siting of light units for T-VASIS**





**Figure 5-18. Light beams and elevation settings of T-VASIS and AT-VASIS**

Location and dimensions (1)	Landing distance available			
	Less than 800m (2)	800 m up to but not including 1200m (3)	1 200 m up to but not including 2400m (4)	2400m and above (5)
Distance from threshold to beginning of marking	<b>150m</b>	<b>250m</b>	<b>300m</b>	<b>400m</b>
Length of stripe (a)	<b>30-45m</b>	<b>30-45m</b>	<b>45-60m</b>	<b>45-60m</b>
Width of stripe	<b>4m (c)</b>	<b>6m</b>	<b>6-10m (b)</b>	<b>6-10m (b)</b>
Lateral spacing between inner sides of stripes	<b>6m (c)</b>	<b>9m (c)</b>	<b>18-22.5m</b>	<b>18-22.5m</b>

- a. The greater dimensions of the specified ranges are intended to be used where increased conspicuity is required.
- b. The lateral spacing may be varied within these limits to minimize the contamination of the marking by rubber deposits.
- c. These figures were deduced by reference to the outer main gear wheel span which is element 2 of the aerodrome reference code at Chapter 1, Table 1-1.



5.3.5.22 The azimuth spread of the light beam shall be suitably restricted where an object located outside the obstacle protection surface of the system, but within the lateral limits of its light beam, is found to extend above the plane of the obstacle protection surface and an aeronautical study indicates that the object could adversely affect the safety of operations. The extent of the restriction shall be such that the object remains outside the confines of the light beam.

## **PAPI and APAPI**

### **Description**

5.3.5.23 The PAPI system shall consist of a wing bar of 4 sharp transition multi-lamp (or paired single lamp) units equally spaced. The system shall be located on the left side of the runway unless it is physically impracticable to do so.

Note.— Where a runway is used by aircraft requiring visual roll guidance which is not provided by other external means, then a second wing bar may be provided on the opposite side of the runway.

5.3.5.24 The APAPI system shall consist of a wing bar of 2 sharp transition multi-lamp (or paired single lamp) units. The system shall be located on the left side of the runway unless it is physically impracticable to do so.

Note.— Where a runway is used by aircraft requiring visual roll guidance which is not provided by other external means, then a second wing bar may be provided on the opposite side of the runway.

5.3.5.25 The wing bar of a PAPI shall be constructed and arranged in such a manner that a pilot making an approach will:

- a) when on or close to the approach slope, see the two units nearest the runway as red and the two units farthest from the runway as white;
- b) when above the approach slope, see the one unit nearest the runway as red and the three units farthest from the runway as white; and when further above the approach slope, see all the units as white; and
- c) when below the approach slope, see the three units nearest the runway as red and the unit farthest from the runway as white; and when further below the approach slope, see all the units as red.

5.3.5.26 The wing bar of an APAPI shall be constructed and arranged in such a manner that a pilot making an approach will:

- a) when on or close to the approach slope, see the unit nearer the runway as red and the unit farther from the runway as white;

- b) when above the approach slope, see both the units as white; and
- c) when below the approach slope, see both the units as red.

### **Siting**

5.3.5.27 The light units shall be located as in the basic configuration illustrated in Figure 5-18, subject to the installation tolerances given therein. The units forming a wing bar shall be mounted so as to appear to the pilot of an approaching aeroplane to be substantially in a horizontal line. The light units shall be mounted as low as possible and shall be frangible.

### **Characteristics of the light units**

5.3.5.28 The system shall be suitable for both day and night operations.

5.3.5.29 The color transition from red to white in the vertical plane shall be such as to appear to an observer, at a distance of not less than 300 m, to occur within a vertical angle of not more than 3'.

5.3.5.30 At full intensity the red light shall have a Y coordinate not exceeding 0.320.


5.3.5.31 The light intensity distribution of the light units shall be as shown in Appendix 2, Figure A2-23.

Note.— See the ICAO Aerodrome Design Manual, Part 4 for additional guidance on the characteristics of light units.


5.3.5.32 Suitable intensity control shall be provided so as to allow adjustment to meet the prevailing conditions and to avoid dazzling the pilot during approach and landing.

5.3.5.33 Each light unit shall be capable of adjustment in elevation so that the lower limit of the white part of the beam may be fixed at any desired angle of elevation between 1°30' and at least 4°30' above the horizontal.

5.3.5.34 The light units shall be so designed that deposits of condensation, snow, ice, dirt, etc., on optically transmitting or reflecting surfaces shall interfere to the least possible extent with the light signals and shall not affect the contrast between the red and white signals and the elevation of the transition sector.




**Figure 5-19. Siting of PAPI and APAPI**



The height of the pilot's eye above the aircraft's ILS glide path/MLS antenna varies with the type of aeroplane and approach attitude. Harmonization of the PAPI signal and ILS glide path and/or MLS minimum glide path to a point closer to the threshold may be achieved by increasing the on-course sector from 20° to 30°. The setting angles for a 3° glide slope would then be 2°25', 2°45', 3°15' and 3°35'.

A—3° PAPI ILLUSTRATED



B—3° APAPI ILLUSTRATED

**Figure 5-20. Light beams and angle of elevation setting of PAPI and APAPI**

Table 5-2. Wheel clearance over threshold for PAPI and APAPI

Eye-to-wheel height of aeroplane in the approach configuration <sup>a</sup>	Desired wheel clearance (metres) <sup>b,c</sup>	Minimum wheel clearance (metres) <sup>d</sup>
(1)	(2)	(3)
up to but not including 3 m	6	3 <sup>e</sup>
3 m up to but not including 5 m	9	4
5 m up to but not including 8 m	9	5
8 m up to but not including 14 m	9	6

a. In selecting the eye-to-wheel height group, only aeroplanes meant to use the system on a regular basis shall be considered. The most demanding amongst such aeroplanes shall determine the eye-to-wheel height group.

b. Where practicable the desired wheel clearances shown in column (2) shall be provided.

c. The wheel clearances in column (2) may be reduced to no less than those in column (3) where an aeronautical study indicates that such reduced wheel clearances are acceptable.

d. When a reduced wheel clearance is provided at a displaced threshold it shall be ensured that the corresponding desired wheel clearance specified in column (2) will be available when an aeroplane at the top end of the eye-to-wheel height group chosen overflies the extremity of the runway.

e. This wheel clearance may be reduced to 1.5 m on runways used mainly by light-weight non-turbo-jet aeroplanes.

Table 5-3. Dimensions and slopes of the obstacle protection surface

Surface dimensions	Runway type/code number							
	Non-instrument				Instrument			
	Code number				Code number			
	1	2	3	4	1	2	3	4
Length of inner edge	60 m	80 m <sup>a</sup>	150 m	150 m	150 m	150 m	300 m	300 m
Distance from threshold	30 m	60 m	60 m	60 m	60 m	60 m	60 m	60 m
Divergence (each side)	10%	10%	10%	10%	15%	15%	15%	15%
Total length	7 500 m	7 500 m <sup>b</sup>	15 000 m	15 000 m	7 500 m	7 500 m <sup>b</sup>	15 000 m	15 000 m
<i>Slope</i>								
a) T-VASIS and AT-VASIS	— <sup>c</sup>	1.9°	1.9°	1.9°	—	1.9°	1.9°	1.9°
b) PAPI <sup>d</sup>	—	A-0.57°	A-0.57°	A-0.57°	A-0.57°	A-0.57°	A-0.57°	A-0.57°
c) APAPI <sup>d</sup>	A-0.9°	A-0.9°	—	—	A-0.9°	A-0.9°	—	—

a. This length is to be increased to 150 m for a T-VASIS or AT-VASIS.

b. This length is to be increased to 15 000 m for a T-VASIS or AT-VASIS.

c. No slope has been specified if a system is unlikely to be used on runway type/code number indicated.

d. Angles as indicated in Figure 5-19.

### **Approach slope and elevation setting of light units**

5.3.5.35 The approach slope as defined in Figure 5-19 shall be appropriate for use by the aeroplanes using the approach.

5.3.5.36 When the runway is equipped with an ILS and/or MLS, the siting and the angle of elevation of the light units shall be such that the visual approach slope conforms as closely as possible with the glide path of the ILS and/or the minimum glide path of the MLS, as appropriate.

5.3.5.37 The angle of elevation settings of the light units in a PAPI wing bar shall be such that, during an approach, the pilot of an aeroplane observing a signal of one white and three reds will clear all objects in the approach area by a safe margin.

5.3.5.38 The angle of elevation settings of the light units in an APAPI wing bar shall be such that, during an approach, the pilot of an aeroplane observing the lowest onslope signal, i.e. one white and one red, will clear all objects in the approach area by a safe margin.

5.3.5.39 The azimuth spread of the light beam shall be suitably restricted where an object located outside the obstacle protection surface of the PAPI or APAPI system, but within the lateral limits of its light beam, is found to extend above the plane of the obstacle protection surface and an aeronautical study indicates that the object could adversely affect the safety of operations. The extent of the restriction shall be such that the object remains outside the confines of the light beam

Note.— See 5.3.5.41 to 5.3.5.45 concerning the related obstacle protection surface.

5.3.5.40 Where wing bars are installed on each side of the runway to provide roll guidance, corresponding units shall be set at the same angle so that the signals of each wing bar change symmetrically at the same time.

### **Obstacle protection surface**

Note.— The following specifications apply to T-VASIS, AT-VASIS, PAPI and APAPI.

5.3.5.41 An obstacle protection surface shall be established when it is intended to provide a visual approach slope indicator system.

5.3.5.42 The characteristics of the obstacle protection surface, i.e. origin, divergence, length and slope shall correspond to those specified in the relevant column of Table 5-3 and in Figure 5-20.

5.3.5.43 New objects or extensions of existing objects shall not be permitted above an obstacle protection surface except when, in the opinion of the appropriate authority, the new object or extension would be shielded by an existing immovable object.

Note.— Circumstances in which the shielding principle may reasonably be applied are described in the ICAO Airport Services Manual, Part 6.

5.3.5.44 Existing objects above an obstacle protection surface shall be removed except when, in the opinion of the appropriate authority, the object is shielded by an existing immovable object, or after aeronautical study it is determined that the object would not adversely affect the safety of operations of aeroplanes.

5.3.5.45 Where an aeronautical study indicates that an existing object extending above an obstacle protection surface could adversely affect the safety of operations of aeroplanes one or more of the following measures shall be taken:

- a) suitably raise the approach slope of the system;
- b) reduce the azimuth spread of the system so that the object is outside the confines of the beam;
- c) displace the axis of the system and its associated obstacle protection surface by no more than 5°;
- d) suitably displace the threshold; and
- e) where d) is found to be impracticable, suitably displace the system upwind of the threshold to provide an increase in threshold crossing height equal to the height of the object penetration.


Note.— Guidance on this issue is contained in the ICAO Aerodrome Design Manual, Part 4.

### **5.3.6 Circling guidance lights**

#### **Application**

5.3.6.1 Circling guidance lights should be provided when existing approach and runway lighting systems do not satisfactorily permit identification of the runway and/or approach area to a circling aircraft in the conditions for which it is intended the runway be used for circling approaches





**Figure 5-21. Obstacles protection surface for visual approach slope indicator systems**



### **Location**

5.3.6.2 The location and number of circling guidance lights should be adequate to enable a pilot, as appropriate, to:

- a) join the downwind leg or align and adjust the aircraft's track to the runway at a required distance from it and to distinguish the threshold in passing; and
- b) keep in sight the runway threshold and/or other features which will make it possible to judge the turn on to base leg and final approach, taking into account the guidance provided by other visual aids.

5.3.6.3 Circling guidance lights should consist of:

- a) lights indicating the extended center line of the runway and/or parts of any approach lighting system; or
- b) lights indicating the position of the runway threshold; or
- c) lights indicating the direction or location of the runway; or a combination of such lights as is appropriate to the runway under consideration.

Note.— Guidance on installation of circling guidance lights is given in the ICAO Aerodrome Design Manual, Part 4.

### **Characteristics**

5.3.6.4 Circling guidance lights should be fixed or flashing lights of an intensity and beam spread adequate for the conditions of visibility and ambient light in which it is intended to make visual circling approaches. The flashing lights should be white, and the steady lights either white or gaseous discharge lights.

5.3.6.5 The lights should be designed and be installed in such a manner that they will not dazzle or confuse a pilot when approaching to land, taking off or taxiing.

### **5.3.7 Runway lead-in lighting systems**

#### **Application**

5.3.7.1 A runway lead-in lighting system should be provided where it is desired to provide visual guidance along a specific approach path, for reasons such as avoiding hazardous terrain or for purposes of noise abatement.

Note.— Guidance on providing lead-in lighting systems is given in the ICAO Aerodrome Design Manual, Part 4.

### **Location**

5.3.7.2 A runway lead-in lighting system should consist of groups of lights positioned so as to define the desired approach path and so that one group may be sighted from

the preceding group. The interval between adjacent groups should not exceed approximately 1 600 m.

Note.— Runway lead-in lighting systems may be curved, straight or a combination thereof.

5.3.7.3 A runway lead-in lighting system should extend from a point as determined by the appropriate authority, up to a point where the approach lighting system, if provided, or the runway or the runway lighting system is in view.

### **Characteristics**

5.3.7.4 Each group of lights of a runway lead-in lighting system should consist of at least three flashing lights in a linear or cluster configuration. The system may be augmented by steady burning lights where such lights would assist in identifying the system.

5.3.7.5 The flashing lights should be white, and the steady burning lights gaseous discharge lights.

5.3.7.6 Where practicable, the flashing lights in each group should flash in sequence towards the runway.

### **5.3.8 Runway threshold identification lights**

#### **Application**

5.3.8.1 Runway threshold identification lights should be installed:

- a) at the threshold of a non-precision approach runway when additional threshold conspicuity is necessary or where it is not practicable to provide other approach lighting aids; and
- b) where a runway threshold is permanently displaced from the runway extremity or temporarily displaced from the normal position and additional threshold conspicuity is necessary.

### **Location**

5.3.8.2 Runway threshold identification lights shall be located symmetrically about the runway center line, in line with the threshold and approximately 10 m outside each line of runway edge lights.

5.3.8.3 Runway threshold identification lights should be flashing white lights with a flash frequency between 60 and 120 per minute.

5.3.8.4 The lights shall be visible only in the direction of approach to the runway.

### **5.3.9 Runway edge lights**

#### **Application**

5.3.9.1 Runway edge lights shall be provided for a runway intended for use at night or for a precision approach runway intended for use by day or night.

5.3.9.2 Runway edge lights should be provided on a runway intended for take-off with an operating minimum below an RVR of the order of 800 m by day.

#### **Location**

5.3.9.3 Runway edge lights shall be placed along the full length of the runway and shall be in two parallel rows equidistant from the center line.

5.3.9.4 Runway edge lights shall be placed along the edges of the area declared for use as the runway or outside the edges of the area at a distance of not more than 3 m.

5.3.9.5 Where the width of the area which could be declared as runway exceeds 60 m, the distance between the rows of lights should be determined taking into account the nature of the operations, the light distribution characteristics of the runway edge lights, and other visual aids serving the runway.

5.3.9.6 The lights shall be uniformly spaced in rows at intervals of not more than 60 m for an instrument runway, and at intervals of not more than 100 m for a non-instrument runway. The lights on opposite sides of the runway axis shall be on lines at right angles to that axis. At intersections of runways, lights may be spaced irregularly or omitted, provided that adequate guidance remains available to the pilot.

#### **Characteristics**

5.3.9.7 Runway edge lights shall be fixed lights showing variable white, except that:

- a) in the case of a displaced threshold, the lights between the beginning of the runway and the displaced threshold shall show red in the approach direction; and
- b) a section of the lights 600 m or one-third of the runway length, whichever is the less, at the remote end of the runway from the end at which the take-off run is started, may show yellow.

5.3.9.8 The runway edge lights shall show at all angles in azimuth necessary to provide guidance to a pilot landing or taking off in either direction. When the runway edge lights are intended to provide circling guidance, they shall show at all angles in azimuth (see 5.3.6.1).

5.3.9.9 In all angles of azimuth required in 5.3.9.8, runway edge lights shall show at angles up to 15° above the horizontal with an intensity adequate for the conditions of visibility and ambient light in which use of the runway for take-off or landing is intended. In any case, the intensity shall be at least 50 cd except that at an aerodrome without extraneous lighting the intensity of the lights may be reduced to not less than 25 cd to avoid dazzling the pilot.

5.3.9.10 Runway edge lights on a precision approach runway shall be in accordance with the specifications of Appendix 2, Figure A2-9 or A2-10.

#### **5.3.10 Runway threshold and wing bar lights (see Figure 5-21)**

##### **Application of runway threshold lights**

5.3.10.1 Runway threshold lights shall be provided for a runway equipped with runway edge lights except on a non-instrument or non-precision approach runway where the threshold is displaced and wing bar lights are provided.

##### **Location of runway threshold lights**

5.3.10.2 When a threshold is at the extremity of a runway, the threshold lights shall be placed in a row at right angles to the runway axis as near to the extremity of the runway as possible and, in any case, not more than 3 m outside the extremity.

5.3.10.3 When a threshold is displaced from the extremity of a runway, threshold lights shall be placed in a row at right angles to the runway axis at the displaced threshold.

5.3.10.4 Threshold lighting shall consist of:

- a) on a non-instrument or non-precision approach runway, at least six lights;
- b) on a precision approach runway category I, at least the number of lights that would be required if the lights were uniformly spaced at intervals of 3 m between the rows of runway edge lights; and
- c) on a precision approach runway category II or III, lights uniformly spaced between the rows of runway edge lights at intervals of not more than 3 m.

5.3.10.5 The lights prescribed in (5.3.10.4 a) and b) should be either:

- a) equally spaced between the rows of runway edge lights, or
- b) symmetrically disposed about the runway center line in two groups, with the lights uniformly spaced in each group and with a gap between the groups equal to the gauge of the touchdown zone marking or lighting, where such is provided, or otherwise not more than half the distance between the rows of runway edge lights.

##### **Application of wing bar lights**

5.3.10.6 Wing bar lights should be provided on a precision approach runway when additional conspicuity is considered desirable.

5.3.10.7 Wing bar lights shall be provided on a noninstrument or non-precision approach runway where the threshold is displaced and runway threshold lights are required, but are not provided.

#### **Location of wing bar lights**

5.3.10.8 Wing bar lights shall be symmetrically disposed about the runway center line at the threshold in two groups, i.e. wing bars. Each wing bar shall be formed by at least five lights extending at least 10 m outward from, and at right angles to, the line of the runway edge lights, with the innermost light of each wing bar in the line of the runway edge lights.

#### **Characteristics of runway threshold and wing bar lights**

5.3.10.9 Runway threshold and wing bar lights shall be fixed unidirectional lights showing green in the direction of approach to the runway. The intensity and beam spread of the lights shall be adequate for the conditions of visibility and ambient light in which use of the runway is intended.

5.3.10.10 Runway threshold lights on a precision approach runway shall be in accordance with the specifications of Appendix 2, Figure A2-3.

5.3.10.11 Threshold wing bar lights on a precision approach runway shall be in accordance with the specifications of Appendix 2, Figure A2-4.

#### **5.3.11 Runway end lights (see Figure 5-21)**

##### **Application**

5.3.11.1 Runway end lights shall be provided for a runway equipped with runway edge lights.

Note.— When the threshold is at the runway extremity, fittings serving as threshold lights may be used as runway end lights.

##### **Location**

5.3.11.2 Runway end lights shall be placed on a line at right angles to the runway axis as near to the end of the

runway as possible and, in any case, not more than 3 m outside the end.

5.3.11.3 Runway end lighting should consist of at least six lights. The lights should be either:

- a) equally spaced between the rows of runway edge lights, or
- b) symmetrically disposed about the runway center line in two groups with the lights uniformly spaced in each group and with a gap between the groups of not more than half the distance between the rows of runway edge lights. For a precision approach runway category III, the spacing between runway end lights, except between the two innermost lights if a gap is used, should not exceed 6 m.

##### **Characteristics**

5.3.11.4 Runway end lights shall be fixed unidirectional lights showing red in the direction of the runway. The intensity and beam spread of the lights shall be adequate for the conditions of visibility and ambient light in which use of the runway is intended.

5.3.11.5 Runway end lights on a precision approach runway shall be in accordance with the specifications of Appendix 2, Figure A2-8.

#### **5.3.12 Runway center line lights**

##### **Application**

5.3.12.1 Runway center line lights shall be provided on a precision approach runway category II or III.

5.3.12.2 Runway center line lights should be provided on a precision approach runway category I, particularly when the runway is used by aircraft with high landing speeds or where the width between the runway edge lights is greater than 50 m.

5.3.12.3 Runway center line lights shall be provided on a runway intended to be used for take-off with an operating minimum below an RVR of the order of 400 m.

CONDITION	LIGHTS	RUNWAY TYPE			
		NON-INSTRUMENT AND NON-PRECISION APPROACH RUNWAYS	PRECISION APPROACH RUNWAYS CATEGORY I		PRECISION APPROACH RUNWAYS CATEGORY II
THRESHOLD AT RUNWAY EXTREMITY	DUMMY THRESHOLD AND RUNWAY END LIGHTS	 (S3, W2, S3, W4-Q, S3, W5, S3, W6, S3, W7, S3, W8, S3, W9, S3, W10, S3, W11, S3, W12, S3, W13)	 (S3, W2, S3, W4-Q, S3, W5, S3, W6, S3, W7, S3, W8, S3, W9, S3, W10, S3, W11, S3, W12, S3, W13)	 (S3, W2, S3, W4-Q, S3, W5, S3, W6, S3, W7, S3, W8, S3, W9, S3, W10, S3, W11, S3, W12, S3, W13)	 (S3, W2, S3, W4-Q, S3, W5, S3, W6, S3, W7, S3, W8, S3, W9, S3, W10, S3, W11, S3, W12, S3, W13)
THRESHOLD DISPLACED FROM RUNWAY EXTREMITY	DUMMY THRESHOLD LIGHTS	 (S3, W3, S3, W4-Q, S3, W5, S3, W6, S3, W7, S3, W8, S3, W9, S3, W10, S3, W11, S3, W12, S3, W13)	 (S3, W3, S3, W4-Q, S3, W5, S3, W6, S3, W7, S3, W8, S3, W9, S3, W10, S3, W11, S3, W12, S3, W13)	 (S3, W3, S3, W4-Q, S3, W5, S3, W6, S3, W7, S3, W8, S3, W9, S3, W10, S3, W11, S3, W12, S3, W13)	 (S3, W3, S3, W4-Q, S3, W5, S3, W6, S3, W7, S3, W8, S3, W9, S3, W10, S3, W11, S3, W12, S3, W13)
	RUNWAY END LIGHTS	 (S3, W12, S3, W13)	 (S3, W12, S3, W13)	 (S3, W12, S3, W13)	 (S3, W12, S3, W13)

LEGEND

- UNDIRECTED LIGHT
- DIRECTED LIGHT
- CONDITIONAL RECOMMENDATION

Note — The minimum number of lights are shown for a runway 45 m wide with runway edge lights installed at the edge.

Figure 5-22. Arrangement of runway threshold and Runway end light




Figure 5-23. Example of approach and runway lighting for runway with displaced thresholds



5.3.12.4 Runway center line lights should be provided on a runway intended to be used for take-off with an operating minimum of an RVR of the order of 400 m or higher when used by aeroplanes with a very high take-off speed, particularly where the width between the runway edge lights is greater than 50 m.

#### **Location**

5.3.12.5 Runway center line lights shall be located along the center line of the runway, except that the lights may be uniformly offset to the same side of the runway center line by not more than 60 cm where it is not practicable to locate them along the center line. The lights shall be located from the threshold to the end at longitudinal spacing of approximately 15 m. Where the serviceability level of the runway center line lights specified as maintenance objectives in 10.4.7 or 10.4.11, as appropriate, can be demonstrated and the runway is intended for use in runway visual range conditions of 350 m or greater, the longitudinal spacing may be approximately 30 m.

Note.— Existing center line lighting where lights are spaced at 7.5 m need not be replaced.

5.3.12.6 Center line guidance for take-off from the beginning of a runway to a displaced threshold should be provided by:

- a) an approach lighting system if its characteristics and intensity settings afford the guidance required during take-off and it does not dazzle the pilot of an aircraft taking off; or
- b) runway center line lights; or
- c) barrettes of at least 3 m length and spaced at uniform intervals of 30 m, as shown in Figure 5-22, designed so that their photometric characteristics and intensity setting afford the guidance required during take-off without dazzling the pilot of an aircraft taking off. Where necessary, provision should be made to extinguish those center line lights specified in b) or reset the intensity of the approach lighting system or barrettes when the runway is being used for landing. In no case should only the single source runway center line lights show from the beginning of the runway to a displaced threshold when the runway is being used for landing.

#### **Characteristics**

5.3.12.7 Runway center line lights shall be fixed lights showing variable white from the threshold to the point 900 m from the runway end; alternate red and variable white from 900 m to 300 m from the runway end; and red from 300 m to the runway end, except that for runways

less than 1 800 m in length, the alternate red and variable white lights shall extend from the mid-point of the runway usable for landing to 300 m from the runway end.

Note.— Care is required in the design of the electrical system to ensure that failure of part of the electrical system will not result in a false indication of the runway distance remaining.

5.3.12.8 Runway center line lights shall be in accordance with the specifications of Appendix 2, Figure A2-6 or A2-7.

### **5.3.13 Runway touchdown zone lights**

#### **Application**

5.3.13.1 Touchdown zone lights shall be provided in the touchdown zone of a precision approach runway category II or III.

#### **Location**

5.3.13.2 Touchdown zone lights shall extend from the threshold for a longitudinal distance of 900 m, except that, on runways less than 1 800 m in length, the system shall be shortened so that it does not extend beyond the midpoint of the runway. The pattern shall be formed by pairs of barrettes symmetrically located about the runway center line. The lateral spacing between the innermost lights of a pair of barrettes shall be equal to the lateral spacing selected for the touchdown zone marking. The longitudinal spacing between pairs of barrettes shall be either 30 m or 60 m.

Note.— To allow for operations at lower visibility minima, it may be advisable to use a 30 m longitudinal spacing between barrettes.

#### **Characteristics**

5.3.13.3 A barrette shall be composed of at least three lights with a spacing between the lights of not more than 1.5 m.

5.3.13.4 A barrette should be not less than 3 m nor more than 4.5 m in length.

5.3.13.5 Touchdown zone lights shall be fixed unidirectional lights showing variable white.

5.3.13.6 Touchdown zone lights shall be in accordance with the specifications of Appendix 2, Figure A2-5.

### **5.3.14 Simple Touchdown Zone Lights**

Note.— The purpose of Simple Touchdown Zone Lights is to provide pilots with enhanced situational awareness in all visibility conditions and to help enable pilots to decide whether to commence a go around if the aircraft has not landed by a certain point on the runway. It is essential that pilots operating at aerodromes with Simple



Touchdown Zone Lights be familiar with the purpose of these lights.

### **Application**

5.3.14.1 Except where TDZ lights are provided in accordance with paragraph 5.3.13, at an aerodrome where the approach angle is greater than 3.5 degrees and/or the Landing Distance Available combined with other factors increases the risk of an overrun, Simple Touchdown Zone Lights should be provided.

### **Location**

5.3.14.2 Simple Touchdown Zone Lights shall be a pair of lights located on each side of the runway centreline 0.3 metres beyond the upwind edge of the final Touchdown Zone Marking. The lateral spacing between the inner lights of the two pairs of lights shall be equal to the lateral spacing selected for the Touchdown Zone Marking. The spacing between the lights of the same pair shall not be more than 1.5 m or half the width of the touchdown zone marking, whichever is greater. (See Figure 5-24)


5.3.14.3 Where provided on a runway without TDZ markings, Simple Touchdown Zone lights should be installed in such a position that provides the equivalent TDZ information.


### **Characteristics**

5.3.14.4 Simple Touchdown Zone Lights shall be fixed unidirectional lights showing variable white, aligned so as to be visible to the pilot of a landing aeroplane in the direction of approach to the runway.

5.3.14.5 Simple Touchdown Zone Lights shall be in accordance with the specifications in Appendix 2, Figure A2-5.

**Note.**— As a good operating practice, Simple Touchdown Zone Lights are supplied with power on a separate circuit to other runway lighting so that they may be used when other lighting is switched off.





**Figure 5-24 Simple touchdown zone lighting**

### 5.3.15 Rapid exit taxiway indicator lights

Note.— The purpose of rapid exit taxiway indicator lights (RETILs) is to provide pilots with distance-to-go information to the nearest rapid exit taxiway on the runway, to enhance situational awareness in low visibility conditions and enable pilots to apply braking action for more efficient roll-out and runway exit speeds. It is essential that pilots operating at aerodromes with runway(s) displaying rapid exit taxiway indicator lights be familiar with the purpose of these lights.

#### Application

5.3.15.1 Rapid exit taxiway indicator lights should be provided on a runway intended for use in runway visual range conditions less than a value of 350 m and/or where the traffic density is heavy.

Note.— See Attachment A, Section 14.

5.3.15.2 Rapid exit taxiway indicator lights shall not be displayed in the event of any lamp failure or other failure that prevents the display of the light pattern depicted in Figure 5-23, in full

5.3.15.3 A set of rapid exit taxiway indicator lights shall be located on the runway on the same side of the runway center line as the associated rapid exit taxiway, in the configuration shown in Figure 5-23. In each set, the lights shall be located 2 m apart and the light nearest to the runway center line shall be displaced 2 m from the runway center line.


5.3.15.4 Where more than one rapid exit taxiway exists on a runway, the set of rapid exit taxiway indicator lights for each exit shall not overlap when displayed.

#### Characteristics

5.3.15.5 Rapid exit taxiway indicator lights shall be fixed unidirectional yellow lights, aligned so as to be visible to the pilot of a landing aeroplane in the direction of approach to the runway.

5.3.15.6 Rapid exit taxiway indicator lights shall be in accordance with the specifications in Appendix 2, Figure A2-6 or Figure A2-7, as appropriate.

5.3.15.7 Rapid exit taxiway indicator lights should be supplied with power on a separate circuit to other runway lighting so that they may be used when other lighting is switched off.



**Figure 5.25 Rapid exit taxiway indicator lights (RETILS)**

### 5.3.16 Stopway lights

#### Application

5.3.16.1 Stopway lights shall be provided for a stopway intended for use at night.

#### Location

5.3.16.2 Stopway lights shall be placed along the full length of the stopway and shall be in two parallel rows that are equidistant from the center line and coincident with the rows of the runway edge lights. Stopway lights shall also be provided across the end of a stopway on a line at right angles to the stopway axis as near to the end of the stopway as possible and, in any case, not more than 3 m outside the end.

#### Characteristics

5.3.16.3 Stopway lights shall be fixed unidirectional lights showing red in the direction of the runway.

### 5.3.17 Taxiway center line lights

#### Application

5.3.17.1 Taxiway center line lights shall be provided on an exit taxiway, taxiway, de-icing/anti-icing facility and

apron intended for use in runway visual range conditions less than a value of 350 m in such a manner as to provide continuous guidance between the runway center line and aircraft stands, except that these lights need not be provided where the traffic density is light and taxiway edge lights and center line marking provide adequate guidance.

5.3.17.2 Taxiway center line lights should be provided on a taxiway intended for use at night in runway visual range conditions of 350 m or greater, and particularly on complex taxiway intersections and exit taxiways, except that these lights need not be provided where the traffic density is light and taxiway edge lights and center line marking provide adequate guidance.

Note.— Where there may be a need to delineate the edges of a taxiway, e.g. on a rapid exit taxiway, narrow taxiway or in snow conditions, this may be done with taxiway edge lights or markers.

5.3.17.3 Taxiway center line lights should be provided on an exit taxiway, taxiway, de-icing/anti-icing facility and apron in all visibility conditions where specified as components of an advanced surface movement guidance and control system in such a manner as to provide continuous guidance between the runway center line and aircraft stands.

5.3.17.4 Taxiway center line lights shall be provided on a runway forming part of a standard taxi-route and intended for taxiing in runway visual range conditions less than a value of 350 m, except that these lights need not be provided where the traffic density is light and taxiway edge lights and center line marking provide adequate guidance.

Note.— See 8.2.3 for provisions concerning the interlocking of runway and taxiway lighting systems.

5.3.17.5 Taxiway center line lights should be provided in all visibility conditions on a runway forming part of a standard taxi-route where specified as components of an advanced surface movement guidance and control system.

#### Characteristics

5.3.17.6 Except as provided for in 5.3.17.8, taxiway center line lights on a taxiway other than an exit taxiway and on a runway forming part of a standard taxi-route shall be fixed lights showing green with beam dimensions such that the light is visible only from aeroplanes on or in the vicinity of the taxiway.

5.3.17.7 Taxiway center line lights on an exit taxiway shall be fixed lights. Alternate taxiway center line lights shall show green and yellow from their beginning near the runway center line to the perimeter of the ILS/MLS critical/sensitive area or the lower edge of the inner transitional surface, whichever is farthest from the runway; and thereafter all lights shall show green (Figure 5-25). The first light in the exit centre line shall always show green and the light nearest to the perimeter shall always show yellow.

Note 1.— Care is necessary to limit the light distribution of green lights on or near a runway so as to avoid possible confusion with threshold lights.

Note 2.— For yellow filter characteristics see Appendix 1, 2.2.

Note 3.— The size of the ILS/MLS critical/sensitive area depends on the characteristics of the associated ILS/MLS and other factors. Guidance is provided in GACA Regulation Section 10 and ICAO Annex 10, Volume I, Attachments C and G.

Note 4.— See 5.4.3 for specifications on runway vacated signs.

5.3.17.8 Where it is necessary to denote the proximity to a runway, taxiway centre line lights should be fixed lights showing alternating green and yellow from the perimeter

of the ILS/MLS critical/sensitive area or the lower edge of the inner transitional surface, whichever is farthest from the runway, to the runway and continue alternating green and yellow until:

- a) their end point near the runway centre line; or
- b) in the case of the taxiway centre line lights crossing the runway, to the opposite perimeter of the ILS/MLS critical/sensitive area or the lower edge of the inner transitional surface, whichever is farthest from the runway.

Note 1.— Care is necessary to limit the light distribution of green lights on or near a runway so as to avoid possible confusion with threshold lights.

Note 2.— The provisions of 5.3.17.8 can form part of effective runway incursion prevention measures.


5.3.17.9 Taxiway center line lights shall be in accordance with the specifications of:

- a) Appendix 2, Figure A2-12, A2-13, or A2-14 for taxiways intended for use in runway visual range conditions of less than a value of 350 m; and
- b) Appendix 2, Figure A2-15 or A2-16 for other taxiways.

5.3.17.10 Where higher intensities are required, from an operational point of view, taxiway center line lights on rapid exit taxiways intended for use in runway visual range conditions less than a value of 350 m should be in accordance with the specifications of Appendix 2, Figure A2-12. The number of levels of brilliancy settings for these lights should be the same as that for the runway center line lights.

5.3.17.11 Where taxiway center line lights are specified as components of an advanced surface movement guidance and control system and where, from an operational point of view, higher intensities are required to maintain ground movements at a certain speed in very low visibilities or in bright daytime conditions, taxiway center line lights should be in accordance with the specifications of Appendix 2, Figure A2-17, A2-18 or A2-19.

Note.— High-intensity center line lights should only be used in case of an absolute necessity and following a specific study.



**Figure 5-26 Taxiway lighting**

### Location

5.3.17.12 Taxiway center line lights should normally be located on the taxiway center line marking, except that they may be offset by not more than 30 cm where it is not practicable to locate them on the marking.

### Taxiway center line lights on taxiways

#### Location

5.3.17.13 Taxiway center line lights on a straight section of a taxiway should be spaced at longitudinal intervals of not more than 30 m, except that:

- a) larger intervals not exceeding 60 m may be used where, because of the prevailing meteorological conditions, adequate guidance is provided by such spacing;
- b) intervals less than 30 m should be provided on short straight sections; and
- c) on a taxiway intended for use in RVR conditions of less than a value of 350 m, the longitudinal spacing should not exceed 15 m.

5.3.17.14 Taxiway center line lights on a taxiway curve should continue from the straight portion of the taxiway at a constant distance from the outside edge of the taxiway curve. The lights should be spaced at intervals such that a clear indication of the curve is provided.

5.3.17.15 On a taxiway intended for use in RVR conditions of less than a value of 350 m, the lights on a curve should not exceed a spacing of 15 m and on a curve of less than 400 m radius the lights should be spaced at intervals of not greater than 7.5 m. This spacing should extend for 60 m before and after the curve.

Note 1.— Spacings on curves that have been found suitable for a taxiway intended for use in RVR conditions of 350 m or greater are:

Curve radius	Light spacing
up to 400 m	7.5 m
401 m to 899 m	15 m
900 m or greater	30 m

Note 2.— See 3.9.6 and Figure 3-2.

### Taxiway center line lights on rapid exit taxiways

#### Location

5.3.17.16 Taxiway center line lights on a rapid exit taxiway should commence at a point at least 60 m before the beginning of the taxiway center line curve and continue beyond the end of the curve to a point on the

center line of the taxiway where an aeroplane can be expected to reach normal taxiing speed. The lights on that portion parallel to the runway center line should always be at least 60 cm from any row of runway center line lights, as shown in Figure 5-25.

5.3.17.17 The lights should be spaced at longitudinal intervals of not more than 15 m, except that, where runway center line lights are not provided, a greater interval not exceeding 30 m may be used.

### Taxiway center line lights on other exit taxiways

#### Location

5.3.17.18 Taxiway center line lights on exit taxiways other than rapid exit taxiways should commence at the point where the taxiway center line marking begins to curve from the runway center line, and follow the curved taxiway center line marking at least to the point where the marking leaves the runway. The first light should be at least 60 cm from any row of runway center line lights, as shown in Figure 5-25.

5.3.17.19 The lights should be spaced at longitudinal intervals of not more than 7.5 m.

### Taxiway center line lights on runways

#### Location

5.3.17.20 Taxiway center line lights on a runway forming part of a standard taxi-route and intended for taxiing in runway visual range conditions less than a value of 350 m should be spaced at longitudinal intervals not exceeding 15 m.

### 5.3.18 Taxiway edge lights

#### Application

5.3.18.1 Taxiway edge lights shall be provided at the edges of a runway turn pad, holding bay, de-icing/anti-icing facility, apron, etc. intended for use at night and on a taxiway not provided with taxiway center line lights and intended for use at night, except that taxiway edge lights need not be provided where, considering the nature of the operations, adequate guidance can be achieved by surface illumination or other means.

Note.— See 5.5.5 for taxiway edge markers.

5.3.18.2 Taxiway edge lights shall be provided on a runway forming part of a standard taxi-route and intended for taxiing at night where the runway is not provided with taxiway center line lights.

Note.— See 8.2.3 for provisions concerning the interlocking of runway and taxiway lighting systems.

#### Location

5.3.18.3 Taxiway edge lights on a straight section of a taxiway and on a runway forming part of a standard taxi-



route should be spaced at uniform longitudinal intervals of not more than 60 m. The lights on a curve should be spaced at intervals less than 60 m so that a clear indication of the curve is provided.

Note.— Guidance on the spacing of taxiway edge lights on curves is given in the ICAO Aerodrome Design Manual, Part 4.

5.3.18.4 Taxiway edge lights on a holding bay, de-icing/anti-icing facility, apron, etc. should be spaced at uniform longitudinal intervals of not more than 60 m.

5.3.18.5 Taxiway edge lights on a runway turn pad should be spaced at uniform longitudinal intervals of not more than 30 m.

5.3.18.6 The lights should be located as near as practicable to the edges of the taxiway, runway turn pad, holding bay, de-icing/anti-icing facility, apron or runway, etc. or outside the edges at a distance of not more than 3m.

#### **Characteristics**

5.3.18.7 Taxiway edge lights shall be fixed lights showing blue. The lights shall show up to at least 75° above the horizontal and at all angles in azimuth necessary to provide guidance to a pilot taxiing in either direction. At an intersection, exit or curve the lights shall be shielded as far as practicable so that they cannot be seen in angles of azimuth in which they may be confused with other lights.

5.3.18.8 The intensity of taxiway edge lights shall be at least 2 cd from 0° to 6° vertical, and 0.2 cd at any vertical angles between 6° and 75°.

#### **5.3.19 Runway turn pad lights** **Application**

5.3.19.1 Runway turn pad lights shall be provided for continuous guidance on a runway turn pad intended for use in runway visual range conditions less than a value of 350 m, to enable an aeroplane to complete a 180-degree turn and align with the runway center line.

5.3.19.2 Runway turn pad lights should be provided on a runway turn pad intended for use at night.

#### **Location**

5.3.19.3 Runway turn pad lights should normally be located on the runway turn pad marking, except that they may be offset by not more than 30 cm where it is not practicable to locate them on the marking.


5.3.19.4 Runway turn pad lights on a straight section of the runway turn pad marking should be spaced at longitudinal intervals of not more than 15 m.

5.3.19.5 Runway turn pad lights on a curved section of the runway turn pad marking should not exceed a spacing of 7.5 m.

#### **Characteristics**

5.3.19.6 Runway turn pad lights shall be unidirectional fixed lights showing green with beam dimensions such that the light is visible only from aeroplanes on or approaching the runway turn pad.

5.3.19.7 Runway turn pad lights shall be in accordance with the specifications of Appendix 2, Figure A2-13, A2-14 or A2-15, as appropriate.



**Figure 5-27. Offset runway and taxiway center line lights**

### 5.3.20 Stop bars

#### Application

Note 1.— A stop bar is intended to be controlled either manually or automatically by air traffic services.

Note 2.— Runway incursions may take place in all visibility or weather conditions. The provision of stop bars at runway holding positions and their use at night and in visibility conditions greater than 550 m runway visual range can form part of effective runway incursion prevention measures.

5.3.20.1 A stop bar shall be provided at every runway-holding position serving a runway when it is intended that the runway will be used in runway visual range conditions less than a value of 350 m, except where:

- a) appropriate aids and procedures are available to assist in preventing inadvertent incursions of traffic onto the runway; or
- b) operational procedures exist to limit, in runway visual range conditions less than a value of 550 m, the number of:
  1. aircraft on the maneuvering area to one at a time; and
  2. vehicles on the maneuvering area to the essential minimum.

5.3.20.2 A stop bar shall be provided at every runway holding position, serving a runway when it is intended that the runway will be used in runway visual range conditions of values between 350 m and 550 m, except where:

- a) appropriate aids and procedures are available to assist in preventing inadvertent incursions of traffic onto the runway; or
- b) operational procedures exist to limit, in runway visual range conditions less than a value of 550 m, the number of:
  - 1) aircraft on the maneuvering area to one at a time; and
  - 2) vehicles on the maneuvering area to the essential minimum.

5.3.20.3 Where there is more than one stop bar associated with a taxiway/runway intersection, only one shall be illuminated at any given time.

5.3.20.4 A stop bar should be provided at an intermediate holding position when it is desired to supplement markings with lights and to provide traffic control by visual means.

#### Location

5.3.20.5 Stop bars shall be located across the taxiway at the point where it is desired that traffic stop. Where the additional lights specified in 5.3.19.4 are provided, these lights shall be located not less than 3 m from the taxiway edge.

#### Characteristics

5.3.20.6 Stop bars shall consist of lights spaced at uniform intervals of no more than 3 m across the taxiway, showing red in the intended direction(s) of approach to the intersection or runway-holding position.

Note.— Where necessary to enhance conspicuity of an existing stop bar, extra lights are installed uniformly.

5.3.20.7 A pair of elevated lights should be added to each end of the stop bar where the in-pavement stop bar lights might be obscured from a pilot's view, for example, by snow or rain, or where a pilot may be required to stop the aircraft in a position so close to the lights that they are blocked from view by the structure of the aircraft

5.3.20.8 Stop bars installed at a runway-holding position shall be unidirectional and shall show red in the direction of approach to the runway.

5.3.20.9 Where the additional lights specified in 5.3.20.8 are provided, these lights shall have the same characteristics as the lights in the stop bar, but shall be visible to approaching aircraft up to the stop bar position.

5.3.20.10 The intensity in red light and beam spreads of stop bar lights shall be in accordance with the specifications in Appendix 2, Figures A2-12 through A2-16, as appropriate.

5.3.20.11 Where stop bars are specified as components of an advanced surface movement guidance and control system and where, from an operational point of view, higher intensities are required to maintain ground movements at a certain speed in very low visibilities or in bright daytime conditions, the intensity in red light and beam spreads of stop bar lights should be in accordance with the specifications of Appendix 2, Figure A2-17, A2-18 or A2-19.

Note.— High-intensity stop bars should only be used in case of an absolute necessity and following a specific study.

5.3.20.12 Where a wide beam fixture is required, the intensity in red light and beam spreads of stop bar lights should be in accordance with the specifications of Appendix 2, Figure A2-17 or A2-19.

5.3.20.13 The lighting circuit shall be designed so that:

- a) stop bars located across entrance taxiways are selectively switchable;
- b) stop bars located across taxiways intended to be used only as exit taxiways are switchable selectively or in groups;
- c) when a stop bar is illuminated, any taxiway center line lights installed beyond the stop bar shall be extinguished for a distance of at least 90 m; and
- d) stop bars are interlocked with the taxiway center line lights so that when the center line lights beyond the stop bar are illuminated the stop bar is extinguished and vice versa.

Note.— Care is required in the design of the electrical system to ensure that all of the lights of a stop bar will not fail at the same time. Guidance on this issue is given in the ICAO Aerodrome Design Manual (*Doc 9157*), Part 5.

### 5.3.21 Intermediate holding position lights

Note.— See 5.2.11 for specifications on intermediate holding position marking.

#### Application

5.3.21.1 Except where a stop bar has been installed, intermediate holding position lights shall be provided at an intermediate holding position intended for use in runway visual range conditions less than a value of 350 m.

5.3.21.2 Intermediate holding position lights should be provided at an intermediate holding position where there is no need for stop-and-go signals as provided by a stop bar.

#### Location

5.3.21.3 Intermediate holding position lights shall be located along the intermediate holding position marking at a distance of 0.3 m prior to the marking.

#### Characteristics

5.3.21.4 Intermediate holding position lights shall consist of three fixed unidirectional lights showing yellow in the direction of approach to the intermediate holding position

with a light distribution similar to taxiway center line lights if provided. The lights shall be disposed symmetrically about and at right angle to the taxiway center line, with individual lights spaced 1.5 m apart.

### 5.3.22 De-icing/anti-icing facility exit lights

#### Application

5.3.22.1 De-icing/anti-icing facility exit lights should be provided at the exit boundary of a remote de-icing/anti-icing facility adjoining a taxiway.


#### Location

5.3.22.2 De-icing/anti-icing facility exit lights shall be located 0.3 m inward of the intermediate holding position marking displayed at the exit boundary of a remote de-icing/anti-icing facility.


#### Characteristics

5.3.22.3 De-icing/anti-icing facility exit lights shall consist of in-pavement fixed unidirectional lights spaced at intervals of 6 m showing yellow in the direction of the approach to the exit boundary with a light distribution similar to taxiway center line lights (see Figure 5-26).

Intentionally left blank



**Figure 5.28 Typical remote de-icing / anti-icing facility**



**Figure 5.29 Runway guard**

### 5.3.23 Runway guard lights

Note.— The purpose of runway guard lights is to warn pilots, and drivers of vehicles when they are operating on taxiways, that they are about to enter runway. There are two standard configurations of runway guard lights as illustrated in Figure 5-28.

#### Application

5.3.23.1 Runway guard lights, Configuration A, shall be provided at each taxiway/runway intersection associated with a runway intended for use in:

- a) runway visual range conditions less than a value of 550 m where a stop bar is not installed; and
- b) runway visual range conditions of values between 550 m and 1 200 m where the traffic density is heavy.

5.3.23.2 As part of runway incursion prevention measures, runway guard lights, Configuration A or B, should be provided at each taxiway/runway intersection where runway incursion hot spots have been identified, and used under all weather conditions during day and night.

5.2.23.3 Configuration B runway guard lights should not be collocated with a stop bar

#### Location

5.3.23.4 Runway guard lights, Configuration A, shall be located at each side of the taxiway at a distance from the runway center line not less than that specified for a take-off runway in Table 3-2.

5.3. 23.5 Runway guard lights, Configuration B, shall be located across the taxiway at a distance from the runway center line not less than that specified for a take-off runway in Table 3-2.

#### Characteristics

5.3.23.6 Runway guard lights, Configuration A, shall consist of two pairs of yellow lights.

5.3.23.7 Where there is a need to enhance the contrast between the on and off state of runway guard lights, Configuration A, intended for use during the day, a visor of sufficient size to prevent sunlight from entering the lens without interfering with the function of the fixture should be located above each lamp.

Note.— Some other device or design, e.g. specially designed optics, may be used in lieu of the visor.

5.3.23.8 Runway guard lights, Configuration B, shall consist of yellow lights spaced at intervals of 3 m across the taxiway.

5.3.23.9 The light beam shall be unidirectional and aligned so as to be visible to the pilot of an aeroplane taxiing to the holding position.

5.3.23.10 The intensity in yellow light and beam spreads of lights of Configuration A should be in accordance with the specifications in Appendix 2, Figure A2-24.

5.3.23.11 Where runway guard lights are intended for use during the day, the intensity in yellow light and beam spreads of lights of Configuration A should be in accordance with the specifications in Appendix 2, Figure A2-25.

5.3.23.12 Where runway guard lights are specified as components of an advanced surface movement guidance and control system where higher light intensities are required, the intensity in yellow light and beam spreads of lights of Configuration A should be in accordance with the specifications in Appendix 2, Figure A2-25.

Note.— Higher light intensities may be required to maintain ground movement at a certain speed in low visibilities.

5.3. 23.13 The intensity in yellow light and beam spreads of lights of Configuration B should be in accordance with the specifications in Appendix 2, Figure A2-12.

5.3.23.14 Where runway guard lights are intended for use during the day, the intensity in yellow light and beam spreads of lights of Configuration B should be in accordance with the specifications in Appendix 2, Figure A2-20.

5.3.23.15 Where runway guard lights are specified as components of an advanced surface movement guidance and control system where higher light intensities are required, the intensity in yellow light and beam spreads of lights of Configuration B should be in accordance with the specifications in Appendix 2, Figure A2-20.

5.3. 23.16 The lights in each unit of Configuration A shall be illuminated alternately.

5.3.23.17 For Configuration B, adjacent lights shall be alternately illuminated and alternative lights shall be illuminated in unison.

5.3.23.18 The lights shall be illuminated between 30 and 60 cycles per minute and the light suppression and illumination periods shall be equal and opposite in each light.

Note.— The optimum flash rate is dependent on the rise and fall times of the lamps used. Runway guard lights, Configuration A, installed on 6.6 ampere series circuits have been found to look best when operated at 45 to 50 flashes per minute per lamp. Runway guard lights,



Configuration B, installed on 6.6 ampere series circuits have been found to look best when operated at 30 to 32 flashes per minute per lamp.

#### **5.3.24 Apron floodlighting** (see also 5.3.16.1 and 5.3.17.1)

##### **Application**

5.3.24.1 Apron floodlighting should be provided on an apron, on a de-icing/anti-icing facility and on a designated isolated aircraft parking position intended to be used at night.

Note 1.— Where a de-icing/anti-icing facility is located in close proximity to the runway and permanent floodlighting could be confusing to pilots, other means of illumination of the facility may be required.

Note 2.— The designation of an isolated aircraft parking position is specified in 3.14.

Note 3.— Guidance on apron floodlighting is given in the ICAO Aerodrome Design Manual, Part 4.

##### **Location**

5.3.24.2 Apron floodlights should be located so as to provide adequate illumination on all apron service areas, with a minimum of glare to pilots of aircraft in flight and on the ground, aerodrome and apron controllers, and personnel on the apron. The arrangement and aiming of floodlights should be such that an aircraft stand receives light from two or more directions to minimize shadows.

##### **Characteristics**

5.3.24.3 The spectral distribution of apron floodlights shall be such that the colors used for aircraft marking connected with routine servicing, and for surface and obstacle marking, can be correctly identified.

5.3.24.4 The average illuminance should be at least the following:

Aircraft stand:

- horizontal illuminance — 20 lux with a uniformity ratio (average to minimum) of not more than 4 to 1; and
- vertical illuminance — 20 lux at a height of 2 m above the apron in relevant directions.

Other apron areas:

- horizontal illuminance — 50 per cent of the average illuminance on the aircraft stands with a uniformity ratio (average to minimum) of not more than 4 to 1.

#### **5.3.25 Visual docking guidance system**

##### **Application**

5.3.25.1 A visual docking guidance system shall be provided when it is intended to indicate, by a visual aid, the precise positioning of an aircraft on an aircraft stand

and other alternative means, such as marshallers, are not practicable.

Note.— The factors to be considered in evaluating the need for a visual docking guidance system are in particular: the number and type(s) of aircraft using the aircraft stand, weather conditions, space available on the apron and the precision required for manoeuvring into the parking position due to aircraft servicing installation, passenger loading bridges, etc. See the ICAO Aerodrome Design Manual, Part 4 — Visual Aids for guidance on the selection of suitable systems.

5.3.25.2 The provisions of 5.3.24.3 to 5.3.24.7, 5.3.24.9, 5.3.25.10, 5.3.24.12 to 5.3.24.15, 5.3.24.17, 5.3.24.18 and 5.3.25.20 require the replacement of existing installations after 1 January 2005.

##### **Characteristics**

5.3.25.3 The system shall provide both azimuth and stopping guidance.

5.3.25.4 The azimuth guidance unit and the stopping position indicator shall be adequate for use in all weather, visibility, background lighting and pavement conditions for which the system is intended both by day and night, but shall not dazzle the pilot

Note.— Care is required in both the design and on-site installation of the system to ensure that reflection of sunlight, or other light in the vicinity, does not degrade the clarity and conspicuity of the visual cues provided by the system.

5.3.25.5 The azimuth guidance unit and the stopping position indicator shall be of a design such that:

- a) a clear indication of malfunction of either or both is available to the pilot; and
- b) they can be turned off.

5.3.25.6 The azimuth guidance unit and the stopping position indicator shall be located in such a way that there is continuity of guidance between the aircraft stand markings, the aircraft stand manoeuvring guidance lights, if present, and the visual docking guidance system.

5.3.25.7 The accuracy of the system shall be adequate for the type of loading bridge and fixed aircraft servicing installations with which it is to be used.

5.3.25.8 The system should be usable by all types of aircraft for which the aircraft stand is intended, preferably without selective operation.

5.3.25.9 If selective operation is required to prepare the system for use by a particular type of aircraft, then the system shall provide an identification of the selected

aircraft type to both the pilot and the system operator as a means of ensuring that the system has been set properly.

### **Azimuth guidance unit**

#### **Location**

5.3.25.10 The azimuth guidance unit shall be located on or close to the extension of the stand center line ahead of the aircraft so that its signals are visible from the cockpit of an aircraft throughout the docking manoeuvre and aligned for use at least by the pilot occupying the left seat.

5.3.25.11 The azimuth guidance unit should be aligned for use by the pilots occupying both the left and right seats.

#### **Characteristics**

5.3.25.12 The azimuth guidance unit shall provide unambiguous left/right guidance which enables the pilot to acquire and maintain the lead-in line without over controlling.

5.3.25.13 When azimuth guidance is indicated by color change, green shall be used to identify the center line and red for deviations from the center line.

### **Stopping position indicator**

#### **Location**

5.3.25.14 The stopping position indicator shall be located in conjunction with, or sufficiently close to, the azimuth guidance unit so that a pilot can observe both the azimuth and stop signals without turning the head.

5.3.25.15 The stopping position indicator shall be usable at least by the pilot occupying the left seat.

5.3.25.16 The stopping position indicator should be usable by the pilots occupying both the left and right seats.

#### **Characteristics**

5.3.25.17 The stopping position information provided by the indicator for a particular aircraft type shall account for the anticipated range of variations in pilot eye height and/or viewing angle.

5.3.25.18 The stopping position indicator shall show the stopping position for the aircraft for which guidance is being provided, and shall provide closing rate information to enable the pilot to gradually decelerate the aircraft to a full stop at the intended stopping position.

5.3.25.19 The stopping position indicator should provide closing rate information over a distance of at least 10 m.

5.3.25.20 When stopping guidance is indicated by color change, green shall be used to show that the aircraft can proceed and red to show that the stop point has been reached except that for a short distance prior to the stop

point a third color may be used to warn that the stopping point is close.

### **5.3.26 Advanced visual docking guidance system**

Note 1.— Advanced visual docking guidance systems (A-VDGS) include those systems that, in addition to basic and passive azimuth and stop position information, provide pilots with active (usually sensor-based) guidance information, such as aircraft type indication (in accordance with ICAO Document 8643), distance-to-go information and closing speed. Docking guidance information is usually provided on a single display unit.

Note 2.— An A-VDGS may provide docking guidance information in three stages: the acquisition of the aircraft by the system, the azimuth alignment of the aircraft, and the stopping position information.

5.3.26.1 An A-VDGS should be provided where it is operationally desirable to confirm the correct aircraft type for which guidance is being provided, and/or to indicate the stand centre line in use, where more than one is provided for.

5.3.26.2 The A-VDGS shall be suitable for use by all types of aircraft for which the aircraft stand is intended.

5.3.26.3 The A-VDGS shall only be used in conditions in which its operational performance is specified.

Note 1.— The use of the A-VDGS in conditions such as weather, visibility, and background lighting both by day and night would need to be specified.

Note 2.— Care is required in both the design and on-site installation of the system to ensure that glare, reflection of sunlight, or other light in the vicinity, does not degrade the clarity and conspicuity of the visual cues provided by the system.

5.3.26.4 The docking guidance information provided by an A-VDGS shall not conflict with that provided by a conventional visual docking guidance system on an aircraft stand if both types are provided and are in operational use. A method of indicating that the A-VDGS is not in operational use or unserviceable, shall be provided.

#### **Location**

5.3.26.5 The A-VDGS shall be located such that unobstructed and unambiguous guidance is provided to the person responsible for, and persons assisting, the docking of the aircraft throughout the docking manoeuvre.

Note.— Usually the pilot-in-command is responsible for the docking of the aircraft. However, in some circumstances, another person could be responsible and

this person may be the driver of a vehicle that is towing the aircraft.

### **Characteristics**

5.3.26.6 The A-VDGS shall provide, at minimum, the following guidance information at the appropriate stage of the docking manoeuvre:

- a. an emergency stop indication;
- b. the aircraft type and model for which the guidance is provided;
- c. an indication of the lateral displacement of the aircraft relative to the stand centre line;
- d. the direction of azimuth correction needed to correct a displacement from the stand centre line;
- e. an indication of the distance to the stop position;
- f. an indication when the aircraft has reached the correct stopping position; and
- g. a warning indication if the aircraft goes beyond the appropriate stop position.

5.3.26.7 The A-VDGS shall be capable of providing docking guidance information for all aircraft taxi speeds encountered during the docking manoeuvre.

*Note.— See the Aerodrome Design Manual, Part 4, for an indication of the maximum aircraft speeds relative to distance to the stopping position.*

5.3.26.8 The time taken from the determination of the lateral displacement to its display shall not result in a deviation of the aircraft, when operated in normal conditions, from the stand centreline greater than 1 m.

5.3.26.9 The information on displacement of the aircraft relative to the stand centre line and distance to the stopping position, when displayed, should be provided with the accuracy specified in Table 5.4

5.3.26.10 Symbols and graphics used to depict guidance information shall be intuitively representative of the type of information provided.

*Note.— The use of colour would need to be appropriate and need to follow signal convention, i.e. red, yellow and green mean hazard, caution and normal/correct conditions, respectively. The effects of colour contrasts would also need to be considered.*

5.3.26.11 Information on the lateral displacement of the aircraft relative to the stand centre line shall be provided at least 25m prior to the stop position.

*Note.— The indication of the distance of the aircraft from the stop position may be colour-coded and presented at a*

rate and distance proportional to the actual closure rate and distance of the aircraft approaching the stop point.

5.3.26.12 Continuous closure distance and closure rate shall be provided from at least 15 m prior to the stop position.

5.3.26.13 Where provided, closure distance displayed in numerals should be provided in metre integers to the stop position and displayed to 1 decimal place at least 3 m prior to the stop position.

5.3.26.14 Throughout the docking manoeuvre, an appropriate means shall be provided on the AVDGS to indicate the need to bring the aircraft to an immediate halt. In such an event, which includes a failure of the A-VDGS, no other information shall be displayed.

5.3.26.15 Provision to initiate an immediate halt to the docking procedure shall be made available to personnel responsible for the operational safety of the stand

5.3.26.16 The word “STOP” in red characters should be displayed when an immediate cessation of the docking manoeuvre is required

### **5.3.27 Aircraft stand manoeuvring guidance lights Application**

5.3.27.1 Aircraft stand maneuvering guidance lights should be provided to facilitate the positioning of an aircraft on an aircraft stand on a paved apron or on a de-icing/anti-icing facility intended for use in poor visibility conditions, unless adequate guidance is provided by other means.

#### **Location**

5.3.27.2 Aircraft stand maneuvering guidance lights shall be collocated with the aircraft stand markings.

#### **Characteristics**

5.3.27.3 Aircraft stand maneuvering guidance lights, other than those indicating a stop position, shall be fixed yellow lights, visible throughout the segments within which they are intended to provide guidance.

5.3.27.4 The lights used to delineate lead-in, turning and lead-out lines should be spaced at intervals of not more than 7.5 m on curves and 15 m on straight sections.

5.3.27.5 The lights indicating a stop position shall be fixed, unidirectional lights, showing red.

5.3.27.6 The intensity of the lights should be adequate for the condition of visibility and ambient light in which the use of the aircraft stand is intended.

5.3.27.7 The lighting circuit should be designed so that the lights may be switched on to indicate that an aircraft

stand is to be used and switched off to indicate that it is not to be used.

### 5.3.28 No-entry bar

Note 1.— A no-entry bar is intended to be controlled manually by air traffic services.

Note 2.— Runway incursions may take place in all visibility or weather conditions. The provision of no-entry bars at taxiway/runway intersections and their use at night and in all visibility conditions can form part of effective runway incursion prevention measures.

#### Application

5.3.28.1 A no-entry bar should be provided across a taxiway which is intended to be used as an exit only taxiway to assist in preventing inadvertent access of traffic to that taxiway.

#### Location

5.3.28.2 A no-entry bar should be located across the taxiway at the end of an exit only taxiway where it is desired to prevent traffic from entering the taxiway in the wrong direction.

#### Characteristics

5.3.28.3 A no-entry bar should consist of unidirectional lights spaced at uniform intervals of no more than 3 m showing red in the intended direction(s) of approach to the runway.

Note.— Where necessary to enhance conspicuity, extra lights are installed uniformly.

5.3.28.4 A pair of elevated lights should be added to each end of the no-entry bar where the in-pavement no entry bar lights might be obscured from a pilot's view, for example, by snow or rain, or where a pilot may be required to stop the aircraft in a position so close to the lights that they are blocked from view by the structure of the aircraft.

5.3.28.5 The intensity in red light and beam spreads of no-entry bar lights shall be in accordance with the specifications in Appendix 2, Figures A2-12 through A2-16, as appropriate

5.3.28.6.— Where no-entry bars are specified as components of an advanced surface movement guidance and control system and where, from an operational point of view, higher intensities are required to maintain ground movements at a certain speed in very low visibilities or in bright daytime conditions, the intensity in red light and beam spreads of no-entry bar lights should be in accordance with the specifications of Appendix 2, Figure A2-17, A2-18 or A2-19.

Note.— High-intensity no-entry bars are typically only used in case of an absolute necessity and following a specific study.

5.3.28.7 Where a wide beam fixture is required, the intensity in red light and beam spreads of no-entry bar lights should be in accordance with the specifications of Appendix 2, Figure A2-17 or A2-19.

5.3.28.8 The lighting circuit shall be designed so that:

- a) no-entry bars are switchable selectively or in groups;
- b) when a no-entry bar is illuminated, any taxiway centre line lights installed beyond the no-entry bar, when viewed towards the runway, shall be extinguished for a distance of at least 90 m; and
- c) when a no-entry bar is illuminated, any stop bar installed between the no-entry bar and the runway shall be extinguished

### 5.3.29 Road-holding position light

#### Application

5.3.29.1 A road-holding position light shall be provided at each road-holding position serving a runway when it is intended that the runway will be used in runway visual range conditions less than a value of 350 m.

5.3.29.2 A road-holding position light should be provided at each road-holding position serving a runway when it is intended that the runway will be used in runway visual range conditions of values between 350 m and 550 m.

#### Location

5.3.29.3 A road-holding position light shall be located adjacent to the holding position marking 1.5 m ( $\pm$  0.5 m) from one edge of the road, i.e. left or right as appropriate to the local traffic regulations

Note.— See 9.9 for the mass and height limitations and frangibility requirements of navigation aids located on runway strips.

#### Characteristics

5.3.29.4 The road-holding position light shall comprise:

- a) a controllable red (stop)/green (go) traffic light; or
- b) a flashing-red light

Note.— It is intended that the lights specified in subparagraph a) be controlled by the air traffic services.

5.3.29.5 The road-holding position light beam shall be unidirectional and aligned so as to be visible to the driver of a vehicle approaching the holding position.



5.3.29.6 The intensity of the light beam shall be adequate for the conditions of visibility and ambient light in which the use of the holding position is intended, but shall not dazzle the driver.

Note.— The commonly used traffic lights are likely to meet the requirements in 5.3.26.5 and 5.3.26.6.

5.3.29.7 The flash frequency of the flashing-red light shall be between 30 and 60 per minute.

## 5.4 Signs

### 5.4.1 General

Note.— Signs shall be either fixed message signs or variable message signs. Guidance on signs is contained in the ICAO Aerodrome Design Manual, Part 4.

#### Application

5.4.1.1 Signs shall be provided to convey a mandatory instruction, information on a specific location or destination on a movement area or to provide other information to meet the requirements of 9.8.1.

Note.— See 5.2.17 for specifications on information marking.

5.4.1.2 A variable message sign should be provided where:

- a) the instruction or information displayed on the sign is relevant only during a certain period of time; and/or
- b) there is a need for variable pre-determined information to be displayed on the sign to meet the requirements of 9.8.1.

#### Characteristics

5.4.1.3 Signs shall be frangible. Those located near a runway or taxiway shall be sufficiently low to preserve clearance for propellers and the engine pods of jet aircraft. The installed height of the sign shall not exceed the dimension shown in the appropriate column of Table 5-4.

5.4.1.4 Signs shall be rectangular, as shown in Figures 5-28 and 5-29 with the longer side horizontal.

5.4.1.5 The only signs on the movement area utilizing red shall be mandatory instruction signs.

5.4.1.6 The inscriptions on a sign shall be in accordance with the provisions of Appendix 4.

5.4.1.7 Signs shall be illuminated in accordance with the provisions of Appendix 4 when intended for use:

- a) in runway visual range conditions less than a value of 800 m; or
- b) at night in association with instrument runways; or
- c) at night in association with non-instrument runways where the code number is 3 or 4.

5.4.1.8 Signs shall be retro reflective and/or illuminated in accordance with the provisions of Appendix 4 when intended for use at night in association with non-instrument runways where the code number is 1 or 2.

5.4.1.9 A variable message sign shall show a blank face when not in use.

5.4.1.10 In case of failure, a variable message sign shall not provide information that could lead to unsafe action from a pilot or a vehicle driver.

5.4.1.11 The time interval to change from one message to another on a variable message sign should be as short as practicable and should not exceed 5 seconds.

### 5.4.2 Mandatory instruction signs

Note.— See Figure 5-28 for pictorial representation of mandatory instruction signs and Figure 5-30 for examples of locating signs at taxiway/runway intersections

#### Application

5.4.2.1 A mandatory instruction sign shall be provided to identify a location beyond which an aircraft taxiing or vehicle shall not proceed unless authorized by the aerodrome control tower.

5.4.2.2 Mandatory instruction signs shall include runway designation signs, category I, II or III holding position signs, runway-holding position signs, road-holding position signs and NO ENTRY signs.

Note.— See 5.4.7 for specifications on road-holding position signs.

5.4.2.3 A pattern “A” runway-holding position marking shall be supplemented at a taxiway/runway intersection or a runway/runway intersection with a runway designation sign.

5.4.2.4 A pattern “B” runway-holding position marking shall be supplemented with a category I, II or III holding position sign.

5.4.2.5 A pattern “A” runway-holding position marking at a runway-holding position established in accordance with 3.12.3 shall be supplemented with a runway-holding position sign.

Note.— See 5.2.10 for specifications on runway-holding position marking.

5.4.2.6 A runway designation sign at a taxiway/runway intersection should be supplemented with a location sign in the outboard (farthest from the taxiway) position, as appropriate.

Note.— See 5.4.3 for characteristics of location signs.

5.4.2.7 A NO ENTRY sign shall be provided when entry into an area is prohibited.

#### **Location**

5.4.2.8 A runway designation sign at a taxiway/runway intersection or a runway/runway intersection shall be located on each side of the runway-holding position marking facing the direction of approach to the runway.

5.4.2.9 A category I, II or III holding position sign shall be located on each side of the runway-holding position marking facing the direction of the approach to the critical area.

5.4.2.10 A NO ENTRY sign shall be located at the beginning of the area to which entrance is prohibited on each side of the taxiway as viewed by the pilot.

5.4.2.11 A runway-holding position sign shall be located on each side of the runway-holding position established in accordance with 3.12.3, facing the approach to the obstacle limitation surface or ILS/MLS critical/sensitive area, as appropriate.

#### **Characteristics**

5.4.2.12 A mandatory instruction sign shall consist of an inscription in white on a red background.

5.4.2.13 Where, owing to environmental or other factors, the conspicuity of the inscription on a mandatory instruction sign needs to be enhanced, the outside edge of the white inscription should be supplemented by a black outline measuring 10 mm in width for runway code numbers 1 and 2, and 20 mm in width for runway code numbers 3 and 4.

5.4.2.14 The inscription on a runway designation sign shall consist of the runway designations of the intersecting runway properly oriented with respect to the viewing position of the sign, except that a runway designation sign installed in the vicinity of a runway extremity may show the runway designation of the concerned runway extremity only.

5.4.2.15 The inscription on a category I, II, III or joint II/III holding position sign shall consist of the runway designator followed by CAT I, CAT II, CAT III or CAT II/III, as appropriate.


5.4.2.16 The inscription on a NO ENTRY sign shall be in accordance with Figure 5-28.

5.4.2.17 The inscription on a runway-holding position sign at a runway-holding position established in accordance with 3.12.3 shall consist of the taxiway designation and a number.



Sign height (mm)				Perpendicular distance from defined taxiway pavement edge to near side of sign	Perpendicular distance from defined runway pavement edge to near side of sign
Code Number	Legend	Face (min.)	Installed (max.)		
1 or 2	200	400	700	5-11 m	3-10 m
1 or 2	300	600	900	5-11 m	3-10 m
3 or 4	300	600	900	11-21 m	8-15 m
3 or 4	400	800	1100	11-21 m	8-15 m

**Table 5-4 Location distances for taxing guidance signs including runway exit signs**






Figure 5.30. Mandatory instruction signs







Figure 5-31. Information signs

NON-INSTRUMENT, NON-PRECISION, TAKE-OFF RUNWAYS





PRECISION APPROACH RUNWAYS

CATEGORY I



CATEGORY II



CATEGORY III





Figure 5-32. Examples of sign positions at taxiway/runway intersections

5.4.2.18 Where appropriate, the following inscriptions/symbol shall be used:

Inscription/ Symbol	Use
Runway designation of a runway extremity, Or	To indicate a runway-holding position at a runway extremity
Runway designation of both extremities of a runway	To indicate a runway-holding position located at other taxiway/runway intersections or runway/runway intersections
25 CAT I (Example)	To indicate a category I runway- holding position at the threshold of runway 25
25 CAT II (Example)	To indicate a category II runway- holding position at the threshold of runway 25
25 CAT III (Example)	To indicate a category III runway- holding position at the threshold of runway 25
25 CAT II/III (Example)	To indicate a joint category II/III runway-holding position at the threshold of runway 25
NO ENTRY symbol	To indicate that entry to an area is prohibited
B2 (Example)	To indicate a runway-holding position established in accordance with 3.12.3

### 5.4.3 Information signs

Note. — See Figure 5-29 for pictorial representations of Information signs.

#### Application

5.4.3.1 An information sign shall be provided where there is an operational need to identify by a sign, a specific location, or routing (direction or destination) information.

5.4.3.2 Information signs shall include: direction signs, location signs, destination signs, runway exit signs, runway vacated signs and intersection take-off signs.

5.4.3.3 A runway exit sign shall be provided where there is an operational need to identify a runway exit.

5.4.3.4 A runway vacated sign shall be provided where the exit taxiway is not provided with taxiway center line light sand there is a need to indicate to a pilot leaving a runway the perimeter of the ILS/MLS critical/sensitive area or the lower edge of the inner transitional surface whichever is farther from the runway center line.

Note.— See 5.3.16 for specifications on color coding taxiway center line lights.

5.4.3.5 An intersection take-off sign should be provided when there is an operational need to indicate the remaining take-off run available (TORA) for intersection take-offs.

5.4.3.6 Where necessary, a destination sign should be provided to indicate the direction to a specific destination on the aerodrome, such as cargo area, general aviation, etc.

5.4.3.7 A combined location and direction sign shall be provided when it is intended to indicate routing information prior to a taxiway intersection

5.4.3.8 A direction sign shall be provided when there is an operational need to identify the designation and direction of taxiways at an intersection.

5.4.3.9 A location sign should be provided at an intermediate holding position.

5.4.3.10 A location sign shall be provided in conjunction with a runway designation sign except at a runway/runway intersection.

5.4.3.11 A location sign shall be provided in conjunction with a direction sign, except that it may be omitted where an aeronautical study indicates that it is not needed.

5.4.3.12 Where necessary, a location sign should be provided to identify taxiways exiting an apron or taxiways beyond an intersection.

5.4.3.13 Where a taxiway ends at an intersection such as a “T” and it is necessary to identify this, a barricade, direction sign and/or other appropriate visual aid should be used.

#### Location

5.4.3.14 Except as specified in 5.4.3.16 and 5.4.3.24 information signs shall, wherever practicable, be located on the left-hand side of the taxiway in accordance with Table 5-4.

5.4.3.15 At a taxiway intersection, information signs shall be located prior to the intersection and in line with the taxiway intersection marking. Where there is no taxiway intersection marking, the signs shall be installed at least 60 m from the center line of the intersecting taxiway where the code number is 3 or 4 and at least 40 m where the code number is 1 or 2.

Note.— A location sign installed beyond a taxiway intersection may be installed on either side of a taxiway.

5.4.3.16 A runway exit sign shall be located on the same side of the runway as the exit is located (i.e. left or right) and positioned in accordance with Table 5-4.

5.4.3.17 A runway exit sign shall be located prior to the runway exit point in line with a position at least 60 m prior to the point of tangency where the code number is 3 or 4, and at least 30 m where the code number is 1 or 2.

5.4.3.18 A runway vacated sign shall be located at least on one side of the taxiway. The distance between the sign and the center line of a runway shall be not less than the greater of the following:

- a) the distance between the center line of the runway and the perimeter of the ILS/MLS critical/sensitive area; or
- b) the distance between the center line of the runway and the lower edge of the inner transitional surface.

5.4.3.19 Where provided in conjunction with a runway vacated sign, the taxiway location sign shall be positioned outboard of the runway vacated sign.

5.4.3.20 An intersection take-off sign shall be located at the left-hand side of the entry taxiway. The distance between the sign and the center line of the runway shall be not less than 60 m where the code number is 3 or 4 and not less than 45 m where the code number is 1 or 2.

5.4.3.21 A taxiway location sign installed in conjunction with a runway designation sign shall be positioned outboard of the runway designation sign.

5.4.3.22 A destination sign should not normally be collocated with a location or direction sign.

5.4.3.23 An information sign other than a location sign shall not be collocated with a mandatory instruction sign.

5.4.3.24 A direction sign, barricade and/or other appropriate visual aid used to identify a “T” intersection should be located on the opposite side of the intersection facing the taxiway.

#### **Characteristics**

5.4.3.25 An information sign other than a location sign shall consist of an inscription in black on a yellow background.

5.4.3.26 A location sign shall consist of an inscription in yellow on a black background and where it is a stand-alone sign shall have a yellow border.

5.4.3.27 The inscription on a runway exit sign shall consist of the designator of the exit taxiway and an arrow indicating the direction to follow.

5.4.3.28 The inscription on a runway vacated sign shall depict the pattern A runway-holding position marking as shown in Figure 5-29.

5.4.3.29 The inscription on an intersection take-off sign shall consist of a numerical message indicating the remaining take-off run available in meters plus an arrow, appropriately located and oriented, indicating the direction of the take-off as shown in Figure 5-29.

5.4.3.30 The inscription on a destination sign shall comprise an alpha, alphanumeric or numerical message identifying the destination plus an arrow indicating the direction to proceed as shown in Figure 5-29.

5.4.3.31 The inscription on a direction sign shall comprise an alpha or alphanumeric message identifying the taxiway(s) plus an arrow or arrows appropriately oriented as shown in Figure 5-29.

5.4.3.32 The inscription on a location sign shall comprise the designation of the location taxiway, runway or other pavement the aircraft is on or is entering and shall not contain arrows.

5.4.3.33 Where it is necessary to identify each of a series of intermediate holding positions on the same taxiway, the location sign should consist of the taxiway designation and a number.

5.4.3.34 Where a location sign and direction signs are used in combination:

- a) all direction signs related to left turns shall be placed on the left side of the location sign and all direction signs related to right turns shall be placed on the right side of the location sign, except that where the junction consists of one intersecting taxiway, the location sign may alternatively be placed on the left hand side;
- b) the direction signs shall be placed such that the direction of the arrows departs increasingly from the vertical with increasing deviation of the corresponding taxiway;
- c) an appropriate direction sign shall be placed next to the location sign where the direction of the location taxiway changes significantly beyond the intersection; and
- d) adjacent direction signs shall be delineated by a vertical black line as shown in Figure 5-29.

5.4.3.35 A taxiway shall be identified by a designator comprising a letter, letters or a combination of a letter or letters followed by a number.

5.4.3.36 When designating taxiways, the use of the letters I, O or X and the use of words such as inner and outer should be avoided wherever possible to avoid confusion with the numerals 1, 0 and closed marking.



5.4.3.37 the use of numbers alone on the maneuvering area shall be reserved for the designation of runways.

#### **5.4.4 VOR aerodrome check-point sign Application**

5.4.4.1 When a VOR aerodrome check-point is established, it shall be indicated by a VOR aerodrome check-point marking and sign.

Note.— See 5.2.12 for VOR aerodrome check-point marking.

5.4.4.2 A VOR aerodrome check-point sign shall be located as near as possible to the check-point and so that the inscriptions are visible from the cockpit of an aircraft properly positioned on the VOR aerodrome check-point marking.

##### **Characteristics**

5.4.4.3 A VOR aerodrome check-point sign shall consist of an inscription in black on a yellow background.

5.4.4.4 The inscriptions on a VOR check-point sign should be in accordance with one of the alternatives shown in Figure 5-31 in which:

- |        |  |
|--------|--|
| VOR    | is an abbreviation identifying this as a VOR check-point;  |
| 116.3  | is an example of the radio frequency of the VOR concerned;   |
| 147°   | is an example of the VOR bearing, to the nearest degree, which should be indicated at the VOR check-point; and |
| 4.3 NM | is an example of the distance in nautical miles to a DME collocated with the VOR concerned.                    |

Note.— Tolerances for the bearing value shown on the sign are given in GACAR Section 10 and ICAO Annex 10, Volume I, Attachment E. It will be noted that a check-point can only be used operationally when periodic checks show it to be consistently within  $\pm 2$  degrees of the stated bearing.

5.4.5.1 An aerodrome identification sign should be provided at an aerodrome where there is insufficient alternative means of visual identification.

##### **Location**

5.4.5.2 The aerodrome identification sign should be placed on the aerodrome so as to be legible, in so far as is practicable, at all angles above the horizontal.

##### **Characteristics**

5.4.5.3 The aerodrome identification sign shall consist of the name of the aerodrome.

5.4.5.4 The color selected for the sign should give adequate conspicuity when viewed against its background.

5.4.5.5 The characters should have a height of not less than 3 m. 5.4.6 Aircraft stand identification signs

#### **5.4.6 Aircraft stand identification signs**

##### **Application**

5.4.6.1 An aircraft stand identification marking should be supplemented with an aircraft stand identification sign where feasible.

##### **Location**

5.4.6.2 An aircraft stand identification sign should be located so as to be clearly visible from the cockpit of an aircraft prior to entering the aircraft stand.


##### **Characteristics**

5.4.6.3 An aircraft stand identification sign should consist of an inscription in black on a yellow background.

**Intentionally left blank**

#### **5.4.5 Aerodrome identification sign**


##### **Application**



(A)

(B)

Where no DME is collocated with the VOR




(C)

(D)

Where a DME is collocated with the VOR

**Figure 5-33. VOR aerodrome check-point sign**



#### 5.4.7 Road-holding position sign

5.4.7.1 A road-holding position sign shall be provided at all road entrances to a runway.

##### Location

5.4.7.2 The road-holding position sign shall be located 1.5 m from one edge of the road (left or right as appropriate to the local traffic regulations) at the holding position.

##### Characteristics

5.4.7.3 A road-holding position sign shall consist of an inscription in white on a red background.

5.4.7.4 The inscription on a road-holding position sign shall be in the national language, be in conformity with the local traffic regulations and include the following:

- a) a requirement to stop; and
- b) Where appropriate:
  1. a requirement to obtain ATC clearance; and
  2. location designator.

Note.— Examples of road-holding position signs are contained in the ICAO Aerodrome Design Manual (Doc 9157), Part 4.

5.4.7.5 A road-holding position sign intended for night use shall be retroreflective or illuminated.

### 5.5 Markers

#### 5.5.1 General

Markers shall be frangible. Those located near a runway or taxiway shall be sufficiently low to preserve clearance for propellers and for the engine pods of jet aircraft.

Note 1.— Anchors or chains, to prevent markers which have broken from their mounting from blowing away, are sometimes used.

Note 2.— Guidance on frangibility of markers is given in the ICAO Aerodrome Design Manual (Doc 9157), Part 6.

#### 5.5.2 Unpaved runway edge markers

##### Application

5.5.2.1 **Markers** should be provided when the extent of an unpaved runway is not clearly indicated by the appearance of its surface compared with that of the surrounding ground.

##### Location

5.5.2.2 Where runway lights are provided, the markers should be incorporated in the light fixtures. Where there are no lights, markers of flat rectangular or conical shape should be placed so as to delimit the runway clearly.

##### Characteristics

5.5.2.3 The flat rectangular markers should have a minimum size of 1 m by 3 m and should be placed with their long dimension parallel to the runway center line. The conical markers should have a height not exceeding 50 cm

#### 5.5.3 Stopway edge markers

##### Application

5.5.3.1 Stopway edge markers should be provided when the extent of a stopway is not clearly indicated by its appearance compared with that of the surrounding ground.

##### Characteristics

5.5.3.2 The stopway edge markers shall be sufficiently different from any runway edge markers used to ensure that the two types of markers cannot be confused.

Note.— Markers consisting of small vertical boards camouflaged on the reverse side, as viewed from the runway, have proved operationally acceptable.

#### 5.5.4 Edge markers for snow-covered runways

##### Application

5.5.4.1 Edge markers for snow covered runways should be used to indicate the usable limits of a snow-covered runway when the limits are not otherwise indicated.

Note.— Runway lights could be used to indicate the limits.

##### Location

5.5.4.2 Edge markers for snow covered runways should be placed along the sides of the runway at intervals of not more than 100 m, and should be located symmetrically about the runway center line at such a distance from the center line that there is adequate clearance for wing tips and power plants. Sufficient markers should be placed across the threshold and end of the runway.

##### Characteristics

5.5.4.3 Edge markers for snow covered runways should consist of conspicuous objects such as evergreen trees about 1.5 m high or light-weight markers.

#### 5.5.5 Taxiway edge markers

##### Application

5.5.5.1 Taxiway edge markers should be provided on a taxiway where the code number is 1 or 2 and taxiway center line or edge lights or taxiway center line markers are not provided.

##### Location

5.5.5.2. Taxiway edge markers should be installed at least at the same locations as would the taxiway edge lights had they been used.

### **Characteristics**

5.5.5.3 A taxiway edge marker shall be retro reflective blue.

5.5.5.4 The marked surface as viewed by the pilot should be a rectangle and should have a minimum viewing area of 150 cm<sup>2</sup>.

5.5.5.5 Taxiway edge markers shall be frangible. Their height shall be sufficiently low to preserve clearance for propellers and for the engine pods of jet aircraft.

### **5.5.6 Taxiway center line markers**

#### **Application**

5.5.6.1 Taxiway center line markers should be provided on a taxiway where the code number is 1 or 2 and taxiway center line or edge lights or taxiway edge markers are not provided.

5.5.6.2 Taxiway center line markers should be provided on a taxiway where the code number is 3 or 4 and taxiway center line lights are not provided if there is a need to improve the guidance provided by the taxiway center line marking.

#### **Location**

5.5.6.3 Taxiway center line markers should be installed at least at the same location as would taxiway center line lights had they been used.

Note.— See 5.3.16.12 for the spacing of taxiway center line lights.

5.5.6.4.— Taxiway center line markers should normally be located on the taxiway center line marking except that they may be offset by not more than 30 cm where it is not practicable to locate them on the marking.

#### **Characteristics**

5.5.6.5 A taxiway center line marker shall be retroreflective green.

5.5.6.6 The marked surface as viewed by the pilot should be a rectangle and should have a minimum viewing area of 20 cm<sup>2</sup>.

5.5.6.7 Taxiway center line markers shall be so designed and fitted as to withstand being run over by the wheels of an aircraft without damage either to the aircraft or to the markers themselves.

### **5.5.7 Unpaved taxiway edge markers**

#### **Application**

5.5.7.1 Where the extent of an unpaved taxiway is not clearly indicated by its appearance compared with that of the surrounding ground, markers should be provided.

#### **Location**

5.5.7.2 Where taxiway lights are provided, the markers should be incorporated in the light fixtures. Where there are no lights, markers of conical shape should be placed so as to delimit the taxiway clearly.

### **5.5.8 Boundary markers**

#### **Application**

5.5.8.1 Boundary markers shall be provided at an aerodrome where the landing area has no runway.


#### **Location**

5.5.8.2 Boundary markers shall be spaced along the boundary of the landing area at intervals of not more than 200 m, if the type shown in Figure 5-32 is used, or approximately 90 m, if the conical type is used with a marker at any corner.

#### **Characteristics**

5.5.8.3 Boundary markers should be of a form similar to that shown in Figure 5-32, or in the form of a cone not less than 50 cm high and not less than 75 cm in diameter at the base. The markers should be colored to contrast with the background against which they will be seen. A single color, orange or red, or two contrasting colors, orange and white or alternatively red and white, should be used, except where such colors merge with the background

**Intentionally left blank**



**Figure 5-34. VOR aerodrome check-point sign**



## **CHAPTER 6 - VISUAL AIDS FOR DENOTING OBSTACLES**

### **6.1 Objects to be marked and/or lighted**

Note. — The marking and/or lighting of obstacles is intended to reduce hazards to aircraft by indicating the presence of the obstacles. It does not necessarily reduce operating limitations which may be imposed by an obstacle.

#### **6.1.1 Objects within the lateral boundaries of the obstacle limitation surfaces**

6.1.1.1 Vehicles and other mobile objects, excluding aircraft, on the movement area of an aerodrome are obstacles and shall be marked and, if the vehicles and aerodrome are used at night or in conditions of low visibility, lighted, except that aircraft servicing equipment and vehicles used only on aprons may be exempt.

6.1.1.2 Elevated aeronautical ground lights within the movement area shall be marked so as to be conspicuous by day. Obstacle lights shall not be installed on elevated ground lights or signs in the movement area.

6.1.1.3 All obstacles within the distance specified in Table 3-1, column 11 or 12, from the centre line of a taxiway, an apron taxiway or aircraft stand taxiway shall be marked and, if the taxiway, apron taxiway or aircraft stand taxiway is used at night, lighted.

6.1.1.4 A fixed obstacle that extends above a take-off climb surface within 3,000 m of the inner edge of the take-off climb surface should be marked and, if the runway is used at night, lighted, except that:

- a) such marking and lighting may be omitted when the obstacle is shielded by another fixed obstacle;
- b) the marking may be omitted when the obstacle is lighted by medium-intensity obstacle lights, Type A, by day and its height above the level of the surrounding ground does not exceed 150 m;
- c) the marking may be omitted when the obstacle is lighted by high-intensity obstacle lights by day; and
- d) the lighting may be omitted where the obstacle is a lighthouse and an aeronautical study indicates the lighthouse light to be sufficient.

6.1.1.5 A fixed object, other than an obstacle, adjacent to a take-off climb surface should be marked and, if the runway is used at night, lighted if such marking and lighting is considered necessary to ensure its avoidance,

except that the marking may be omitted when:

- a) the object is lighted by medium-intensity obstacle lights Type A, by day and its height above the level of the surrounding ground does not exceed 150 m; or
- b) the object is lighted by high-intensity obstacle lights by day.

6.1.1.6 A fixed obstacle that extends above an approach surface within 3,000 m of the inner edge or above a transitional surface shall be marked and, if the runway is used at night, lighted, except that:

- a) such marking and lighting may be omitted when the obstacle is shielded by another fixed obstacle;
- b) the marking may be omitted when the obstacle is lighted by medium-intensity obstacle lights, Type A, by day and its height above the level of the surrounding ground does not exceed 150 m;
- c) the marking may be omitted when the obstacle is lighted by high-intensity obstacle lights by day; and
- d) the lighting may be omitted where the obstacle is a lighthouse and an aeronautical study indicates the lighthouse light to be sufficient.

6.1.1.7 A fixed obstacle that extends above a horizontal surface should be marked and, if the aerodrome is used at night, lighted except that:

- a) such marking and lighting may be omitted when:
  - 1) the obstacle is shielded by another fixed obstacle; or
  - 2) for a circuit extensively obstructed by immovable objects or terrain, procedures have been established to ensure safe vertical clearance below prescribed flight paths; or
  - 3) an aeronautical study shows the obstacle not to be of operational significance;
- b) the marking may be omitted when the obstacle is lighted by medium-intensity obstacle lights, Type A, by day and its height above the level of the surrounding ground does not exceed 150 m;
- c) the marking may be omitted when the obstacle is lighted by high-intensity obstacle lights by day; and
- d) the lighting may be omitted where the obstacle is a lighthouse and an aeronautical study indicates



the lighthouse light to be sufficient.

6.1.1.8 A fixed object that extends above an obstacle protection surface shall be marked and, if the runway is used at night, lighted.

Note. — See 5.3.5 for information on the obstacle protection surface.

6.1.1.9 – Other objects inside the obstacle limitation surfaces should be marked and/or lighted if an aeronautical study indicates that the object could constitute a hazard to aircraft (this includes objects adjacent to visual routes e.g. waterway or highway).

Note.- See note below 4.4.2.

6.1.1.10 Overhead wires, cables, etc., crossing a river, waterway, valley or highway should be marked and their supporting towers marked and lighted if an aeronautical study indicated that the wires or cables could constitute a hazard to aircraft.

## **6.1.2 Objects outside the lateral boundaries of the obstacle limitation surfaces**

6.1.2.1 Obstacles in accordance with 4.3.2 should be marked and lighted, except that the marking may be omitted when the obstacle is lighted by high-intensity obstacle lights by day.

6.1.2.2 Other objects outside the obstacle limitation surfaces should be marked and/or lighted if an aeronautical study indicates that the object could constitute a hazard to aircraft (this includes objects adjacent to visual routes e.g. waterway, highway).

6.1.2.3 Overhead wires, cables, etc., crossing a river, waterway, valley or highway should be marked and their supporting towers marked and lighted if an aeronautical study indicates that the wires or cables could constitute a hazard to aircraft.

## **6.2 Marking and/or lighting of objects**

### **6.2.1 General**

6.2.1.1 The presence of objects which must be lighted, as specified in 6.1, shall be indicated by low-, medium- or high-intensity obstacle lights, or a combination of such lights.

6.2.1.2 Low-intensity obstacle lights, Types A B, C and D, medium-intensity obstacle lights, types A, B and C, high-intensity obstacle lights Type A and B, shall be in accordance with the specifications in Table 6-3 and

### **Appendix 1**

6.2.1.3 The number and arrangement of low-, medium- or high-intensity obstacle lights at each level to be marked shall be such that the object is indicated from every angle in azimuth. Where a light is shielded in any direction by another part of the object, or by an adjacent object, additional lights shall be provided on that adjacent object or the part of the object that is shielding the light, in such a way as to retain the general definition of the object to be lighted. If the shielded light does not contribute to the definition of the object to be lighted, it may be omitted.

### **6.2.2 Mobile objects**

#### **Marking**

6.2.2.1 All mobile objects to be marked shall be colored or display flags.

#### **Marking by colour**

6.2.2.2 When mobile objects are marked by color, a single conspicuous color, preferably red or yellowish green for emergency vehicles and yellow for service vehicles should be used.

#### **Marking by flags**

6.2.2.3 Flags used to mark mobile objects shall be displayed around, on top of, or around the highest edge of, the object. Flags shall not increase the hazard presented by the object they mark.

6.2.2.4 Flags used to mark mobile objects shall not be less than 0.9 m on each side and shall consist of a chequered pattern, each square having sides of not less than 0.3 m. The colours of the pattern shall contrast each with the other and with the background against which they will be seen. Orange and white or alternatively red and white shall be used, except where such colours merge with the background.

#### **Lighting**

6.2.2.5 Low-intensity obstacle lights, Type C, shall be displayed on vehicles and other mobile objects excluding aircraft.

Note – See Annex 2 for lights to be displayed by aircraft.

6.2.2.6 Low-intensity obstacle lights, Type C, displayed on vehicles associated with emergency or security shall be flashing-blue and those displayed on other vehicles shall be flashing-yellow.

6.2.2.7 Low-intensity obstacle lights, Type D, shall be displayed on follow-me vehicles.

6.2.2.8 Low-intensity obstacle lights on objects with limited mobility such as aerobridges shall be fixed-red, and as a minimum be in accordance with the specifications for low-intensity obstacle lights, type A, in table 6-3. The intensity of the lights shall be sufficient to ensure conspicuity considering the intensity of the adjacent lights and the general levels of illumination against which they would normally be viewed.

### **6.2.3 Fixed objects**

Note.— The fixed objects of wind turbines are addressed separately in 6.2.4 and the fixed objects of overhead wires, cables, etc. and supporting towers are addressed separately in 6.2.5.

#### ***Marking***

6.2.3.1 All fixed objects to be marked shall, whenever practicable, be colored, but if this is not practicable, markers or flags shall be displayed on or above them, except that objects that are sufficiently conspicuous by their shape, size or color need not be otherwise marked.

#### ***Marking by colour***

6.2.3.2 An object should be colored to show a checkered pattern if it has essentially unbroken surfaces and its projection on any vertical plane equals or exceeds 4.5 m in both dimensions. The pattern should consist of rectangles of not less than 1.5 m and not more than 3 m on a side, the corners being of the darker color. The colors of the pattern should contrast each with the other and with the background against which they will be seen. Orange and white or alternatively red and white should be used, except where such colors merge with the background. (See Figure 6-1)

6.2.3.3 An object should be colored to show alternating contrasting bands if:

- a. it has essentially unbroken surfaces and has one dimension, horizontal or vertical, greater than 1.5 m, and the other dimension, horizontal or vertical, less than 4.5 m; or
- b. it is of skeletal type with either a vertical or a horizontal dimension greater than 1.5 m.

The bands should be perpendicular to the longest dimension and have a width approximately 1/7 of the longest dimension or 30 m, whichever is less. The colors of the bands should contrast with the background against which they will be seen. Orange and white should be used, except where such colors are not conspicuous when

viewed against the background. The bands on the extremities of the object should be of the darker color. (See Figures 6-1 and 6-2)

Note. — Table 6-1 shows a formula for determining band widths and for having an odd number of bands, thus permitting both the top and bottom bands to be of the darker color.

6.2.3.4 An object should be colored in a single conspicuous color if its projection on any vertical plane has both dimensions less than 1.5 m. Orange or red should be used, except where such colors merge with the background.

Note. — Against some backgrounds it may be found necessary to use a different color from orange or red to obtain sufficient contrast.

#### ***Marking by flags***

6.2.3.5 Flags used to mark fixed objects shall be displayed around, on top of, or around the highest edge of the object. When flags are used to mark extensive objects or a group of closely spaced objects, they shall be displayed at least every 15 m. Flags shall not increase the hazard presented by the object they mark.

6.2.3.6 Flags used to mark fixed objects shall not be less than 0.6 m on each side.

6.2.3.7 Flags used to mark fixed objects should be orange in colour or a combination of two triangular sections, one orange and the other white, or one red and the other white, except that where such colours merge with the background, other conspicuous colours should be used.

#### ***Marking by markers***

6.2.3.8 Markers displayed on or adjacent to objects shall be located in conspicuous positions so as to retain the general definition of the object and shall be recognizable in clear weather from a distance of at least 1,000 m for an object to be viewed from the air and 300 m for an object to be viewed from the ground in all directions in which an aircraft is likely to approach the object. The shape of markers shall be distinctive to the extent necessary to ensure that they are not mistaken for markers employed to convey other information, and they shall be such that the hazard presented by the object they mark is not increased.

6.2.3.9 A marker should be of one color. When installed, white and red, or white and orange markers should be displayed alternately. The color selected should contrast with the background against which it will be seen.

### ***Lighting***

900 m.

6.2.3.10 In case of an object to be lighted one or more low-, medium- or high-intensity obstacle lights shall be located as close as practicable to the top of the object.

Note. — Recommendations on how a combination of low-, medium-, and/or high-intensity lights on obstacles should be displayed are given in Appendix 6.

6.2.3.11 In the case of chimney or other structure of like function, the top lights should be placed sufficiently below the top so as to minimize contamination by smoke etc. (see figure 6-2).

6.2.3.12 In the case of a tower or antenna structure indicated by high-intensity obstacle lights by day with an appurtenance, such as a rod or an antenna, greater than 12 m where it is not practicable to locate a high-intensity obstacle light on the top of the appurtenance, such a light shall be located at the highest practicable point and, if practicable, a medium-intensity obstacle light, Type A, mounted on the top

6.2.3.13 In the case of an extensive object or of a group of closely spaced objects to be lighted that are:

- a. penetrating a horizontal OLS or located outside an OLS, the top lights shall be so arranged as to at least indicate the points or edges of the object highest in relation to the obstacle limitation surface or above the ground, and so as to indicate the general definition and the extent of the objects; and
- b. penetrating a sloping OLS the top lights shall be so arranged as to at least indicate the points or edges of the object highest in relation to the obstacle limitation surface, and so as to indicate the general definition and the extent of the objects. If two or more edges are of the same height, the edge nearest the landing area shall be marked.

6.2.3.14 When the obstacle limitation surface concerned is sloping and the highest point above the obstacle limitation surface is not the highest point of the object, additional obstacle lights should be placed on the highest point of the object.

6.2.3.15 Where lights are applied to display the general definition of an extensive object or a group of closely spaced objects, and

- a. low-intensity lights are used, they shall be spaced at longitudinal intervals not exceeding 45 m.
- b. medium-intensity lights are used, they shall be spaced at longitudinal intervals not exceeding

6.2.3.16 High-intensity obstacle lights, Type A, medium-intensity obstacle lights, Types A and B, located on an object shall flash simultaneously.

6.2.3.17 Recommendation – The installation setting angles for high-intensity obstacle lights, Type A, should be in accordance with Table 6-2

Note – High intensity obstacle lights are intended for day use as well as night use. Care is needed to ensure that these lights do not create disconcerting dazzle. Guidance on the design, operation and the location of high-intensity obstacle lights is given in the Aerodrome Design Manual, Part 4.

6.2.3.18 Where, in the opinion of the appropriate authority, the use of high-intensity obstacle lights, Type A, or medium-intensity obstacle lights, Type A, at night may dazzle pilots in the vicinity of an aerodrome (within approximately 10,000 m radius) or cause significant environmental concerns, a dual obstacle lighting system should be provided. This system should be composed of high-intensity obstacle lights, Type A or medium intensity Type A obstacle lights, as appropriate, for daytime and twilight use and medium-intensity obstacle lights, Type B or C, for night-time use.

### ***Lighting of objects with a height less than 45m above ground level***

6.2.3.19 Low-intensity obstacle lights, Type A or B, should be used where the object is a less extensive one and its height above the surrounding ground is less than 45 m.

6.2.3.20 Where the use of low-intensity obstacle lights, Type A or B, would be inadequate or an early special warning is required, then medium- or high-intensity obstacle lights should be used.

6.2.3.21 Low-intensity Type B obstacle lights should be used either alone or in combination with medium-intensity obstacle lights, Type B, in accordance with 6.2.3.22.

6.2.3.22 Medium-intensity obstacle lights, Type A, B or C, should be used where the object is an extensive one. Medium-intensity obstacle lights, Types A and C, should be used alone, whereas medium intensity obstacle lights, Type B, should be used either alone or in combination with low-intensity obstacle lights, Type B.

Note. — A group of buildings is regarded as an extensive

object.

***Lighting of objects with a height 45 m to a height less than 150 m above ground level***

6.2.3.23 Medium-intensity obstacle lights, Type A, B or C, should be used. Medium-intensity obstacle lights, Types A and C, should be used alone, whereas medium intensity obstacle lights, Type B, should be used either alone or in combination with low-intensity obstacle lights, Type B.

6.2.3.24 Where an object is indicated by medium-intensity obstacle lights, Type A, and the top of the object is more than 105 m above the level of the surrounding ground or the elevation of tops of nearby buildings (when the object to be marked is surrounded by buildings), additional lights shall be provided at intermediate levels. These additional intermediate lights shall be spaced as equally as practicable, between the top lights and ground level or the level of tops of nearby buildings, as appropriate, with the spacing not exceeding 105 m.

6.2.3.25 Where an object is indicated by medium-intensity obstacle lights, Type B, and the top of the object is more than 45 m above the level of the surrounding ground or the elevation of tops of nearby buildings (when the object to be marked is surrounded by buildings), additional lights shall be provided at intermediate levels. These additional intermediate lights shall be alternately low-intensity obstacle lights, Type B, and medium-intensity obstacle lights, Type B, and shall be spaced as equally as practicable between the top lights and ground level or the level of tops of nearby buildings, as appropriate, with the spacing not exceeding 52 m.

6.2.3.26 Where an object is indicated by medium-intensity obstacle lights, Type C, and the top of the object is more than 45 m above the level of the surrounding ground or the elevation of tops of nearby buildings (when the object to be marked is surrounded by buildings), additional lights shall be provided at intermediate levels. These additional intermediate lights shall be spaced as equally as practicable between the top lights and ground level or the level of tops of nearby buildings, as appropriate, with the spacing not exceeding 52 m.

6.2.3.27 Where high-intensity obstacle lights, Type A, are used, they shall be spaced at uniform intervals not exceeding 105 m between the ground level and the top light(s) specified in 6.2.3.10 except that where an object to be marked is surrounded by buildings, the elevation of the tops of the buildings may be used as the equivalent of the ground level when determining the number of light levels.

***Lighting of objects with a height 150 m or more above ground level***

6.2.3.28 High-intensity obstacle lights, Type A, should be used to indicate the presence of an object if its height above the level of the surrounding ground exceeds 150 m and an aeronautical study indicates such lights to be essential for the recognition of the object by day.

6.2.3.29 Where high-intensity obstacle lights, Type A, are used, they shall be spaced at uniform intervals not exceeding 105 m between the ground level and the top light(s) specified in 6.2.3.10 except that where an object to be marked is surrounded by buildings, the elevation of the tops of the buildings may be used as the equivalent of the ground level when determining the number of light levels.

6.2.3.30 Where, in the opinion of the appropriate authority, the use of high-intensity obstacle lights, Type A, at night may dazzle pilots in the vicinity of an aerodrome (within approximately 10 000 m radius) or cause significant environmental concerns, medium-intensity obstacle lights, Type C, should be used alone, whereas medium-intensity obstacle lights, Type B, should be used either alone or in combination with low-intensity obstacle lights, Type B.

6.2.3.31 Where an object is indicated by medium-intensity obstacle lights, Type A, additional lights shall be provided at intermediate levels. These additional intermediate lights shall be spaced as equally as practicable, between the top lights and ground level or the level of tops of nearby buildings, as appropriate, with the spacing not exceeding 105 m.

6.2.3.32 Where an object is indicated by medium-intensity obstacle lights, Type B, additional lights shall be provided at intermediate levels. These additional intermediate lights shall be alternately low-intensity obstacle lights, type B, and medium-intensity obstacle lights, type B, and shall be spaced as equally as practicable between the top lights and ground level or the level of tops of nearby buildings, as appropriate, with the spacing not exceeding 52 m.

6.2.3.33 Where an object is indicated by medium-intensity obstacle lights, Type C, additional lights shall be provided at intermediate levels. These additional intermediate lights shall be spaced as equally as practicable, between the top lights and ground level or the level of tops of nearby buildings, as appropriate, with the spacing not exceeding 52 m.

**6.2.4 Wind turbines**



### **Markings**

6.2.4.1A wind turbine shall be marked and/or lighted if it is determined to be an obstacle.

Note – see 4.3.1 and 4.3.2

6.2.4.2 The rotor blades, nacelle and upper 2/3 of the supporting mast of wind turbines should be painted white, unless otherwise indicated by an aeronautical study.

### **Lighting**

6.2.4.3 When lighting is deemed necessary, medium intensity obstacle lights should be used. In the case of a wind farm, i.e. group of two or more wind turbines it should be regarded as an extensive object and the lights should be installed:

- a. to identify the perimeter of the wind farm;
- b. respecting the maximum spacing, in accordance with 6.2.3.15, between the lights along the perimeter, unless a dedicated assessment shows that a greater spacing can be used;
- c. so that, where flashing lights are used, they flash simultaneously; and
- d. so that, within a wind farm, any wind turbines of significantly higher elevation are also identified wherever they are located.

6.2.4.4 The obstacle lights should be installed on the nacelle in such a manner as to provide an unobstructed view for aircraft approaching from any direction.

### **6.2.5 Overhead wires, cables, etc. and supporting towers**

#### **Marking**

6.2.5.1 The wires, cables, etc. to be marked should be equipped with markers; the supporting tower should be coloured.

#### **Marking by colours**

6.2.5.2 The supporting towers of overhead wires, cables, etc. that require marking should be marked in accordance with 6.2.3.1 to 6.2.3.4, except that the marking of the supporting towers may be omitted when they are lighted by high-intensity obstacle lights by day.

#### **Marking by markers**

6.2.5.3 Markers displayed on or adjacent to objects shall

be located in conspicuous positions so as to retain the general definition of the object and shall be recognizable in clear weather from a distance of at least 1 000 m for an object to be viewed from the air and 300 m for an object to be viewed from the ground in all directions in which an aircraft is likely to approach the object. The shape of markers shall be distinctive to the extent necessary to ensure that they are not mistaken for markers employed to convey other information, and they shall be such that the hazard presented by the object they mark is not increased.

6.2.5.4 A marker displayed on an overhead wire, cable, etc. should be spherical and have a diameter of not less than 60 cm.

6.2.5.5 The spacing between two consecutive markers or between a marker and a supporting tower should be appropriate to the diameter of the marker, but in no case should the spacing exceed:

- a. 30 m where the marker diameter is 60 cm progressively increasing with the diameter of the marker to
- b. 35 m where the marker diameter is 80 cm and further progressively increasing to a maximum of
- c. 40 m where the marker diameter is of at least 130 cm.

Where multiple wires, cables, etc. are involved, a marker should be located not lower than the level of the highest wire at the point marked.

6.2.5.6 A marker should be of one colour. When installed, white and red, or white and orange markers should be displayed alternately. The colour selected should contrast with the background against which it will be seen.

6.2.5.7 When it has been determined that an overhead wire, cable, etc., needs to be marked but it is not practicable to install markers on the wire, cable, etc., then high-intensity obstacle lights, Type B, should be provided on their supporting towers.

### **Lighting**

6.2.5.8 High intensity obstacle lights, Type B, should be used to indicate the presence of the tower supporting overhead wires, cables, etc. where:

- a. an aeronautical study indicates such light to be essential for the recognition of the presence of wires, cables, etc.; or
- b. it has not been found practicable to install marker on the wires, cables, etc.

6.2.5.9 Where high-intensity obstacle lights, Type B, are used, they shall be located at three levels:

- at the top of the tower;
- at the lowest level of the catenary of the wires or cables; and
- at approximately midway between these two levels.

Note -In some cases, this may require locating the lights off the tower.

6.2.5.10 High-intensity obstacle lights, Type B, indicating the presence of a tower supporting overhead wires, cables, etc., should flash sequentially; first the middle light, second the top light and last, the bottom light. The intervals between flashes of the lights should be approximate the following ratios:

Flash interval between	Ratio of cycle time
middle and top light	1/13
top and bottom light	2/13
bottom and middle light	10/13.

Note. – High intensity obstacle lights are intended for day use as well as night use. Care is needed to ensure that these lights do not create disconcerting dazzle. Guidance on the design, operation and the location of high-intensity obstacle lights is given in the Aerodrome Design Manual (Doc 9157), Part 4.

6.2.5.11 where, in the opinion of the appropriate authority, the use of high-intensity obstacle lights, Type B, at night may dazzle pilots in the vicinity of an aerodrome (within approximately 10 000 m radius) or cause significant environmental concerns, a dual obstacle lighting system should be provided. This system should be composed of high-intensity obstacle lights, Type B, for daytime and twilight use and medium-intensity obstacle lights, Type B, for night-time use. Where medium-intensity lights are used they should be installed at the same level as the high-intensity obstacle light Type B.

6.2.5.12 The installation setting angles for high-intensity obstacle lights, Type B, should be in accordance with Table 6-2.








Figure 9.1. Basic marking patterns



*Note.— H is less than 45 m for the examples shown above.  
For greater heights intermediate lights must be added as shown below.*



Light spacing (X) in accordance with Appendix 6

$$\text{Number of levels of lights} = N = \frac{Y \text{ (metres)}}{X \text{ (metres)}}$$

Figure 6-2. Examples of marking and lighting of tall structures

**GACA REGULATIONS - SECTION 14 - AERODROMES**  
**VOLUME I – AERODROME DESIGN AND OPERATIONS**  
**CHAPTER -6- VISUAL AIDS FOR DENOTING OBSTACLES**

**Table 6-1 Marking band width**

Longest dimension		
Greater than (m)	Not exceeding (m)	Band width
1.5	210	1/7 of longest dimension
210	270	1/9 of longest dimension
270	330	1/11 of longest dimension
330	390	1/13 of longest dimension
390	450	1/15 of longest dimension
450	210	1/17 of longest dimension
510	570	1/19 of longest dimension
570	630	1/21 of longest dimension

**Table 6-2. Installation setting angles for  
high-intensity obstacle lights**

Height of light unit above terrain	Angle of the peak of the beam above the horizontal
greater than 151 m AGL	0°
122 m to 151 m AGL	1°
92 m to 122 m AGL	2°
less than 92 m AGL	3°

Note. — See GACAR Section 2 for lights to be displayed by aircraft.

**Table 6-3. Characteristics of obstacle lights**

1	2	3	4	5	6	7
Light Type	Colour	Signal type/ (Flash rate)	Peak intensity (cd) at given Background Luminance (b)			Light Distribution Table
			Day (Above 500 cd/m <sup>2</sup> )	Twilight (50-500 cd/m <sup>2</sup> )	Night (Below 50 cd/m <sup>2</sup> )	
Low-intensity, Type A (fixed obstacle)	Red	Fixed	N/A	N/A	10	6-X
Low-intensity, Type B (fixed obstacle)	Red	Fixed	N/A	N/A	32	6-X
Low-intensity, Type C (mobile obstacle)	Yellow/ Blue (a)	Flashing (60-90 fpm)	N/A	40	40	6-X
Low-intensity, Type D Follow-me vehicle	Yellow	Flashing (60-90 fpm)	N/A	200	200	6-X
Medium-intensity, Type A	White	Flashing (20-60 fpm)	20 000	20 000	2 000	6-Y

(a) See §6.2.2.6

(b) For flashing lights, effective intensity as determined in accordance with the Aerodrome Design Manual, Part 4.

**GACA REGULATIONS - SECTION 14 - AERODROMES**  
**VOLUME I – AERODROME DESIGN AND OPERATIONS**  
**CHAPTER -6- VISUAL AIDS FOR DENOTING OBSTACLES**

**Table 6-X Light distribution for low intensity obstacle lights**

	Minimum intensity (a)	Maximum intensity (a)	Vertical beam spread (f)	
			Minimum beam spread	Intensity
Type A	10cd (b)	N/A	10°	5cd
Type B	32cd (b)	N/A	10°	16cd
Type C	40cd (b)	400cd	12° (d)	20cd
Type D	200cd (c)	400cd	N/A (e)	N/A

*Note.— This table does not include recommended horizontal beam spreads. 6.2.1.3 requires 360° coverage around an obstacle. Therefore, the number of lights needed to meet this requirement will depend on the horizontal beam spreads of each light as well as the shape of the obstacle. Thus, with narrower beam spreads, more lights will be required.*

(a) 360° horizontal. For flashing lights, the intensity is read into effective intensity, as determined in accordance with the Aerodrome Design Manual, Part 4.

(b) Between 2 and 10° vertical. Elevation vertical angles are referenced to the horizontal when the light is levelled.

(c) Between 2 and 20° vertical. Elevation vertical angles are referenced to the horizontal when the light is levelled.

(d) Peak intensity should be located at approximately 2.5° vertical.

(e) Peak intensity should be located at approximately 17° vertical.

(f) Beam spread is defined as the angle between the horizontal plan and the directions for which the intensity exceeds that mentioned in the “intensity” column.

**Table 6-Y Light distribution for medium and high intensity obstacle lights according to benchmark intensities of table 6-3**

Benchmark intensity	Minimum requirements					Recommendations				
	Vertical elevation angle (b)			Vertical beam spread (c)		Vertical elevation angle (b)			Vertical beam spread (c)	
	0°		-1°			0°	-1°	-10°		
	Minimum average intensity (a)	Minimum intensity (a)	Minimum intensity (a)	Minimum beam spread	Intensity (a)	Maximum intensity (a)	Maximum intensity (a)	Maximum intensity (a)	Maximum beam spread	Intensity (a)
200 000	200 000	150 000	75 000	3°	75 000	250 000	112 500	7 500	7°	75 000
100 000	100 000	75 000	37 500	3°	37 500	125 000	56 250	3 750	7°	37 500
20 000	20 000	15 000	7 500	3°	7 500	25 000	11 250	750	N/A	N/A
2 000	2 000	1 500	750	3°	750	2 500	1 125	75	N/A	N/A

*Note.— This table does not include recommended horizontal beam spreads. 6.2.1.3 requires 360° coverage around an obstacle. Therefore, the number of lights needed to meet this requirement will depend on the horizontal beam spreads of each light as well as the shape of the obstacle. Thus, with narrower beam spreads, more lights will be required.*

(a) 360° horizontal. All intensities are expressed in Candela. For flashing lights, the intensity is read into effective intensity, as determined in accordance with the Aerodrome Design Manual, Part 4.

(b) Elevation vertical angles are referenced to the horizontal when the light unit is levelled.

(c) Beam spread is defined as the angle between the horizontal plan and the directions for which the intensity exceeds that mentioned in the “intensity” column.

*Note.— an extended beam spread may be necessary under specific configuration and justified by an aeronautical study.*



## CHAPTER 7 - VISUAL AIDS FOR DENOTING RESTRICTED USE AREAS

### 7.1 Closed runways and taxiways, or parts thereof

#### Application

7.1.1 A closed marking shall be displayed on a runway or taxiway, or portion thereof, which is permanently closed to the use of all aircraft.

7.1.2 A closed marking should be displayed on a temporarily closed runway or taxiway or portion thereof, except that such marking may be omitted when the closing is of short duration and adequate warning by air traffic services is provided.

#### Location

7.1.3 On a runway a closed marking shall be placed at each end of the runway, or portion thereof, declared closed, and additional markings shall be so placed that the maximum interval between markings does not exceed 300 m. On a taxiway a closed marking shall be placed at least at each end of the taxiway or portion thereof closed.

#### Characteristics

7.1.4 The closed marking shall be of the form and proportions as detailed in Figure 7-1, Illustration a) when displayed on a runway, and shall be of the form and proportions as detailed in Figure 7-1, Illustration b), when displayed on a taxiway. The marking shall be white when displayed on a runway and shall be yellow when displayed on a taxiway.

Note. — When an area is temporarily closed, frangible barriers or markings utilizing materials other than paint or other suitable means may be used to identify the closed area.

7.1.5 When a runway or taxiway or portion thereof is permanently closed, all normal runway and taxiway markings shall be obliterated.

7.1.6 Lighting on a closed runway or taxiway or portion thereof shall not be operated, except as required for maintenance purposes.

7.1.7 In addition to closed markings, when the runway or taxiway or portion thereof closed is intercepted by a usable runway or taxiway which is used at night, unserviceability lights shall be placed across the entrance to the closed area at intervals not exceeding 3 m (see 7.4.4).

### 7.2 Non-load-bearing surfaces

#### Application

7.2.1 Shoulders for taxiways, holding bays and aprons and other non-load-bearing surfaces which cannot readily be distinguished from load-bearing surfaces and which, if used by aircraft, might result in damage to the aircraft shall have the boundary between such areas and the load-bearing surface marked by a taxi side stripe marking.

Note. — The marking of runway sides is specified in 5.2.7.

#### Location

7.2.2 A taxi side stripe marking should be placed along the edge of the load-bearing pavement, with the outer edge of the marking approximately on the edge of the load-bearing pavement.

#### Characteristics

7.2.3 A taxi side stripe marking should consist of a pair of solid lines, each 15 cm wide and spaced 15 cm apart and the same color as the taxiway center line marking.

Note. — Guidance on providing additional transverse stripes at an intersection or a small area on the apron is given in the ICAO Aerodrome Design Manual, Part 4.

### 7.3 Pre-threshold area

#### Application

7.3.1 When the surface before a threshold is paved and exceeds 60 m in length and is not suitable for normal use by aircraft, the entire length before the threshold should be marked with a chevron marking.

#### Location

7.3.2 A chevron marking should point in the direction of the runway and be placed as shown in Figure 7-2.

#### Characteristics

7.3.3 A chevron marking should be of conspicuous color and contrast with the color used for the runway markings; it should preferably be yellow. It should have an over-all width of at least 0.9 m.

### 7.4 Unserviceable areas

#### Application

7.4.1 Unserviceability markers shall be displayed wherever any portion of a taxiway, apron or holding bay is unfit for the movement of aircraft but it is still possible for aircraft to bypass the area safely. On a movement area used at night, unserviceability lights shall be used.



Note. — Unserviceability markers and lights are used for such purposes as warning pilots of a hole in a taxiway or apron pavement or outlining a portion of pavement, such as on an apron, that is under repair. They are not suitable for use when a portion of a runway becomes unserviceable or on a taxiway when a major portion of the width becomes unserviceable. In such instances, the runway or taxiway is normally closed.

#### **Location**

7.4.2 Unserviceability markers and lights shall be placed at intervals sufficiently close so as to delineate the unserviceable area.

Note. — Guidance on the location of unserviceability lights is given in Attachment A, Section 13.

#### **Characteristics of unserviceability markers**

7.4.3 Unserviceability markers shall consist of conspicuous upstanding devices such as flags, cones or marker boards.

#### **Characteristics of unserviceability lights**

7.4.4 An unserviceability light shall consist of a red fixed light. The light shall have intensity sufficient to ensure conspicuity considering the intensity of the adjacent lights and the general level of illumination against which it would normally be viewed. In no case shall the intensity be less than 10 cd of red light.

#### **Characteristics of unserviceability cones**

7.4.5 An unserviceability cone should be at least 0.5 m in height and red, orange or yellow or any one of these colors in combination with white.

#### **Characteristics of unserviceability flags**

7.4.6 An unserviceability flag should be at least 0.5 m square and red, orange or yellow or any one of these colors in combination with white.

#### **Characteristics of unserviceability marker boards**

7.4.7 An unserviceability marker board should be at least 0.5 m in height and 0.9 m in length, with alternate red and white or orange and white vertical stripes.

**Intentionally left blank**




Figure 7-1. Closed runway and taxiway markings




Figure 7-2. Pre-threshold marking

## CHAPTER 8 - ELECTRICAL SYSTEMS

### 8.1 Electrical power supply systems for air navigation facilities

Introductory Note.— The safety of operations at aerodromes depends on the quality of the supplied power. The total electrical power supply system may include connections to one or more external sources of electric power supply, one or more local generating facilities and to a distribution network including transformers and switchgear. Many other aerodrome facilities supplied from the same system need to be taken into account while planning the electrical power system at aerodromes.

8.1.1 Adequate primary power supply shall be available at aerodromes for the safe functioning of air navigation facilities.

8.1.2 The design and provision of electrical power systems for aerodrome visual and radio navigation aids shall be such that an equipment failure will not leave the pilot with inadequate visual and non-visual guidance or misleading information.

Note.— The design and installation of the electrical systems need to take into consideration factors that can lead to malfunction, such as electromagnetic disturbances, line losses, power quality, etc. Additional guidance is given in the ICAO Aerodrome Design Manual, Part 5.

8.1.3 Electric power supply connections to those facilities for which secondary power is required should be so arranged that the facilities are automatically connected to the secondary power supply on failure of the primary source of power.

8.1.4 The time interval between failure of the primary source of power and the complete restoration of the services required by 8.1.10 should be as short as practicable, except that for visual aids associated with non-precision, precision approach or take-off runways the requirements of Table 8-1 for maximum switch-over times should apply.

Note.— A definition of switch-over time is given in Chapter 1

8.1.5 The provision of a definition of switch-over time shall not require the replacement of an existing secondary power supply before 1 January 2010. However, for a secondary power supply installed after 4 November 1999, the electric power supply connections to those facilities for which secondary power is required shall be so arranged that the facilities are capable of meeting the

requirements of Table 8-1 for maximum switch-over times as defined in Chapter 1.

### Visual aids

#### Application

8.1.6 For a precision approach runway, a secondary power supply capable of meeting the requirements of Table 8-1 for the appropriate category of precision approach runway shall be provided. Electric power supply connections to those facilities for which secondary power is required shall be so arranged that the facilities are automatically connected to the secondary power supply on failure of the primary source of power.

8.1.7 For a runway meant for take-off in runway visual range conditions less than a value of 800 m, a secondary power supply capable of meeting the relevant requirements of Table 8-1 shall be provided.

8.1.8 At an aerodrome where the primary runway is a non-precision approach runway, a secondary power supply capable of meeting the requirements of Table 8-1 should be provided except that a secondary power supply for visual aids need not be provided for more than one non-precision approach runway.

8.1.9 At an aerodrome where the primary runway is a non-instrument runway, a secondary power supply capable of meeting the requirements of 8.1.4 should be provided, except that a secondary power supply for visual aids need not be provided when an emergency lighting system in accordance with the specification of 5.3.2 is provided and capable of being deployed in 15 minutes.

8.1.10 The following aerodrome facilities should be provided with a secondary power supply capable of supplying power when there is a failure of the primary power supply:

- a) the signaling lamp and the minimum lighting necessary to enable air traffic services personnel to carry out their duties;

Note.— The requirement for minimum lighting may be met by other than electrical means.

- b) all obstacle lights which, in the opinion of the appropriate authority, are essential to ensure the safe operation of aircraft;
- c) approach, runway and taxiway lighting as specified in 8.1.6 to 8.1.9;
- d) meteorological equipment;

CHAPTER -8- ELECTRICAL SYSTEMS

- e) essential security lighting, if provided in accordance with 9.11;
- f) essential equipment and facilities for the aerodrome responding emergency agencies;
- g) floodlighting on a designated isolated aircraft parking position if provided in accordance with 5.3.23.1; and h) illumination of apron areas over which passengers may walk.

Note.— Specifications for secondary power supply for radio navigation aids and ground elements of communications systems are given in GACA Regulation Section 10 and ICAO Annex 10, Volume I, Chapter 2.

8.1.11 Requirements for a secondary power supply should be met by either of the following:

- independent public power, which is a source of power supplying the aerodrome service from a substation other than the normal substation through a transmission line following a route different from the normal power supply route and such that the possibility of a simultaneous failure of the normal and independent public power supplies is extremely remote; or
- standby power unit(s), which are engine generators, batteries, etc., from which electric power can be obtained.

Note.— Guidance on electrical systems is included in the ICAO Aerodrome Design Manual, Part 5.

### 8.2 System design

8.2.1 For a runway meant for use in runway visual range conditions less than a value of 550 m, the electrical systems for the power supply, lighting and control of the lighting systems included in Table 8-1 shall be so designed that an equipment failure will not leave the pilot with inadequate visual guidance or misleading information.

Note.— Guidance on means of providing this protection is given in the ICAO Aerodrome Design Manual, Part 5.

8.2.2 Where the secondary power supply of an aerodrome is provided by the use of duplicate feeders, such supplies shall be physically and electrically separate so as to ensure the required level of availability and independence.

8.2.3 Where a runway forming part of a standard taxiway is provided with runway lighting and taxiway lighting, the lighting systems shall be interlocked to preclude the

possibility of simultaneous operation of both forms of lighting.

### 8.3 Monitoring

Note.— Guidance on this subject is given in the ICAO Aerodrome Design Manual, Part 5.

8.3.1 A system of monitoring should be employed to indicate the operational status of the lighting systems.

8.3.2 Where lighting systems are used for aircraft control purposes, such systems shall be monitored automatically so as to provide an indication of any fault which may affect the control functions. This information shall be automatically relayed to the air traffic service unit.

8.3.3 Where a change in the operational status of lights has occurred, an indication should be provided within two seconds for a stop bar at a runway holding position and within five seconds for all other types of visual aids.

8.3.4 For a runway meant for use in runway visual range conditions less than a value of 550 m, the lighting systems detailed in Table 8-1 should be monitored automatically so as to provide an indication when the serviceability level of any element falls below the minimum serviceability level specified in 10.4.7 to 10.4.11, as appropriate. This information should be automatically relayed to the maintenance crew.

8.3.5 For a runway meant for use in runway visual range conditions less than a value of 550 m, the lighting systems detailed in Table 8-1 should be monitored automatically to provide an indication when the serviceability level of any element falls below the minimum level specified by the appropriate authority below which operations should not continue. This information should be automatically relayed to the air traffic services unit and displayed in a prominent position.

Note.— Guidance on air traffic control interface and visual aids monitoring is included in the ICAO Aerodrome Design Manual, Part 5.

**Intentionally left blank**

Table 8-1. Secondary power supply requirements  
(see 8.1.4)

Runway	Lighting aids requiring power	Maximum switch-over time
Non-instrument	Visual approach slope indicators <sup>a</sup>	See
	Runway edge <sup>b</sup>	8.1.4 and
	Runway threshold <sup>b</sup>	8.1.9
	Runway end <sup>b</sup>	
	Obstacle <sup>a</sup>	
Non-precision approach	Approach lighting system	15 seconds
	Visual approach slope indicators <sup>a, d</sup>	15 seconds
	Runway edge <sup>d</sup>	15 seconds
	Runway threshold <sup>d</sup>	15 seconds
	Runway end	15 seconds
	Obstacle <sup>a</sup>	15 seconds
Precision approach category I	Approach lighting system	15 seconds
	Runway edge <sup>d</sup>	15 seconds
	Visual approach slope indicators <sup>a, d</sup>	15 seconds
	Runway threshold <sup>d</sup>	15 seconds
	Runway end	15 seconds
	Essential taxiway <sup>a</sup>	15 seconds
	Obstacle <sup>a</sup>	15 seconds
Precision approach category II/III	Inner 300 m of the approach lighting system	1 second
	Other parts of the approach lighting system	15 seconds
	Obstacle <sup>a</sup>	15 seconds
	Runway edge	15 seconds
	Runway threshold	1 second
	Runway end	1 second
	Runway centre line	1 second
	Runway touchdown zone	1 second
	All stop bars	1 second
Runway meant for take-off in runway visual range conditions less than a value of 800 m	Essential taxiway	15 seconds
	Runway edge	15 seconds <sup>c</sup>
	Runway end	1 second
	Runway centre line	1 second
	All stop bars	1 second
	Essential taxiway <sup>a</sup>	15 seconds
	Obstacle <sup>a</sup>	15 seconds

a. Supplied with secondary power when their operation is essential to the safety of flight operation.

b. See Chapter 5, 5.3.2 regarding the use of emergency lighting.

c. One second where no runway centre line lights are provided.

d. One second where approaches are over hazardous or precipitous terrain.



**CHAPTER -9- AERODROME OPERATIONAL SERVICES, EQUIPMENT AND  
INSTALLATIONS**

**CHAPTER 9 - AERODROME  
OPERATIONAL SERVICES, EQUIPMENT  
AND INSTALLATIONS**

**9.1 Aerodrome emergency planning**

**General**

Introductory Note — Aerodrome emergency planning is the process of preparing an aerodrome to cope with an emergency occurring at the aerodrome or in its vicinity. The objective of aerodrome emergency planning is to minimize the effects of an emergency, particularly in respect of saving lives and maintaining aircraft operations. The aerodrome emergency plan sets forth the procedures for coordinating the response of different aerodrome agencies (or services) and of those agencies in the surrounding community that could be of assistance in responding to the emergency. Guidance material to assist the appropriate authority in establishing aerodrome emergency planning is given in the ICAO Airport Services Manual, Part 7.

9.1.1 An aerodrome emergency plan shall be established at an aerodrome, commensurate with the aircraft operations and other activities conducted at the aerodrome.

9.1.2 The aerodrome emergency plan shall provide for the coordination of the actions to be taken in an emergency occurring at an aerodrome or in its vicinity.

Note. 1— Examples of emergencies are: aircraft emergencies, sabotage including bomb threats, unlawfully seized aircraft, dangerous goods occurrences, building fires, natural disasters and public health emergencies..

Note 2.— Examples of public health emergencies are increased risk of travellers or cargo spreading a serious communicable disease internationally through air transport and severe outbreak of a communicable disease potentially affecting a large proportion of aerodrome staff.

9.1.3 The plan shall coordinate the response or participation of all existing agencies which, in the opinion of the appropriate authority, could be of assistance in responding to an emergency.

Note.1 — Examples of agencies are:

- on the aerodrome: air traffic control unit, rescue and fire fighting services, aerodrome administration, medical and ambulance services, aircraft operators, security services, and police;

- off the aerodrome: fire departments, police, health authorities (including medical ambulance, hospitals, and public health services), military, and harbor patrol or coast guard.

Note 2.— Public health services include planning to minimize adverse effects to the community from health related events and deal with population health issues rather than provision of health services to individuals.

9.1.4 The plan should provide for cooperation and coordination with the rescue coordination center, as necessary.

9.1.5 The aerodrome emergency plan document should include at least the following:

- a. types of emergencies planned for;
- b. agencies involved in the plan;
- c. responsibility and role of each agency, the emergency operations center and the command post, for each type of emergency;
- d. information on names and telephone numbers of offices or people to be contacted in the case of a particular emergency; and
- e. a grid map of the aerodrome and its immediate vicinity.

9.1.6 The plan shall observe Human Factors principles to ensure optimum response by all existing agencies participating in emergency operations.

Note. — Guidance material on Human Factors principles can be found in the Human Factors Training Manual.

**Emergency operations center and command post**

9.1.7 A fixed emergency operations center and a mobile command post should be available for use during an emergency.

9.1.8 The emergency operations center should be a part of the aerodrome facilities and should be responsible for the overall coordination and general direction of the response to an emergency.

9.1.9 The command post should be a facility capable of being moved rapidly to the site of an emergency, when required, and should undertake the local coordination of those agencies responding to the emergency.

9.1.10 A person should be assigned to assume control of the emergency operations center and, when appropriate, another person the command post.

**Communication system**



**CHAPTER -9- AERODROME OPERATIONAL SERVICES, EQUIPMENT AND  
INSTALLATIONS**

9.1.11 Adequate communication systems linking the command post and the emergency operations center with each other and with the participating agencies should be provided in accordance with the plan and consistent with the particular requirements of the aerodrome

**Aerodrome emergency exercise**

9.1.12 The plan shall contain procedures for periodic testing of the adequacy of the plan and for reviewing the results in order to improve its effectiveness.

Note. — The plan includes all participating agencies and associated equipment.

9.1.13 The plan shall be tested by conducting:

- a) a full-scale aerodrome emergency exercise at intervals not exceeding two years and partial emergency exercises in the intervening year to ensure that any deficiencies found during the full-scale aerodrome emergency exercise have been corrected; or
- b) a series of modular tests commencing in the first year and concluding in a full-scale aerodrome emergency exercise at intervals not exceeding three years;

and reviewed thereafter, or after an actual emergency, so as to correct any deficiency found during such exercises or actual emergency.

Note 1. — The purpose of a full-scale exercise is to ensure the adequacy of the plan to cope with different types of emergencies. The purpose of a partial exercise is to ensure the adequacy of the response to individual participating agencies and components of the plan, such as the communications system. The purpose of modular tests is to enable concentrated effort on specific components of established emergency plans.

Note 2. — Guidance material on airport emergency is available in the Airport Service Manual, Part 7.

**Emergencies in difficult environments**

9.1.14 The plan shall include the ready availability of and coordination with appropriate specialist rescue services to be able to respond to emergencies where an aerodrome is located close to water and/or swampy areas and where a significant portion of approach or departure operations takes place over these areas.

9.1.15 At those aerodromes located close to water and/or swampy areas, or difficult terrain, the aerodrome emergency plan should include the establishment, testing and assessment at regular intervals of a pre-determined

response for the specialist rescue services.

9.1.15A. An assessment of the approach and departure areas within 1,000 m of the runway threshold should be carried out to determine the options available for intervention.

Note. — Guidance material on accessing approach and departure areas within 1,000 m of runway thresholds can be found in Chapter 13 of the Airport Service Manual (Doc 9137), Part 1.

**9.2 Rescue and fire fighting**

**General**

Introductory Note — The principal objective of a rescue and fire fighting service is to save lives in the event of an aircraft accident or incident occurring at, or in the immediate vicinity of, an aerodrome. The rescue and fire fighting service is provided to create and maintain survivable conditions, to provide egress routes for occupants and to initiate the rescue of those occupants unable to make their escape without direct aid. The rescue may require the use of equipment and personnel other than those assessed primarily for rescue and fire fighting purposes

**Application**

9.2.1 Rescue and firefighting equipment and services shall be provided at an aerodrome.

Note. — Public or private organizations, suitably located and equipped, may be designated to provide the rescue and fire fighting service. It is intended that the fire station housing these organizations be normally located on the aerodrome, although an off-aerodrome location is not precluded provided the response time can be met.

9.2.2 Where an aerodrome is located close to water/swampy areas, or difficult terrain, and where a significant portion of approach or departure operations takes place over these areas, specialist rescue services and fire fighting equipment appropriate to the hazard and risk shall be available.

Note 1.— Special fire fighting equipment need not be provided for water areas; this does not prevent the provision of such equipment if it would be of practical use, such as when the areas concerned include reefs or islands.

Note 2 — The objective is to plan and deploy the necessary life-saving flotation equipment as expeditiously as possible in a number commensurate with the largest aeroplane normally using the aerodrome.

**CHAPTER -9- AERODROME OPERATIONAL SERVICES, EQUIPMENT AND  
INSTALLATIONS**

Note 3 — Additional guidance is available in Chapter 13 of the ICAO Airport Services Manual, Part 1.

**Level of protection to be provided**

9.2.3 The level of protection provided at an aerodrome for rescue and fire fighting shall be appropriate to the aerodrome category determined using the principles in 9.2.5 and 9.2.6, except that, where the number of movements of the aeroplanes in the highest category normally using the aerodrome is less than 700 in the busiest consecutive three months, the level of protection provided shall be not less than one category below the determined category.

Note. — Either a take-off or a landing constitutes a movement.

9.2.4 The level of protection provided at an aerodrome for rescue and fire fighting should be equal to the aerodrome category determined using the principles in 9.2.5 and 9.2.6.

9.2.5 The aerodrome category shall be determined from Table 9-1 and shall be based on the longest aeroplanes normally using the aerodrome and their fuselage width.

Note. — To categorize the aeroplanes using the aerodrome, first evaluate their overall length and second, their fuselage width.

Aerodrome category (1)	Aeroplane overall length (2)	Maximum fuselage width (3)
1	0 m up to but not including 9 m	2 m
2	9 m up to but not including 12 m	2 m
3	12 m up to but not including 18 m	3 m
4	18 m up to but not including 24 m	4 m
5	24 m up to but not including 28 m	4 m
6	28 m up to but not including 39 m	5 m
7	39 m up to but not including 49 m	5 m
8	49 m up to but not including 61 m	7 m
9	61 m up to but not including 76 m	7 m
10	76 m up to but not including 90 m	8 m

**Table 9-1 Aerodrome category for rescue and fire fighting**

9.2.6 If, after selecting the category appropriate to the longest airplane's overall length, that airplane's fuselage

width is greater than the maximum width in Table 9-1, column 3 for that category, then the category for that aeroplane shall actually be one category higher.

Note 1. — See guidance in the Airport Services Manual, Part 1 for categorizing aerodromes, including those for all-cargo aircraft operations, for rescue and fire fighting purposes.

Note 2. — Guidance on training of personnel, rescue equipment for difficult environment and other facilities and services for rescue and fire fighting is given in Attachment A, Section 17 and in the Airport Services Manual, Part 1.

9.2.7 During anticipated periods of reduced activity, the level of protection available shall be no less than that needed for the highest category of aeroplane planned to use the aerodrome during that time irrespective of the number of movements.

**Extinguishing agents**

9.2.8 Both principal and complementary agents should normally be provided at an aerodrome.

Note. — Descriptions of the agents may be found in the Airport Services Manual, Part 1.

9.2.9 The principal extinguishing agent should be:

- a) a foam meeting the minimum performance level A; or
- b) a foam meeting the minimum performance level B; or
- c) a foam meeting the minimum performance Level C; or.
- d) a combination of these agents;

except that the principal extinguishing agent for aerodromes in categories 1 to 3 should preferably meet performance level B or C foam.

Note. — Information on the required physical properties and fire extinguishing performance criteria needed for foam to achieve an acceptable performance level A, B or C rating is given in the ICAO Airport Services Manual, Part 1.

9.2.10 The complementary extinguishing agent should be a dry chemical powder suitable for extinguishing hydrocarbon fires.

Note 1 — When selecting dry chemical powders for use with foam, care must be exercised to ensure compatibility.

Note 2 — Alternate complementary agents having equivalent fire fighting capability may be utilized. Additional information on extinguishing agents is given

**GACA REGULATIONS - SECTION 14 - AERODROMES  
VOLUME I - AERODROME DESIGN AND OPERATIONS**

**CHAPTER -9- AERODROME OPERATIONAL SERVICES, EQUIPMENT AND  
INSTALLATIONS**

in the ICAO Airport Services Manual, Part 1.

9.2.11 The amounts of water for foam production and the complementary agents to be provided on the rescue and fire fighting vehicles shall be in accordance with the aerodrome category determined under 9.2.3, 9.2.4, 9.2.5, 9.2.6 and Table 9-2, except that for aerodrome categories 1 and 2 up to 100 per cent of the water may be substituted by complementary agent.

For the purpose of agent substitution, 1 kg of complementary agent shall be taken as equivalent to 1.0L of water for production of a foam meeting performance level A.

Note 1 — The amounts of water specified for foam production are predicated on an application rate of 8.2 L/min/m<sup>2</sup> for a foam meeting performance level A, 5.5 L/min/m<sup>2</sup> for a foam meeting performance level B and 3.75L/min/m<sup>2</sup> for a foam meeting performance Level C..

Note 2 — When any other complementary agent is used, the substitution ratios need to be checked.

**Table 9-2. Minimum usable amounts of extinguishing agents**

Aerodrome Category	Foam meeting performance Level A		Foam meeting performance Level B		Foam meeting performance Level C		Complementary agents	
	Water (L)	Discharge rate foam solution / minute (L)	Water (L)	Discharge rate foam solution / minute (L)	Water (L)	Discharge rate foam solution / minute (L)	Dry Chemical powders (Kg)	Discharge Rate (Kg/second)
(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)
1	350	350	230	230	160	160	45	2.25
2	1000	800	670	550	460	360	90	2.25
3	1800	1300	1200	900	820	630	135	2.25
4	3600	2600	2400	1800	1700	1100	135	2.25
5	8100	4500	5400	3000	3900	2200	180	2.25
6	11800	6000	7900	4000	5800	2900	225	2.25
7	18200	7900	12100	5300	8800	3800	225	2.25
8	27300	10800	18200	7200	12800	5100	450	4.5
9	36400	13500	24300	9000	17100	6300	450	4.5
10	48200	16600	32300	11200	22800	7900	450	4.5

Note.— The quantities of water shown in columns 2, and 4, and 6 are based on the average overall length of aeroplanes in a given category.

9.2.12 At aerodromes where operation by aeroplanes larger than the average size in a given category are planned, the quantities of water should be recalculated and the amount of water for foam production and the discharge rates for foam solution should be increased accordingly.

Note. — Guidance on the determination of quantities of water and discharge rates based on the largest theoretical aeroplane in a given category is available in Chapter 2 of the Airport Service Manual (Doc 9137). Part 1.

9.2.12A From 1 January 2015, at aerodromes where operations by aeroplanes larger than the average size in a given category are planned, the quantities of water shall be recalculated and the amount of water for foam production and the discharge rates for foam solution shall be increased accordingly.

Note. — Guidance on the determination of quantities of water and discharge rates based on the largest overall length of aeroplane in a given category is available in Chapter 2 of the Airport Service Manual (Doc 9137). Part 1.

9.2.13 The quantity of foam concentrates separately provided on vehicles for foam production shall be in proportion to the quantity of water provided and the foam concentrate selected.

9.2.14 The amount of foam concentrate provided on a vehicle should be sufficient to produce at least two loads of foam solution.

9.2.15 Supplementary water supplies, for the expeditious replenishment of rescue and fire fighting vehicles at the

**CHAPTER -9- AERODROME OPERATIONAL SERVICES, EQUIPMENT AND  
INSTALLATIONS**

scene of an aircraft accident, should be provided.

9.2.16 When a combination of different performance level foams are provided at an aerodrome, the total amount of water to be provided for foam production should be calculated for each foam type and the distribution of these quantities should be.

9.2.17 The discharge rate of the foam solution shall not be less than the rates shown in Table 9-2.

9.2.18 The complementary agents should comply with the appropriate specifications of the International Organization for Standardization (ISO).\*

9.2.19 The discharge rate of complementary agents should be selected be no less than the rates shown in Table 9-2.

9.2.20 Dry chemical powders should only be substituted with an agent that has equivalent or better fire fighting capabilities, for all types of fires where complementary agent is expected to be used.

Note.— Guidance on the use of complementary agents can be found in the Airport Services Manual – Part 1

\* See ISO Publications 5923 (Carbon Dioxide), 7201 (Halogenated Hydrocarbons) and 7202 (Powder).

9.2.21A A reserve supply of foam concentrate, equivalent to 200 per cent of the quantities identified in Table 9-2, should be maintained on the aerodrome for vehicle replenishment purposes.

Note. — Foam concentrate carried on fire vehicles in excess of quantity identified in Table 9-2 can contribute to the reserve.

9.2.21B A reserve supply of complementary agent, equivalent to 100 per cent of the quantity identified in Table 9-2, should be maintained on the aerodrome for vehicle replenishment purposes. Sufficient propellant gas should be included to utilize this reserve complementary agent.

9.2.21C Category 1 and 2 aerodromes that have replaced up to 100 per cent of the water with complementary agent should hold a reserve supply of complementary agent of 200 per cent.

9.2.21D. where a major delay in the replenishment of the supplies is anticipated, the amount of reserve supply in 9.2.19A, 9.2.19B and 9.2.19C should be increased as determined by a risk assessment.

Note. — See Airport Services Manual (Doc 9137), Part 1 for guidance on the conduct of a risk analysis to determine the quantities of reserve extinguishing agents.

**Rescue equipment**

9.2.22 Rescue equipment commensurate with the level of aircraft operations should be provided on the rescue and fire fighting vehicle(s).

Note. — Guidance on the rescue equipment to be provided at an aerodrome is given in the ICAO Airport Services Manual, Part 1.

**Response time**

9.2.23 The operational objective of the rescue and fire fighting service shall be to achieve a response time not exceeding three minutes to any point of each operational runway, in optimum visibility and surface conditions.

9.2.24 The operational objective of the rescue and fire fighting service should be to achieve a response time not exceeding two minutes to any point of each operational runway, in optimum visibility and surface conditions.

9.2.25 The operational objective of the rescue and fire fighting service should be to achieve a response time not exceeding three minutes to any other part of the movement area in optimum visibility and surface conditions.

Note 1 — Response time is considered to be the time between the initial call to the rescue and fire fighting service, and the time when the first responding vehicle(s) is (are) in position to apply foam at a rate of at least 50 per cent of the discharge rate specified in Table 9-2.

Note 2.— Optimum visibility and surface conditions are defined as daytime, good visibility, no precipitation with normal response route free of surface contamination e.g. water, ice or snow.

9.2.26 To meet the operational objective as nearly as possible in less than optimum conditions of visibility, especially during low visibility operations, suitable guidance, equipment and/or procedures for rescue and fire fighting services should be provided.

Note.— Additional guidance is available in the Airport Services Manual, Part 1.

9.2.27 Any vehicles, other than the first responding vehicle(s), required to deliver the amounts of extinguishing agents specified in Table 9-2 shall ensure continuous agent application and shall arrive no more than four minutes from the initial call..



**CHAPTER -9- AERODROME OPERATIONAL SERVICES, EQUIPMENT AND  
INSTALLATIONS**

9.2.28 Any vehicles, other than the first responding vehicles(s), required to deliver the amounts of extinguishing agents specified in Table 9-2 should ensure continuous agent application and should arrive no more than three minutes from the initial call.

9.2.29 A system of preventive maintenance of rescue and fire fighting vehicles should be employed to ensure effectiveness of the equipment and compliance with the specified response time throughout the life of the vehicle.

**Emergency access roads**

9.2.30 Emergency access roads should be provided on an aerodrome where terrain conditions permit their construction, so as to facilitate achieving minimum response times. Particular attention should be given to the provision of ready access to approach areas up to 1, 000 m from the threshold, or at least within the aerodrome boundary. Where a fence is provided, the need for convenient access to outside areas should be taken into account.

Note. — Aerodrome service roads may serve as emergency access roads when they are suitably located and constructed.

9.2.31 Emergency access roads should be capable of supporting the heaviest vehicles which will use them, and be usable in all weather conditions. Roads within 90 m of a runway should be surfaced to prevent surface erosion and the transfer of debris to the runway. Sufficient vertical clearance should be provided from overhead obstructions for the largest vehicles.

9.2.32 When the surface of the road is indistinguishable from the surrounding area or in areas where snow may obscure the location of the roads, edge markers should be placed at intervals of about 10 m.

**Fire stations**

9.2.33 All rescue and fire fighting vehicles should normally be housed in a fire station. Satellite fire stations should be provided whenever the response time cannot be achieved from a single fire station.

9.2.34 The fire station should be located so that the access for rescue and fire fighting vehicles into the runway area is direct and clear, requiring a minimum number of turns.

**Communication and alerting systems**

9.2.35 A discrete communication system should be provided linking a fire station with the control tower, any other fire station on the aerodrome and the rescue and fire fighting vehicles.

9.2.36 An alerting system for rescue and fire fighting

personnel, capable of being operated from that station, should be provided at a fire station, any other fire station on the aerodrome and the aerodrome control tower.

**Number of rescue and fire fighting vehicles**

9.2.37 The minimum number of rescue and fire fighting vehicles provided at an aerodrome should be in accordance with the following tabulation.

Aerodrome category	Rescue and fire fighting vehicles
1	1
2	1
3	1
4	1
5	1
6	2
7	2
8	3
9	3
10	3

Note. — Guidance on minimum characteristics of rescue and fire fighting vehicles is given in the ICAO Airport Services Manual, Part 1.

**Personnel**

9.2.38 All rescue and fire fighting personnel shall be properly trained to perform their duties in an efficient manner and shall participate in live fire drills commensurate with the types of aircraft and type of rescue and firefighting equipment in use at the aerodrome, including pressure-fed fuel fires.

Note 1.— Guidance to assist the appropriate authority in providing proper training is given in Attachment A, Section 17 and Airport Services Manual, Part 1

Note 2 — Fires associated with fuel discharged under very high pressure from a ruptured fuel tank are known as “pressure-fed fuel fires”.

9.2.39 The rescue and fire fighting personnel training program shall include training in human performance, including team coordination.

Note. — Guidance material to design training program on human performance and team coordination can be found in the Human Factors Training Manual.

9.2.40 During flight operations, sufficient trained and competent personnel should be detailed and be readily available to ride the rescue and fire fighting vehicles and to operate the equipment at maximum capacity. These

**CHAPTER -9- AERODROME OPERATIONAL SERVICES, EQUIPMENT AND  
INSTALLATIONS**

personnel should be deployed in a way that ensures that minimum response times can be achieved and that continuous agent application at the appropriate rate can be fully maintained. Consideration should also be given for personnel to use hand lines, ladders and other rescue and fire fighting equipment normally associated with aircraft rescue and fire fighting operations.

9.2.41 In determining the minimum number of rescue and fire fighting personnel required, a task resource analysis should be completed and the level of staffing documented in the aerodrome Manual.

Note: - Guidance on the use of a task resource analysis can be found in the Airport Services Manual (Doc 9137), Part 1.

9.2.42 All responding rescue and fire fighting personnel shall be provided with protective clothing and respiratory equipment to enable them to perform their duties in an effective manner.

### **9.3 Disabled aircraft removal**

Note. — Guidance on removal of a disabled aircraft, including recovery equipment, is given in the ICAO Airport Services Manual, Part 5. See also GACA Regulation Section 13 and ICAO Annex 13 concerning protection of evidence, custody and removal of aircraft.

9.3.1 A plan for the removal of an aircraft disabled on, or adjacent to, the movement area should be established for an aerodrome, and a coordinator designated to implement the plan, when necessary.

9.3.2 The disabled aircraft removal plan should be based on the characteristics of the aircraft that may normally be expected to operate at the aerodrome, and include among other things:

- a) a list of equipment and personnel on, or in the vicinity of, the aerodrome which would be available for such purpose; and
- b) arrangements for the rapid receipt of aircraft recovery equipment kits available from other aerodromes.

### **9.4 Wildlife strike hazard reduction**

9.4.1 The wildlife strike hazard on, or in the vicinity of, an aerodrome shall be assessed through:

- a) the establishment of a national procedure for recording and reporting wildlife strikes to aircraft; and

- b) the collection of information from aircraft operators, airport personnel, etc. on the presence of wildlife on or around the aerodrome constituting a potential hazard to aircraft operations.
- c) an ongoing evaluation of the wildlife hazard by competent personnel

Note.— See GACA Regulation Section 15 and ICAO Annex 15, Chapter 8.

9.4.2 Wildlife strike reports shall be collected and forwarded to ICAO for inclusion in the ICAO Bird Strike Information System (IBIS) database.

Note.— The IBIS is designed to collect and disseminate information on wildlife strikes to aircraft. Information on the system is included in the Manual on the ICAO Bird Strike Information System (IBIS).

9.4.3 Action shall be taken to decrease the risk to aircraft operations by adopting measures to minimize the likelihood of collisions between wildlife and aircraft .

Note.— Guidance on effective measures for establishing whether or not wildlife , on or near an aerodrome, constitute a potential hazard to aircraft operations, and on methods for discouraging their presence, is given in the ICAO Airport Services Manual, Part 3.

9.4.4 The appropriate authority shall take action to eliminate or to prevent the establishment of garbage disposal dumps or any other source which may attract wildlife to the aerodrome, or its vicinity, unless an appropriate wildlife assessment indicates that they are unlikely to create conditions conducive to a bird hazard problem. Where the elimination of existing sites is not possible, the appropriate authority shall ensure that any risk to aircraft posed by these sites is assessed and reduced to as low as reasonably practicable..

9.4.5 GACA should give due consideration needs to be given to airport operators' concerns related to land developments that may attract wildlife.

### **9.5 Apron management service**

9.5.1 When warranted by the volume of traffic and operating conditions, an appropriate apron management service should be provided on an apron by an aerodrome ATS unit, by another aerodrome operating authority, or by a cooperative combination of these, in order to:



**CHAPTER -9- AERODROME OPERATIONAL SERVICES, EQUIPMENT AND  
INSTALLATIONS**

- a) regulate movement with the objective of preventing collisions between aircraft, and between aircraft and obstacles;
- b) regulate entry of aircraft into, and coordinate exit of aircraft from, the apron with the aerodrome control tower; and
- c) ensure safe and expeditious movement of vehicles and appropriate regulation of other activities.

9.5.2 When the aerodrome control tower does not participate in the apron management service, procedures should be established to facilitate the orderly transition of aircraft between the apron management unit and the aerodrome control tower.

Note.— Guidance on an apron management service is given in the ICAO Airport Services Manual, Part 8 and in the Manual of Surface Movement Guidance and Control Systems (SMGCS).

9.5.3 An apron management service shall be provided with radiotelephony communications facilities.

9.5.4 Where low visibility procedures are in effect, persons and vehicles operating on an apron shall be restricted to the essential minimum.

Note.— Guidance on related special procedures is given in the ICAO Manual of Surface Movement Guidance and Control Systems (SMGCS).

9.5.5 An emergency vehicle responding to an emergency shall be given priority over all other surface movement traffic.

9.5.6 A vehicle operating on an apron shall:

- a. give way to an emergency vehicle; an aircraft taxiing, about to taxi, or being pushed or towed; and
- b. give way to other vehicles in accordance with local regulations.

9.5.7 An aircraft stand shall be visually monitored to ensure that the recommended clearance distances are provided to an aircraft using the stand.

#### **9.6 Ground servicing of aircraft**

9.6.1 Fire extinguishing equipment suitable for at least initial intervention in the event of a fuel fire and personnel trained in its use shall be readily available during the ground servicing of an aircraft, and there shall be a means of quickly summoning the rescue and fire fighting service in the event of a fire or major fuel spill.

9.6.2 When aircraft refueling operations take place while passengers are embarking, on board or disembarking, ground equipment shall be positioned so as to allow:

- a) the use of a sufficient number of exits for expeditious evacuation; and
- b) a ready escape route from each of the exits to be used in an emergency.

#### **9.7 Aerodrome vehicle operations**

Note 1.— Guidance on aerodrome vehicle operations is contained in Attachment A, Section 18 and on traffic rules and regulations for vehicles in the ICAO Manual of Surface Movement Guidance and Control Systems (SMGCS).

Note 2.— It is intended that roads located on the movement area be restricted to the exclusive use of aerodrome personnel and other authorized persons, and that access to the public buildings by an unauthorized person will not require use of such roads.

9.7.1 A vehicle shall be operated:

- a) on a maneuvering area only as authorized by the aerodrome control tower; and
- b) on an apron only as authorized by the appropriate designated authority.

9.7.2 The driver of a vehicle on the movement area shall comply with all mandatory instructions conveyed by markings and signs unless otherwise authorized by:

- a) the aerodrome control tower when on the maneuvering area; or
- b) the appropriate designated authority when on the apron.

9.7.3 The driver of a vehicle on the movement area shall comply with all mandatory instructions conveyed by lights.

9.7.4 The driver of a vehicle on the movement area shall be appropriately trained for the tasks to be performed and shall comply with the instructions issued by:

- a) the aerodrome control tower, when on the maneuvering area; and
- b) the appropriate designated authority, when on the apron.

9.7.5 The driver of a radio-equipped vehicle shall establish satisfactory two-way radio communication with

**CHAPTER -9- AERODROME OPERATIONAL SERVICES, EQUIPMENT AND  
INSTALLATIONS**

the aerodrome control tower before entering the maneuvering area and with the appropriate designated authority before entering the apron. The driver shall maintain a continuous listening watch on the assigned frequency when on the movement area.

**9.8 Surface movement guidance and  
control systems**

**Application**

9.8.1 A surface movement guidance and control system shall be provided at an aerodrome.

Note.— Guidance on surface movement guidance and control systems is contained in the ICAO Manual of Surface Movement Guidance and Control Systems (SMGCS).

**Characteristics**

9.8.2 The design of a surface movement guidance and control system should take into account:

- a) the density of air traffic;
- b) the visibility conditions under which operations are intended;
- c) the need for pilot orientation;
- d) the complexity of the aerodrome layout; and
- e) movements of vehicles.

9.8.3 The visual aid components of a surface movement guidance and control system, i.e. markings, lights and signs should be designed to conform with the relevant specifications in 5.2, 5.3 and 5.4, respectively.

9.8.4 A surface movement guidance and control system should be designed to assist in the prevention of inadvertent incursions of aircraft and vehicles onto an active runway.

9.8.5 The system should be designed to assist in the prevention of collisions between aircraft, and between aircraft and vehicles or objects, on any part of the movement area.

Note.— Guidance on control of stop bars through induction loops and on a visual taxiing guidance and control system is contained in the ICAO Aerodrome Design Manual, Part 4

9.8.6 Where a surface movement guidance and control system is provided by selective switching of stop bars and taxiway center line lights, the following requirements shall be met:

- a) taxiway routes which are indicated by illuminated taxiway center line lights shall be capable of being terminated by an illuminated stop bar;
- b) the control circuits shall be so arranged that when a stop bar located ahead of an aircraft is illuminated, the appropriate section of taxiway center line lights beyond it is suppressed; and
- c) the taxiway center line lights are activated ahead of an aircraft when the stop bar is suppressed.

Note 1.— See Sections 5.3.16 and 5.3.19 for specifications on taxiway center line lights and stop bars, respectively.

Note 2.— Guidance on installation of stop bars and taxiway center line lights in surface movement guidance and control systems is given in the ICAO Aerodrome Design Manual, Part 4.

9.8.7 Surface movement radar for the maneuvering area should be provided at an aerodrome intended for use in runway visual range conditions less than a value of 350 m.

9.8.8 Surface movement radar for the maneuvering area should be provided at an aerodrome other than that in 9.8.7 when traffic density and operating conditions are such that regularity of traffic flow cannot be maintained by alternative procedures and facilities.

Note.— Guidance on the use of surface movement radar is Given in the ICAO Manual of Surface Movement Guidance and Control Systems (SMGCS) and in the Air Traffic Services Planning Manual (Doc 9426).

**9.9 Siting of equipment and installations on  
operational areas**

Note 1.— Requirements for obstacle limitation surfaces are specified in 4.2.

Note 2.— The design of light fixtures and their supporting structures, light units of visual approach slope indicators, signs, and markers, is specified in 5.3.1, 5.3.5, 5.4.1 and 5.5.1, respectively. Guidance on the frangible design of visual and non-visual aids for navigation is given in the ICAO Aerodrome Design Manual (Doc 9157), Part 6.

9.9.1 Unless its function requires it to be there for air navigation or for aircraft safety purposes, no equipment or installation shall be:

**CHAPTER -9- AERODROME OPERATIONAL SERVICES, EQUIPMENT AND  
INSTALLATIONS**

- a) on a runway strip, a runway end safety area, a taxiway strip or within the distances specified in Table 3-1, column 11, if it would endanger an aircraft; or
- b) on a clearway if it would endanger an aircraft in the air.

9.9.2 Any equipment or installation required for air navigation or for aircraft safety purposes which must be located:

- a) on that portion of a runway strip within:
  - 1) 75 m of the runway center line where the code number is 3 or 4; or
  - 2) 45 m of the runway center line where the code number is 1 or 2; or
- b) on a runway end safety area, a taxiway strip or within the distances specified in Table 3-1; or
- c) on a clearway and which would endanger an aircraft in the air;

shall be frangible and mounted as low as possible.

9.9.3 Any equipment or installation required for air navigation or for aircraft safety purposes which must be located on the non-graded portion of a runway strip should be regarded as an obstacle and should be frangible and mounted as low as possible.

Note.— Guidance on the siting of navigation aids is contained in the ICAO Aerodrome Design Manual (Doc 9157), Part 6.

9.9.4 Unless its function requires it to be there for air navigation or for aircraft safety purposes, no equipment or installation shall be located within 240 m from the end of the strip and within:

- a) 60 m of the extended center line where the code number is 3 or 4; or
- b) 45 m of the extended center line where the code number is 1 or 2;

of a precision approach runway category I, II or III.

9.9.5 Any equipment or installation required for air navigation or for aircraft safety purposes which must be located on or near a strip of a precision approach runway category I, II or III and which:

- a) is situated on that portion of the strip within 77.5 m of the runway center line where the code number is 4 and the code letter is F; or

- b) is situated within 240 m from the end of the strip and within:

- 1) 60 m of the extended runway center line where the code number is 3 or 4; or
- 2) 45 m of the extended runway center line where the code number is 1 or 2; or

- c) penetrates the inner approach surface, the inner transitional surface or the balked landing surface;

shall be frangible and mounted as low as possible.

Note. — See 5.3.1.5 for the protection date for existing elevated approach lights.

9.9.6 Any equipment or installation required for air navigation purposes which is an obstacle of operational significance in accordance with 4.2.4, 4.2.11, 4.2.20 or 4.2.27 should be frangible and mounted as low as possible.

## **9.10 Fencing**

### **Application**

9.10.1 A fence or other suitable barrier should be provided on an aerodrome to prevent the entrance to the movement area of animals large enough to be a hazard to aircraft.

9.10.2 A fence or other suitable barrier shall be provided on an aerodrome to prevent the entrance to the movement area of animals large enough to be a hazard to aircraft.

9.10.3 A fence or other suitable barrier should be provided on an aerodrome to deter the inadvertent or premeditated access of an unauthorized person onto a non-public area of the aerodrome.

Note 1.— This is intended to include the barring of sewers, ducts, tunnels, etc., where necessary to prevent access.

Note 2.— Special measures may be required to prevent the access of an unauthorized person to runways or taxiways which overpass public roads.

9.10.4 A fence or other suitable barrier shall be provided on an aerodrome to deter the inadvertent or premeditated access of an unauthorized person onto a non-public area of the aerodrome.

Note 1.— This is intended to include the barring of sewers, ducts, tunnels, etc., where necessary to prevent access.

Note 2.— Special measures may be required to prevent the access of an unauthorized person to runways or taxiways which overpass public roads.

**CHAPTER -9- AERODROME OPERATIONAL SERVICES, EQUIPMENT AND  
INSTALLATIONS**

9.10.5 Suitable means of protection should be provided to deter the inadvertent or premeditated access of unauthorized persons into ground installations and facilities essential for the safety of civil aviation located off the aerodrome.

9.10.6 Suitable means of protection shall be provided to deter the inadvertent or premeditated access of unauthorized persons into ground installations and facilities essential for the safety of civil aviation located off the aerodrome.

**Location**

9.10.7 The fence or barrier should be located so as to separate the movement area and other facilities or zones on the aerodrome vital to the safe operation of aircraft from areas open to public access.

9.10.8 The fence or barrier shall be located so as to separate the movement area and other facilities or zones on the aerodrome vital to the safe operation of aircraft from areas open to public access.

9.10.9 When greater security is thought necessary, a cleared area should be provided on both sides of the fence or barrier to facilitate the work of patrols and to make trespassing more difficult. Consideration should be given to the provision of a perimeter road inside the aerodrome fencing for the use of both maintenance personnel and security patrols.

**9.11 Security lighting**

At an aerodrome where it is deemed desirable for security reasons, a fence or other barrier provided for the protection of international civil aviation and its facilities should be illuminated at a minimum essential level. Consideration should be given to locating lights so that the ground area on both sides of the fence or barrier, particularly at access points, is illuminated.

**Intentionally left blank**

## CHAPTER 10 - AERODROME MAINTENANCE

### 10.1 General

10.1.1 A maintenance program, including preventive maintenance where appropriate, shall be established at an aerodrome to maintain facilities in a condition which does not impair the safety, regularity or efficiency of air navigation.

Note 1. — Preventive maintenance is programmed maintenance work done in order to prevent a failure or degradation of facilities.

Note 2. — “Facilities” are intended to include such items as pavements, visual aids, fencing, drainage and electrical systems and buildings.

10.1.2 The design and application of the maintenance program should observe Human Factors principles.

Note. — Guidance material on Human Factors principles can be found in the Human Factors Training Manual (Doc 9683) and in the Airport Service Manual (Doc 9137), Part 8.

### 10.2 Pavements

10.2.1 The surfaces of all movement areas including pavements (runways, taxiways, aprons and adjacent areas) shall be inspected and their conditions monitored regularly as part of an aerodrome preventive and corrective maintenance programme with the objective of avoiding and eliminating of any loose stones or other objects that might cause damage to aircraft structures or engines, or impair the operation of aircraft systems.

Note 1. — See 2.9.3 for inspections of movements areas.

Note 2.— Guidance on carrying out daily inspections of the movement area is given in the Airport Services Manual (Doc 9137), Part 8, the Manual of Surface Movement Guidance and Control Systems (SMGCS) (Doc 9476) and the Advanced Surface Movement Guidance and Control Systems (A-SMGCS) Manual (Doc 9830).

Note 3. — Additional guidance on sweeping/cleaning of surface is contained in the Airport Service Manual (Doc 9137), Part 9.

Note 4. — Guidance on precautions to be taken in regard to the surface of shoulders is given in Attachment A, Section 8, and the ICAO Aerodrome Design Manual, Part 2.

Note 5. — Where the pavement is used by large aircraft or aircraft with tire pressures in the upper categories referred

to in 2.6.6(c), particular attention should be given to the integrity of light fittings in the pavement and pavement joints.

10.2.2 The surface of a runway shall be maintained in a condition such as to prevent formation of harmful irregularities.

Note. — See Attachment A, Section 5.

10.2.3 A paved runway shall be maintained in a condition so as to provide surface friction characteristics at or above the minimum friction level specified by the state.

Note.— The Airport Services Manual (Doc 9137), Part 2, contains further information on this subject, on improving surface friction characteristics of the runways.

10.2.4. Runway friction characteristics for maintenance purpose shall be periodically measured with a continuous friction measuring device using self-wetting features and documented. The frequency of these measurements shall be sufficient to determine the trend of the surface friction characteristics of the runway.

Note 1.— Guidance on evaluating the friction characteristics of a runway is provided in Attachment A, Section 7. Additional guidance is included in the ICAO Airport Services Manual (Doc 9137), Part 2.

Note 2.— The objective of 10.2.3 to 10.2.6 is to ensure that the surface friction characteristics for the entire runway remain at or above a minimum friction level specified by GACA.

Note 3.— Guidance for the determination of the required frequency is provided in Attachment A, Section 7 and in the Airport Services Manual (Doc 9137, Part 2, Appendix 5).

10.2.5 Corrective maintenance action shall be taken to prevent the runway surface friction characteristics for either the entire runway or a portion thereof from failing below a minimum friction level specified by GACA.

Note.— A portion of runway in the order of 100 m long may be considered significant for maintenance or reporting action.

10.2.6 When there is reason to believe that the drainage characteristics of a runway, or portions thereof, are poor due to slopes or depressions, then the runway surface friction characteristics should be assessed under natural or simulated conditions that are representative of local rain and corrective maintenance action should be taken as necessary.



CHAPTER 10. AERODROME MAINTENANCE

10.2.7 When a taxiway is used by turbine-engined aeroplanes, the surface of the taxiway shoulders should be maintained so as to be free of any loose stones or other objects that could be ingested by the aeroplane engines.

Note.— Guidance on this subject is given in the ICAO Aerodrome ICAO Design Manual, Part 2.

10.3 Removal of contaminants

10.3.1. Snow, slush, ice, standing water, mud, dust, sand, oil, rubber deposits and other contaminants shall be removed from the surface of runways in use as rapidly and completely as possible to minimize accumulation.

Note.— The above requirement does not imply that winter operations on compacted snow and ice are prohibited. Guidance on snow removal and ice control and removal of other contaminants is given in the Aerodrome Service Manual (Doc 9137), Part 2 and 9.

10.3.2 Taxiways should be kept clear of snow, slush, ice, etc., to the extent necessary to enable aircraft to be taxied to and from an operational runway.

10.2.3 Aprons should be kept clear of snow, slush, ice, etc., to the extent necessary To enable aircraft to maneuver safely or, where appropriate, to be towed or pushed.

10.3.4 Whenever the clearance of snow, slush, ice, etc., from the various parts of the movement area cannot be carried out simultaneously, the order of priority after the runway(s) is use should be set in consultation with the affected parties such as rescue and fire fighting service and documented in a snow plan.

Note 1.— See Annex 15, Appendix 1, Part 3, AD 1.2.2 for information to be promulgated in an AIP concerning a snow plan. Doc 8126 Chapter 5 contains guidance on the description of a snow plan including general policy concerning operational priorities established for the clearance of movement areas.

Note 2. — Doc 9137, Part 8, Chapter 6 specifies that an aerodrome snow plan clearly define, inter alia, the priority of surfaces to be cleared.

10.3.5 Chemicals to remove or to prevent the formation of ice and frost on aerodrome pavements should be used when conditions indicate their use could be effective. Caution should be exercised in the application of the chemicals so as not to create a more slippery condition.

Note. — Guidance on the use of chemicals for aerodrome pavements is given in the ICAO Airport Services Manual, Part 2.

10.3.6 Chemicals which may have harmful effects on aircraft or pavements, or chemicals which may have toxic effects on the aerodrome environment, shall not be used.

10.4 Runway pavement overlays

Note. — The following specifications are intended for runway pavement overlay projects when the runway is to be returned temporarily to an operational status before resurfacing is complete. This may necessitate a temporary ramp between the new and old runway surfaces. Guidance on overlaying pavements and assessing their operational status is given in the ICAO Aerodrome Design Manual, Part 3.

10.4.1 The longitudinal slope of the temporary ramp, measured with reference to the existing runway surface or previous overlay course, shall be:

- a) 0.5 to 1.0 per cent for overlays up to and including 5 cm in thickness; and
- b) not more than 0.5 per cent for overlays more than 5 cm in thickness.

10.4.2 Overlaying should proceed from one end of the runway toward the other end so that based on runway utilization most aircraft operations will experience a down ramp.

10.4.3 The entire width of the runway should be overlaid during each work session.

10.4.4 Before a runway being overlaid is returned to a temporary operational status, a runway center line marking conforming to the specifications in Section 5.2.3 shall be provided. Additionally, the location of any temporary threshold shall be identified by a 3.6 m wide transverse stripe.

10.4.5 The overlay should be constructed and maintained above the minimum friction level specified in 10.2.3.

10.5 Visual aids

Note 1. — These specifications are intended to define the maintenance performance level objectives. They are not intended to define whether the lighting system is operationally out of service.

Note 2. — The energy saving of light emitting diodes (LEDs) are due in large part to the fact that they do not produce the infra-red heat signature of incandescent lamps. Aerodrome operators who have come to expect the melting of ice and snow by this heat signature may wish to evaluate whether or not a modified maintenance schedule is required during such conditions, or evaluate



CHAPTER 10. AERODROME MAINTENANCE

the possible operational value of installing LED fixtures with heating elements.

Note 3. — Enhanced vision systems (EVs) technology relies on the infra-red heat signature provided by incandescent lighting. Annex 15 protocols provide an appropriate means of notifying aerodrome users of EVS when lighting systems are converted to LED.

10.5.1 A light shall be deemed to be unserviceable when the main beam average intensity is less than 50 per cent of the value specified in the appropriate figure in Appendix 2. For light units where the designed main beam average intensity is above the value shown in Appendix 2, the 50 per cent value shall be related to that design value.

10.5.2 A system of preventive maintenance of visual aids shall be employed to ensure lighting and marking system reliability.

Note.— Guidance on preventive maintenance of visual aids is given in the ICAO Airport Services Manual, Part 9.

10.5.3 The system of preventive maintenance employed for a precision approach runway category II or III should include at least the following checks:

- a) visual inspection and in-field measurement of the intensity, beam spread and orientation of lights included in the approach and runway lighting systems;
- b) control and measurement of the electrical characteristics of each circuitry included in the approach and runway lighting systems; and
- c) control of the correct functioning of light intensity settings used by air traffic control.

10.5.4 In-field measurement of intensity, beam spread and orientation of lights included in approach and runway lighting systems for a precision approach runway category II or III should be undertaken by measuring all lights, as far as practicable, to ensure conformance with the applicable specification of Appendix 2.

10.5.5 Measurement of intensity, beam spread and orientation of lights included in approach and runway lighting systems for a precision approach runway category II or III should be undertaken using a mobile measuring unit of sufficient accuracy to analyze the characteristics of the individual lights.

10.5.6 The frequency of measurement of lights for a precision approach runway category II or III should be based on traffic density, the local pollution level, the reliability of the installed lighting equipment and the

continuous assessment of the results of the in-field measurements but in any event should not be less than twice a year for in-pavement lights and not less than once a year for other lights.

10.5.7 The system of preventive maintenance employed for a precision approach runway category II or III shall have as its objective that, during any period of category II or III operations, all approach and runway lights are serviceable, and that in any event at least:

- a) 95 per cent of the lights are serviceable in each of the following particular significant elements:
  1. precision approach category II and III lighting system, the inner 450 m;
  2. runway center line lights;
  3. runway threshold lights; and
  4. runway edge lights;
- b) 90 per cent of the lights are serviceable in the touchdown zone lights;
- c) 85 per cent of the lights are serviceable in the approach lighting system beyond 450 m; and
- d) 75 per cent of the lights are serviceable in the runway end lights.

In order to provide continuity of guidance, the allowable percentage of unserviceable lights shall not be permitted in such a way as to alter the basic pattern of the lighting system. Additionally, an unserviceable light shall not be permitted adjacent to another unserviceable light, except in a barrette or a crossbar where two adjacent unserviceable lights may be permitted.

Note. — With respect to barrettes, crossbars and runway edge lights, lights are considered to be adjacent if located consecutively and:

- laterally: in the same barrette or crossbar; or
- longitudinally: in the same row of edge lights or barrettes.

10.5.8 The system of preventive maintenance employed for a stop bar provided at a runway-holding position used in conjunction with a runway intended for operations in runway visual range conditions less than a value of 350 m shall have the following objectives:

- a. no more than two lights will remain unserviceable; and
- b. two adjacent lights will not remain unserviceable unless the light spacing is significantly less than that specified.

CHAPTER 10. AERODROME MAINTENANCE

10.5.9 The system of preventive maintenance employed for a taxiway intended for use in runway visual range conditions less than a value of 350 m shall have as its objective that no two adjacent taxiway center line lights be unserviceable.

10.5.10 The system of preventive maintenance employed for a precision approach runway category I shall have as its objective that, during any period of category I operations, all approach and runway lights are serviceable, and that in any event at least 85 per cent of the lights are serviceable in each of the following:

- a) precision approach category I lighting system;
- b) runway threshold lights;
- c) runway edge lights; and
- d) runway end lights.

In order to provide continuity of guidance an unserviceable light shall not be permitted adjacent to another unserviceable light unless the light spacing is significantly less than that specified.

Note.— In barrettes and crossbars, guidance is not lost by having two adjacent unserviceable lights.

10.5.11 The system of preventive maintenance employed for a runway meant for take-off in runway visual range conditions less than a value of 550 m shall have as its objective that, during any period of operations, all runway lights are serviceable and that in any event:

- a) at least 95 per cent of the lights are serviceable in the runway center line lights (where provided) and in the runway edge lights; and
- b) at least 75 per cent of the lights are serviceable in the runway end lights.

In order to provide continuity of guidance, an unserviceable light shall not be permitted adjacent to another unserviceable light.

10.5.12 The system of preventive maintenance employed for a runway meant for take-off in runway visual range conditions of a value of 550 m or greater shall have as its objective that, during any period of operations, all runway lights are serviceable and that, in any event, at least 85 per cent of the lights are serviceable in the runway edge lights and runway end lights. In order to provide continuity of guidance, an unserviceable light shall not be permitted adjacent to another unserviceable light.

10.5.13 During low visibility procedures the appropriate authority should restrict construction or maintenance activities in the proximity of aerodrome electrical systems.

**Intentionally left blank**

**APPENDIX 1. COLOURS FOR AERONAUTICAL GROUND LIGHTS,  
MARKINGS, SIGNS AND PANELS**

**APPENDIX 1 - COLOURS FOR  
AERONAUTICAL GROUND LIGHTS,  
MARKINGS, SIGNS AND PANELS**

**1. General**

Introductory Note — The following specifications define the chromaticity limits of colors to be used for aeronautical ground lights, markings, signs and panels. The specifications are in accord with the 1983 specifications of the International Commission on Illumination (CIE).

It is not possible to establish specifications for colors such that there is no possibility of confusion. For reasonably certain recognition, it is important that the eye illumination be well above the threshold of perception, that the color is not greatly modified by selective atmospheric attenuations and that the observer's color vision is adequate. There is also a risk of confusion of color at an extremely high level of eye illumination such as may be obtained from a high-intensity source at very close range. Experience indicates that satisfactory recognition can be achieved if due attention is given to these factors.

The chromaticities are expressed in terms of the standard observer and coordinate system adopted by the International Commission on Illumination (CIE) at its Eighth Session at Cambridge, England, in 1931.\*

**2. Colors for aeronautical ground lights**

**2.1 Chromaticities**

2.1.1 The chromaticities of aeronautical ground lights shall be within the following boundaries:

CIE Equations (see Figure 1.1):

- |                 |                      |
|-----------------|----------------------|
| a) Red          |                      |
| Purple boundary | $y = 0.980 - x$      |
| Yellow boundary | $y = 0.335$          |
| b) Yellow       |                      |
| Red boundary    | $y = 0.382$          |
| White boundary  | $y = 0.790 - 0.667x$ |
| Green boundary  | $y = x - 0.120$      |
| c) Green        |                      |
| Yellow boundary | $x = 0.360 - 0.080y$ |
| White boundary  | $x = 0.650y$         |
| Blue boundary   | $y = 0.390 - 0.171x$ |

- |                   |  |
|-------------------|--|
| d) Blue           |  |
| Green boundary    | $y = 0.805x + 0.065$                                     |
| White boundary    | $y = 0.400 - x$  |
| Purple boundary   | $x = 0.600y + 0.133$                                     |
| e) White          |  |
| i. incandescent   | $x = 0.500$  |
| Yellow boundary   | $x = 0.285$  |
| Blue boundary     | $y = 0.440$  |
| Green boundary    | $\text{and } y = 0.150 + 0.640x$                         |
|                   | $y = 0.050 + 0.750x$                                     |
| Purple boundary   | $\text{and } y = 0.382$                                  |
| ii. LED           |  |
| Yellow boundary   | $x = 0.440$  |
| Blue boundary     | $x = 0.320$  |
| Green boundary    | $y = 0.150 + 0.643x$                                     |
| Purple boundary   | $y = 0.050 + 0.757x$                                     |
| f) Variable white |  |
| Yellow boundary   | $x = 0.255 + 0.750y$<br>$\text{and } x = 1.185 - 1.500y$ |
| Blue boundary     | $x = 0.285$  |
| Green boundary    | $y = 0.440$<br>$\text{and } y = 0.150 + 0.640x$          |
| Purple boundary   | $y = 0.050 + 0.750x$<br>$\text{and } y = 0.38$           |

Note. — Guidance on chromaticity changes resulting from the effect of temperature on filtering elements is given in the ICAO Aerodrome Design Manual, Part 4.

2.1.2 Where dimming is not required, or where observers with defective color vision must be able to determine the color of the light, green signals should be within the following boundaries:


- |                    |                      |
|--------------------|----------------------|
| a) Yellow boundary | $y = 0.726 - 0.726x$ |
| b) White boundary  | $x = 0.650y$         |
| c) Blue boundary   | $y = 0.390 - 0.171x$ |

2.1.3 Where increased certainty of recognition is more important than maximum visual range, green signals should be within the following boundaries:

- |                    |                      |
|--------------------|----------------------|
| a) Yellow boundary | $y = 0.726 - 0.726x$ |
| b) White boundary  | $x = 0.625y - 0.041$ |

**APPENDIX 1. COLOURS FOR AERONAUTICAL GROUND LIGHTS,  
MARKINGS, SIGNS AND PANELS**

- c) Blue boundary  $y = 0.390 - 0.171x$   
\* See CIE Publication No. 15, Colorimetry (1971)



APPENDIX 1. COLOURS FOR AERONAUTICAL GROUND LIGHTS,  
MARKINGS, SIGNS AND PANELS

2.2 Discrimination between lights

2.2.1 If there is a requirement to discriminate yellow and white from each other, they should be displayed in close proximity of time or space as, for example, by being flashed successively from the same beacon.

2.2.2 If there is a requirement to discriminate yellow from green and/or white, as for example on exit taxiway center line lights, the y coordinates of the yellow light should not exceed a value of 0.40.

Note. — The limits of white have been based on the assumption that they will be used in situations in which the characteristics (color temperature) of the light source will be substantially constant.

2.2.3 The color variable white is intended to be used only for lights that are to be varied in intensity, e.g. to avoid dazzling. If this color is to be discriminated from yellow, the lights should be so designed and operated that:

- a) the x coordinate of the yellow is at least 0.050 greater than the x coordinate of the white; and
- b) the disposition of the lights will be such that the yellow lights are displayed simultaneously and in close proximity to the white lights.

2.2.4 The color of aeronautical ground lights shall be verified as being within the boundaries specified in Figure 1.1 by measurement at five points within the area limited by the innermost isocandela curve (isocandela diagrams in Appendix 2 refer), with operation at rated current or voltage. In the case of elliptical or circular isocandela curves, the color measurements shall be taken at the center and at the horizontal and vertical limits. In the case of rectangular isocandela curves, the color measurements shall be taken at the center and the limits of the diagonals (corners). In addition, the color of the light shall be checked at the outermost isocandela curve to ensure that there is no color shift that might cause signal confusion to the pilot.

Note 1 — For the outermost isocandela curve, a measurement of color coordinates should be made and recorded for review and judgment of acceptability by the appropriate authority.

Note 2 — Certain light units may have application so that they may be viewed and used by pilots from directions beyond that of the outermost isocandela curve (e.g. stop bar lights at significantly wide runway-holding positions). In such instances, the appropriate authority should assess the actual application and if necessary require a check of

color shift at angular ranges beyond the outermost curve.

2.2.5 In the case of visual approach slope indicators and other light units having a color transition sector, the color shall be measured at points in accordance with 2.2.4, except that the color areas shall be treated separately and no point shall be within 0.5 degrees of the transition sector.

3. Colors for markings, signs and panels

Note 1 — The specifications of surface colors given below apply only to freshly colored surfaces. Colors used for markings, signs and panels usually change with time and therefore require renewal.

Note 2 — Guidance on surface colors is contained in the CIE document entitled

Recommendations for Surface Colors for Visual Signaling — Publication No. 39-2 (TC-106) 1983.

Note 3 — The specifications recommended in 3.4 below for transilluminated panels are interim in nature and are based on the CIE specifications for transilluminated signs. It is intended that these specifications will be reviewed and updated as and when CIE develops specifications for transilluminated panels.

3.1 The chromaticities and luminance factors of ordinary, colors of retro-reflective materials and colors of transilluminated (internally illuminated) signs and panels shall be determined under the following standard conditions:

- a) angle of illumination: 45°;
- b) direction of view: perpendicular to surface; and
- c) illuminant: CIE standard illuminant D65.

3.2 The chromaticity and luminance factors of ordinary colors for markings and externally illuminated signs and panels should be within the following boundaries when determined under standard conditions. CIE Equations (see Figure 1.2):

- a) Red
  - Purple boundary  $y = 0.345 - 0.051x$
  - White boundary  $y = 0.910 - x$
  - Orange boundary  $y = 0.314 + 0.047x$
  - Luminance factor  $\beta = 0.07 \text{ (mm)}$

**GACA REGULATIONS - SECTION 14 - AERODROMES  
VOLUME I - AERODROME DESIGN AND OPERATIONS**

**APPENDIX 1. COLOURS FOR AERONAUTICAL GROUND LIGHTS,  
MARKINGS, SIGNS AND PANELS**

b) Orange  
Red boundary  $y = 0.265 + 0.205x$   
White boundary  $y = 0.910 - x$   
Yellow boundary  $y = 0.207 + 0.390x$   
Luminance factor  $\beta = 0.20$  (mnm)

c) Yellow  
Orange boundary  $y = 0.108 + 0.707x$   
White boundary  $y = 0.910 - x$   
Green boundary  $y = 1.35x - 0.093$   
Luminance factor  $\beta = 0.45$  (mnm)

d) White  
Purple boundary  $y = 0.010 + x$   
Blue boundary  $y = 0.610 - x$   
Green boundary  $y = 0.030 + x$   
Yellow boundary  $y = 0.710 - x$   
Luminance factor  $\beta = 0.75$  (mnm)

e) Black  
Purple boundary  $y = x - 0.030$   
Blue boundary  $y = 0.570 - x$   
Green boundary  $y = 0.050 + x$   
Yellow boundary  $y = 0.740 - x$   
Luminance factor  $\beta = 0.03$  (max)

f) Yellowish green  
Green boundary  $y = 1.317x + 0.4$   
White boundary  $y = 0.910 - x$   
Yellow boundary  $y = 0.867x + 0.4$

Note. — The small separation between surface red and surface orange is not sufficient to ensure the distinction of these colors when seen separately.

3.3 The chromaticity and luminance factors of colors of retro-reflective materials for markings, signs and panels should be within the following boundaries when determined under standard conditions. CIE Equations (see Figure 1.3):

a) Red  
Purple boundary  $y = 0.345 - 0.051x$   
White boundary  $y = 0.910 - x$   
Orange boundary  $y = 0.314 + 0.047x$   
Luminance factor  $\beta = 0.03$  (mnm)

b) Orange  
Red boundary  $y = 0.265 + 0.205x$   
White boundary  $y = 0.910 - x$   
Yellow boundary  $y = 0.207 + 0.390x$   
Luminance factor  $\beta = 0.14$  (mnm)

c) Yellow  
Orange boundary  $y = 0.160 + 0.540x$   
White boundary  $y = 0.910 - x$   
Green boundary  $y = 1.35x - 0.093$   
Luminance factor  $\beta = 0.16$  (mnm)

d) White  
Purple boundary  $y = x$   
Blue boundary  $y = 0.610 - x$   
Green boundary  $y = 0.040 + x$   
Yellow boundary  $y = 0.710 - x$   
Luminance factor  $\beta = 0.27$  (mnm)

e) Blue  
Green boundary  $y = 0.118 + 0.675x$   
White boundary  $y = 0.370 - x$   
Purple boundary  $y = 1.65x - 0.187$   
Luminance factor  $\beta = 0.01$  (mnm)

f) Green  
Yellow boundary  $y = 0.711 - 1.22x$   
White boundary  $y = 0.243 + 0.670x$   
Blue boundary  $y = 0.405 - 0.243x$   
Luminance factor  $\beta = 0.03$  (mnm)

3.4 The chromaticity and luminance factors of colors for transilluminated (internally illuminated) signs and panels should be within the following boundaries when determined under standard conditions. CIE Equations (see Figure 1.4):

a) Red  
Purple boundary  $y = 0.345 - 0.051x$   
White boundary  $y = 0.910 - x$   
Orange boundary  $y = 0.314 + 0.047x$   
Luminance factor  $\beta = 0.07$  (mnm)  
(day condition)  
Relative luminance 5% (mnm)  
to white (night condition 20% (max))

b) Yellow  
Orange boundary  $y = 0.108 + 0.707x$   
White boundary  $y = 0.910 - x$   
Green boundary  $y = 1.35x - 0.093$   
Luminance factor  $\beta = 0.45$  (mnm)  
(day condition)  
Relative luminance 30% (mnm)  
to white (night condition 80% (max))

c) White  
Purple boundary  $y = 0.010 + x$   
Blue boundary  $y = 0.610 - x$   
Green boundary  $y = 0.030 + x$   
Yellow boundary  $y = 0.710 - x$   
Luminance factor  $\beta = 0.75$  (mnm)



APPENDIX 1. COLOURS FOR AERONAUTICAL GROUND LIGHTS,  
MARKINGS, SIGNS AND PANELS

(day condition)

Relative luminance 100% to white (night condition)

d) Black

Purple boundary  $y = x - 0.030$

Blue boundary  $y = 0.570 - x$

Green boundary  $y = 0.050 + x$

Yellow boundary  $y = 0.740 - x$

Luminance factor  $\beta = 0.03$  (max)


(day condition) Relative luminance 0% (min)

to white (night condition 2% (max))



**GACA REGULATIONS - SECTION 14 - AERODROMES  
VOLUME I - AERODROME DESIGN AND OPERATIONS**

**APPENDIX 1. COLOURS FOR AERONAUTICAL GROUND LIGHTS,  
MARKINGS, SIGNS AND PANELS**



**Figure A1-1. Colors for aeronautical ground lights**



APPENDIX 1. COLOURS FOR AERONAUTICAL GROUND LIGHTS,  
MARKINGS, SIGNS AND PANELS




Figure A1-3. Colors of retro-reflective materials for markings, signs and panels

APPENDIX 1. COLOURS FOR AERONAUTICAL GROUND LIGHTS,  
MARKINGS, SIGNS AND PANELS





Figure A1-4. Colors of transilluminated (internally illuminated) signs and panels

APPENDIX 2 AERONAUTICAL GROUND LIGHT CHARACTERISTICS



Notes:

1. Curves calculated on formula  $\frac{x^2}{a^2} + \frac{y^2}{b^2} = 1$

a	10	14	15
b	5.5	6.5	8.5

2. Vertical setting angles of the lights shall be such that the following vertical coverage of the main beam will be met:


distance from threshold      vertical main beam coverage

threshold to 315 m	0° — 11°
316 m to 475 m	0.5° — 11.5°
476 m to 640 m	1.5° — 12.5°
641 m and beyond	2.5° — 13.5° (as illustrated above)

3. Lights in crossbars beyond 22.5 m from the centre line shall be toed-in 2 degrees. All other lights shall be aligned parallel to the centre line of the runway.
4. See collective notes for Figures A2-1 to A2-11.

Figure A2-1. Isocandela diagram for approach center line light and crossbars (white light)





Notes:

- Curves calculated on formula  $\frac{x^2}{a^2} + \frac{y^2}{b^2} = 1$


a	7.0	11.5	16.5
b	5.0	6.0	8.0

- Toe-in 2 degrees
- Vertical setting angles of the lights shall be such that the following vertical coverage of the main beam will be met:

distance from threshold	vertical main beam coverage
threshold to 115 m	0.5° — 10.5°
116 m to 215 m	1° — 11°
216 m and beyond	1.5° — 11.5° (as illustrated above)

- See collective notes for Figures A2-1 to A2-11.

Figure A2-2. Isocandela diagram for approach side row light (red light)




Notes:

1. Curves calculated on formula  $\frac{x^2}{a^2} + \frac{y^2}{b^2} = 1$

a	5.5	7.5	9.0
b	4.5	6.0	8.5

2. Toe-in 3.5 degrees
3. See collective notes for Figures A2-1 to A2-11.

Figure A2-3. Isocandela diagram for threshold light (green light)



Notes:

1. Curves calculated on formula  $\frac{x^2}{a^2} + \frac{y^2}{b^2} = 1$


a	7.0	11.5	16.5
b	5.0	6.0	8.0

2. Toe-in 2 degrees
3. See collective notes for Figures A2-1 to A2-11.

Figure A2-4. Isocandela diagram for threshold wing bar light (green light)

**GACA REGULATIONS - SECTION 14 - AERODROMES  
VOLUME I - AERODROME DESIGN AND OPERATIONS**

**APPENDIX 2. AERONAUTICAL GROUND LIGHT CHARACTERISTICS**




Notes:

1. Curves calculated on formula  $\frac{x^2}{a^2} + \frac{y^2}{b^2} = 1$

a	5.0	7.0	8.5
b	3.5	6.0	8.5

2. Toe-in 4 degrees
3. See collective notes for Figures A2-1 to A2-11.

Figure A2-3. Isocandela diagram for touchdown zone light (white light)



Notes:

1. Curves calculated on formula  $\frac{x^2}{a^2} + \frac{y^2}{b^2} = 1$


a	5.0	7.0	8.5
b	3.5	6.0	8.5

2. For red light, multiply values by 0.15.
3. For yellow light, multiply values by 0.40.
4. See collective notes for Figures A2-1 to A2-11.

Figure A2-6. Isocandela diagram for runway centre line light with 30 m longitudinal spacing (white light) and rapid exit taxiway indicator light (yellow light)

**GACA REGULATIONS - SECTION 14 - AERODROMES  
VOLUME I – AERODROME DESIGN AND OPERATIONS**

**APPENDIX 2. AERONAUTICAL GROUND LIGHT CHARACTERISTICS**



Notes:


1. Curves calculated on formula  $\frac{x^2}{a^2} + \frac{y^2}{b^2} = 1$

a	5.0	7.0	8.5
b	4.5	8.5	10

2. For red light, multiply values by 0.15.  
3. For yellow light, multiply values by 0.40.  
4. See collective notes for Figures A2-1 to A2-11.

Figure A2-7. Isocandela diagram for runway centre line light  
with 15 m longitudinal spacing (white light) and rapid exit  
taxiway indicator light (yellow light)






Notes:

1. Curves calculated on formula  $\frac{x^2}{a^2} + \frac{y^2}{b^2} = 1$

a	6.0	7.5	9.0
b	2.25	5.0	6.5

2. See collective notes for Figures A2-1 to A2-11.

Figure A2-8. Isocandela diagram for runway end light (red light)




Notes:

1. Curves calculated on formula  $\frac{x^2}{a^2} + \frac{y^2}{b^2} = 1$

a	5.5	7.5	9.0
b	3.5	6.0	8.5

2. Toe-in 3.5 degrees
3. For yellow light, multiply values by 0.40.
4. See collective notes for Figures A2-1 to A2-11.

Figure A2-9. Isocandela diagram for runway edge light where width of runway is 45 m (white light)



Notes:

1. Curves calculated on formula  $\frac{x^2}{a^2} + \frac{y^2}{b^2} = 1$

a	6.5	8.5	10.0
b	3.5	6.0	8.5

2. Toe-in 4.5 degrees
3. For yellow light, multiply values by 0.40.
4. See collective notes for Figures A2-1 to A2-11.

Figure A2-10. Isocandela diagram for runway edge light where width of runway is 60 m (white light)





Figure A2-11. Grid points to be used for the calculation of average intensity of approach and runway lights

**Collective notes to Figures A2-1 to A2-11**

1. The ellipses in each figure are symmetrical about the common vertical and horizontal axes.
2. Figures A2-1 to A2-10 show the minimum allowable light intensities. The average intensity of the main beam is calculated by establishing grid points as shown in Figure A2-11 and using the intensity values measured at all grid points located within and on the perimeter of the ellipse representing the main beam. The average value is the arithmetic average of light intensities measured at all considered grid points.
3. No deviations are acceptable in the main beam pattern when the lighting fixture is properly aimed.
4. Average intensity ratio. The ratio between the average intensity within the ellipse defining the main beam of a typical new light and the average light intensity of the main beam of a new runway edge light shall be as follows:

Figure A2-1	Approach center line and crossbars	1.5 to 2.0 (white light)
Figure A2-2	Approach side row	0.5 to 1.0 (red light)
Figure A2-3	Threshold	1.0 to 1.5 (green light)
Figure A2-4	Threshold wing bar	1.0 to 1.5 (green light)
Figure A2-5	Touchdown zone	0.5 to 1.0 (white light)
Figure A2-6	Runway center line (longitudinal spacing 30 m)	0.5 to 1.0 (white light)
Figure A2-7	Runway center line (longitudinal spacing 15 m)	0.5 to 1.0 for CAT III (white light) 0.25 to 0.5 for CAT I, II white light)
Figure A2-8	Runway end	0.25 to 0.5 (red light)
Figure A2-9	Runway edge (45 m runway width)	1.0 (white light)
Figure A2-10	Runway edge (60 m runway width)	1.0 (white light)

5. The beam coverages in the figures provide the necessary guidance for approaches down to an RVR of the order of 150 m and take-offs down to an RVR of the order of 100 m.
6. Horizontal angles are measured with respect to the vertical plane through the runway center line. For lights other than center line lights, the direction towards the runway center line is considered positive. Vertical angles are measured with respect to the horizontal plane.
7. Where, for approach center line lights and crossbars and for approach side row lights, inset lights are used in lieu of elevated lights, e.g. on a runway with a displaced threshold, the intensity requirements can be met by installing two or three fittings (lower intensity) at each position.
8. The importance of adequate maintenance cannot be over-emphasized. The average intensity should never fall to a value less than 50 per cent of the value shown in the figures and it should be the aim of airport authorities to maintain a level of light output close to the specified minimum average intensity.
9. The light unit shall be installed so that the main beam is aligned within one-half degree of the specified requirement.




Notes:

1. These beam coverages allow for displacement of the cockpit from the center line up to distances of the order of 12 m and are intended for use before and after curves.
2. See collective notes for Figures A2-12 to A2-21.
3. Increased intensities for enhanced rapid exit taxiway center line lights as recommended in 5.3.16.9 are four times the respective intensities in the figure (i.e. 800 cd for minimum average main beam).

**Figure A2-12. Isocandela diagram for taxiway center line (15 m spacing), no-entry bar and stop bar lights in straight sections intended for use in runway visual range conditions of less than a value of 350 m where large offsets can occur and for low-intensity runway guard lights, Configuration B**






Notes:

1. These beam coverages are generally satisfactory and cater for a normal displacement of the cockpit from the center line of approximately 3 m.
2. See collective notes for Figures A2-12 to A2-21.


**Figure A2-13. Isocandela diagram for taxiway center line (15 m spacing), no-entry bar and stop bar lights in straight sections intended for use in runway visual range conditions of less than a value of 350 m**



Notes:

1. Lights on curves to be toed-in 15.75 degrees with respect to the tangent of the curve.
2. See collective notes for Figures A2-12 to A2-21.


**Figure A2-14. Isocandela diagram for taxiway center line (7.5 m spacing), no-entry bar and stop bar lights in curved sections intended for use in runway visual range conditions of less than a value of 350 m**



Notes:

1. At locations where high background luminance is usual and where deterioration of light output resulting from dust, snow and local contamination is a significant factor, the cd-values should be multiplied by 2.5.
2. Where omnidirectional lights are used they shall comply with the vertical beam requirements in this figure.
3. See collective notes for Figures A2-12 to A2-21.


**Figure A2-15. Isocandela diagram for taxiway center line (30 m, 60 m spacing), no-entry bar and stop bar lights in straight sections intended for use in runway visual range conditions of 350 m or greater**



Notes:

1. Lights on curves to be toed-in 15.75 degrees with respect to the tangent of the curve.
2. At locations where high background luminance is usual and where deterioration of light output resulting from dust, snow and local contamination is a significant factor, the cd-values should be multiplied by 2.5.
3. These beam coverages allow for displacement of the cockpit from the center line up to distances of the order of 12 m as could occur at the end of curves.
4. See collective notes for Figures A2-12 to A2-21.

**Figure A2-16. Isocandela diagram for taxiway center line (7.5 m, 15 m, 30 m spacing) , no-entry bar and stop bar lights in curved sections intended for use in runway visual range conditions of 350 m or greater**




Curve	a	b	c	d	e
Intensity (cd)	8	20	100	450	1800

Notes:

1. Beam coverage allows for displacement of the cockpit from the center line up of distances in the order of 12 m and is intended for use before and after curves.
2. See collective notes for Figures A2.12 to A2.21.

**Figure A2.17 Isocandela diagram for high-intensity taxiway center line (15 m spacing), no-entry bar and stop bar lights in straight sections intended for use in an advanced surface movement guidance and control system where higher light intensities are required and where large offsets can occur**




Curve	a	b	c	d	e
Intensity (cd)	8	20	100	450	1800

Notes:

1. Beam coverage is generally satisfactory and caters to a normal displacement of the cockpit corresponding to the outer main gear wheel on the taxiway edge.
2. See collective notes for Figures A2.12 to A2.21.

**Figure A2.18 Isocandela diagram for high-intensity taxiway center line (15 m spacing), no-entry bar and stop bar lights in straight sections intended for use in an advanced surface movement guidance and control system where higher light intensities are required**






Curve	a	b	c	d
Intensity (cd)	8	100	200	400

Notes:

1. Lights on curves to be toed-in 17 degrees with respect to the tangent of the curve.
2. See collective notes for Figures A2.12 to A2.21.


**Figure A2.19 Isocandela diagram for high-intensity taxiway center line (7.5 m spacing), no-entry bar and stop bar lights in curved sections intended for use in an advanced surface movement guidance and control system where higher light intensities are required**



Notes

1. Although the lights flash in normal operation, the light intensity is specified as if the lights were fixed for incandescent lamps.
2. See collective notes for Figures A2.12 to A 2.21.

**Figure A2.20 Isocandela diagram for high-intensity runway guard lights, Configuration B**



**Figure A2.21 Grid points to be used for calculation of average intensity of taxiway center line and stop bar light**

Collective notes to Figures 2.12 to 2.21

1. The intensities specified in Figures 2.12 to 2.20 are in green and yellow light for taxiway center line lights, yellow light for runway guard lights and red light for stop bar lights.
2. Figures 2.12 to 2.20 show the minimum allowable light intensities. The average intensity of the main beam is calculated by establishing grid points as shown in Figure 2.21 and using the intensity values measured at all grid points located within and on the perimeter of the rectangle representing the main beam. The average value is the arithmetic average of the light intensities measured at all considered grid points.
3. No deviations are acceptable in the main beam or in the innermost beam, as applicable, when the lighting fixture is properly aimed.
4. Horizontal angles are measured with respect to the vertical plane through the taxiway center line except on curves where they are measured with respect to the tangent to the curve.
5. Vertical angles are measured from the longitudinal slope of the taxiway surface.
6. The importance of adequate maintenance cannot be over-emphasized. The intensity, either average where applicable or as specified on the corresponding isocandela curves, should never fall to a value less than 50 per cent of the value shown in the figures and it should be the aim of airport authorities to maintain a level of light output close to the specified minimum average intensity.
7. The light unit shall be installed so that the main beam or the innermost beam, as applicable, is aligned within one-half degree of the specified requirement.






Figure A2-22. Light intensity distribution of T-VASIS and AT-VASIS



**GACA REGULATIONS - SECTION 14 - AERODROMES  
VOLUME I - AERODROME DESIGN AND OPERATIONS**

**APPENDIX 2. AERONAUTICAL GROUND LIGHT CHARACTERISTICS**




Note 1.— These curves are for minimum intensities in red light.

Note 2.— The intensity value in the white sector of the beam is no less than 2 and may be as high as 6.5 times the corresponding intensity in the red sector.

Note 3.— The intensity values shown in brackets are for APAPI.

**Figure A2-23. Light intensity distribution of PAPI and APAPI**




Notes:

1. Although the lights flash in normal operation, the light intensity is specified as if the lights were fixed or incandescent lamps.
2. The intensities specified are in yellow light.

**Figure 2.24 Isocandela diagram for each light in high-intensity runway guard lights, Configuration A**





Notes:


1. Although the lights flash in normal operation, the light intensity is specified as if the lights were fixed for incandescent lamps.
2. The intensities specified are in yellow light.

**Figure A2-25. Isocandela diagram for each light in high-intensity runway guard lights, Configuration A**


### **APPENDIX 3 - MANDATORY INSTRUCTION MARKINGS AND INFORMATION MARKINGS**

Note 1 — See Chapter 5, Sections 5.2.15 and 5.2.16 for specifications on the application, location and characteristics of mandatory instruction markings and information markings.


Note 2 — This appendix details the form and proportions of the letters, numbers and symbols of mandatory instruction markings and information markings on a 20 cm grid




**GACA REGULATIONS - SECTION 14 - AERODROMES**  
**VOLUME I - AERODROME DESIGN AND OPERATIONS**  
**APPENDIX 3. MANDATORY INSTRUCTION MARKINGS AND**  
**INFORMATION MARKINGS**




**GACA REGULATIONS - SECTION 14 - AERODROMES**  
**VOLUME I - AERODROME DESIGN AND OPERATIONS**  
**APPENDIX 3. MANDATORY INSTRUCTION MARKINGS AND**  
**INFORMATION MARKINGS**



**GACA REGULATIONS - SECTION 14 - AERODROMES**  
**VOLUME I - AERODROME DESIGN AND OPERATIONS**  
**APPENDIX 3. MANDATORY INSTRUCTION MARKINGS AND**  
**INFORMATION MARKINGS**




**GACA REGULATIONS - SECTION 14 - AERODROMES**  
**VOLUME I - AERODROME DESIGN AND OPERATIONS**  
**APPENDIX 3. MANDATORY INSTRUCTION MARKINGS AND**  
**INFORMATION MARKINGS**





**GACA REGULATIONS - SECTION 14 - AERODROMES**  
**VOLUME I - AERODROME DESIGN AND OPERATIONS**  
**APPENDIX 3. MANDATORY INSTRUCTION MARKINGS AND**  
**INFORMATION MARKINGS**



**APPENDIX 4. REQUIREMENTS CONCERNING DESIGN OF  
TAXIING GUIDANCE SIGNS**

**APPENDI 4. REQUIREMENTS  
CONCERNING DESIGN OF TAXIING  
GUIDANCE SIGNS**

Note. — See Chapter 5, Section 5.4 for specifications on the application, location and characteristics of signs.

1. Inscription heights shall conform to the following tabulation:

Runway code number	Minimum character height		
	Mandatory instruction sign	Information sign	
		Runway exit and runway vacated signs	Other signs
1 or 2	300 mm	300 mm	200 mm
3 or 4	400 mm	400 mm	300 mm

Note. — Where a taxiway location sign is installed in conjunction with a runway designation sign (see 5.4.3.22), the character size shall be that specified for mandatory instruction signs.

2. Arrow dimensions shall be as follows:

Legend height	Stroke
200 mm	32 mm
300 mm	48 mm
400 mm	64 mm

3. Stroke width for single letter shall be as follows:

Legend height	Stroke
200 mm	32 mm
300 mm	48 mm
400 mm	64 mm

4. Sign luminance shall be as follows:

- a) Where operations are conducted in runway visual range conditions less than a value of 800m, average sign luminance shall be at least:

Red	30 cd/m <sup>2</sup>
Yellow	150 cd/m <sup>2</sup>
White	300 cd/m <sup>2</sup>

- b) Where operations are conducted in accordance with 5.4.1.7 b) and c) and 5.4.1.8, average sign luminance shall be at least:

Red	10 cd/m <sup>2</sup>
Yellow	50 cd/m <sup>2</sup>
White	100 cd/m <sup>2</sup>

Note. — In runway visual range conditions less than a value of 400 m, there will be some degradation in the performance of signs.

5. The luminance ratio between red and white elements of a mandatory sign shall be between 1:5 and 1:10.

6. The average luminance of the sign is calculated by establishing grid points as shown in Figure 4.1 and using the luminance values measured at all grid points located within the rectangle representing the sign.

7. The average value is the arithmetic average of the luminance values measured at all considered grid points.

Note. — Guidance on measuring the average luminance of a sign is contained in the ICAO Aerodrome Design Manual, Part 4.

8. The ratio between luminance values of adjacent grid points shall not exceed 1.5:1. For areas on the sign face where the grid spacing is 7.5 cm, the ratio between luminance values of adjacent grid points shall not exceed 1.25:1. The ratio between the maximum and minimum luminance value over the whole sign face shall not exceed 5:1.

9. The forms of characters, i.e. letters, numbers, arrows and symbols, shall conform to those shown in Figure 4.2. The width of characters and the space between individual characters shall be determined as indicated in Table 4.1.

10. The face height of signs shall be as follows:

Legend height	Face height (min)
200 mm	400 mm
300 mm	600 mm
400 mm	800 mm

11. The face width of signs shall be determined using Figure 4.3 except that, where a mandatory instruction sign is provided on one side of a taxiway only, the face width shall not be less than:

- a) 1.94 m where the code number is 3 or 4; and  
b) 1.46 m where the code number is 1 or 2.


Note. — Additional guidance on determining the face width of a sign is contained in the ICAO Aerodrome Design Manual, Part 4.

12. Borders

- a) The black vertical delineator between adjacent direction signs should have a width of approximately 0.7 of the stroke width  
b) The yellow border on a stand-alone location sign should be approximately 0.5 stroke width.

APPENDIX 4. REQUIREMENTS CONCERNING DESIGN OF  
TAXIING GUIDANCE SIGNS

13. The colors of signs shall be in accordance with the appropriate specifications in Appendix 1.



**Figure A4-1. Grid points for calculating average luminance of a sign**

Note 1.— The average luminance of a sign is calculated by establishing grid points on a sign face showing typical inscriptions and a background of the appropriate color (red for mandatory instruction signs and yellow for direction and destination signs) as follows:

- Starting at the top left corner of the sign face, establish a reference grid point at 7.5 cm from the left edge and the top of the sign face.
- Create a grid of 15 cm spacing horizontally and vertically from the reference grid point. Grid points within 7.5 cm of the edge of the sign face shall be excluded.
- Where the last point in a row/column of grid points is located between 22.5 cm and 15 cm from the edge of the sign face (but not inclusive), an additional point shall be added 7.5 cm from this point.
- Where a grid point falls on the boundary of a character and the background, the grid point shall be slightly shifted to be completely outside the character.

Note 2.— Additional grid points may be required to ensure that each character includes at least five evenly spaced grid points.

Note 3.— Where one unit includes two types of signs, a separate grid shall be established for each type.




Figure A4-2. Forms of characters




Figure A4-2. (cont.)




Figure A4-2. (cont.)






Figure A4-2. (cont.)






Figure A4-2. (cont.)

APPENDIX 4. REQUIREMENTS CONCERNING DESIGN OF  
TAXIING GUIDANCE SIGNS



Runway vacated sign




Arrow, dot and dash

*Note 1.— The arrow stroke width, diameter of the dot, and both width and length of the dash shall be proportioned to the character stroke widths.*

*Note 2.— The dimensions of the arrow shall remain constant for a particular sign size, regardless of orientation.*

**APPENDIX 4. REQUIREMENTS CONCERNING DESIGN OF  
TAXIING GUIDANCE SIGNS**



**NO ENTRY sign**

Note. — Existing NO ENTRY signs not conforming to the above dimensions are to be replaced not later than 1 January 2012

**Figure A4-2. (cont.)**

**GACA REGULATIONS - SECTION 14 - AERODROMES  
VOLUME I – AERODROME DESIGN AND OPERATIONS**

**APPENDIX 4. REQUIREMENTS CONCERNING DESIGN OF  
TAXIING GUIDANCE SIGNS**

**Table A4-1. Letter and numeral widths and space between letters or numerals**

a) Letter to letter code number			
Preceding Letter	Following Letter		
	B, D, E, F, H, I, K, L, M, N, P, R, U	C, G, O, Q, S, X, Z	A, J, T, V, W, Y
	Code number		
A	2	2	4
B	1	2	2
C	2	2	3
D	1	2	2
E	2	2	3
F	2	2	3
G	1	2	2
H	1	1	2
I	1	1	2
J	1	1	2
K	2	2	3
L	2	2	4
M	1	1	2
N	1	1	2
O	1	2	2
P	1	2	2
Q	1	2	2
R	1	2	2
S	1	2	2
T	2	2	4
U	1	1	2
V	2	2	4
W	2	2	4
X	2	2	3
Y	2	2	4
Z	2	2	3

d) Width of letter			
Letter	Letter height (mm)		
	200	300	400
	Width (mm)		
A	170	255	340
B	137	205	274
C	137	205	274
D	137	205	274
E	124	186	248
F	124	186	248
G	137	205	274
H	137	205	274
I	32	48	64
J	127	190	254
K	140	210	280
L	124	186	248
M	157	236	314
N	137	205	274
O	143	214	286
P	137	205	274
Q	143	214	286
R	137	205	274
S	137	205	274
T	124	186	248
U	137	205	274
V	152	229	304
W	178	267	356
X	137	205	274
Y	171	257	342
Z	137	205	274

e) Width of numeral			
Letter	Numeral height (mm)		
	200	300	400
	Width (mm)		
1	50	74	98
2	137	205	274
3	137	205	274
4	149	224	298
5	137	205	274
6	137	205	274
7	137	205	274
8	137	205	274
9	137	205	274
0	143	214	286

b) Numeral to numeral code number			
Preceding Numeral	Following number		
	1, 5	2, 3, 6, 8, 9, 0	4, 7
	Code number		
1	1	1	2
2	1	2	2
3	1	2	2
4	2	2	4
5	1	2	2
6	1	2	2
7	2	2	4
8	1	2	2
9	1	2	2
0	1	2	2

c) Space between characters			
Code No.	Letter Height (mm)		
	200	300	400
	Space (mm)		
1	48	71	96
2	38	57	76
3	25	38	50
4	13	19	26

**INSTRUCTIONS**

1. To determine the proper SPACE between letters or numerals, obtain the code number from table a or b and enter table c for that code number to the desired letter or numeral height.
2. The space between words or groups of characters forming an abbreviation or symbol should be equal to 0.5 to 0.75 of the height of the characters used except that where an arrow is located with a single character such as 'A →', the space may be reduced to not less than one quarter of the height of the character in order to provide a good visual balance.
3. Where the numeral follows a letter or vice versa use Code 1.
4. Where a hyphen, dot, or diagonal stroke follows a character or vice versa use Code 1.





Figure A4-3. Sign dimensions





**APPENDIX 5 AERONAUTICAL DATA QUALITY REQUIREMENTS**

**Table A5-1 Latitude and longitude**

<b>Latitude and longitude</b>	<b>Accuracy Date type</b>	<b>Integrity Classification</b>
Aerodrome reference point	30 Surveyed / calculated	Routine
Nav aids located at the aerodrome	3 Surveyed / calculated	Essential
Obstacles in Area 3	0.5 Surveyed / calculated	Essential
Obstacles in Area 2 (the part within the aerodrome boundary)	5 Surveyed / calculated	Essential
Runway threshold	1 Surveyed / calculated	Critical
Runway end (flight path alignment point)	1 Surveyed / calculated	Critical
Runway centre line	1 Surveyed / calculated	Critical
Runway-holding position	0.5 Surveyed / calculated	Critical
Taxiway centre line / parking guidance line points	0.5 Surveyed / calculated	Essential
Taxiway intersection marking line	0.5 Surveyed / calculated	Essential
Exit guidance line	0.5 Surveyed / calculated	Essential
Apron boundaries (polygon)	1 Surveyed / calculated	Routine
De-icing / anti-icing facility (polygon)	1 Surveyed / calculated	Routine
Aircraft stand points/NS checkpoint	0.5 Surveyed / calculated	Routine

Note 1.— See GACA Regulation Section 15 and ICAO Annex 15, Appendix 8, for graphical illustrations of obstacle data collection surfaces and criteria used to identify obstacles in the defined areas.

**GACA REGULATIONS - SECTION 14 - AERODROMES  
VOLUME I – AERODROME DESIGN AND OPERATIONS**

**APPENDIX 5. AERONAUTICAL DATA QUALITY REQUIREMENTS**

**Table A5-2. Elevation/altitude/height**

<b>Latitude and longitude</b>	<b>Accuracy Date type</b>	<b>Integrity Classification</b>
Aerodrome elevation	0.5 Surveyed / calculated	Essential
WGS-84 geoid undulation at aerodrome elevation position	0.5 Surveyed / calculated	Essential
Runway threshold, non-precision approaches	0.5 Surveyed / calculated	Essential
WGS-84 geoid undulation at runway threshold, non-precision approaches	0.5 Surveyed / calculated	Essential
Runway threshold, precision approaches	0.25 Surveyed / calculated	Critical
WGS-84 geoid undulation at runway threshold, precision approaches	0.25 Surveyed / calculated	Critical
Runway centre line points	0.25 Surveyed / calculated	Critical
Taxiway centre line / parking guidance line points	1 Surveyed / calculated	Essential
Obstacle in Area 2 (the part within the aerodrome boundary)	3 Surveyed / calculated	Essential
Obstacle in Area 3	0.5 Surveyed / calculated	Essential
Distance measuring equipment / precision (DME/P)	3 Surveyed / calculated	Essential

Note 1.— See GACA Regulation Section 15 and ICAO Annex 15, Appendix 8, for graphical illustrations of obstacle data collection surfaces and criteria used to identify obstacles in the defined areas.

**Table A5-3. Declination and magnetic variation**


<b>Latitude and longitude</b>	<b>Accuracy Date type</b>	<b>Integrity Classification</b>
Aerodrome magnetic variation	1 Surveyed / calculated	Essential
ILS localizer antenna magnetic variation	1 Surveyed / calculated	Essential
MLS azimuth antenna magnetic variation	1 Surveyed / calculated	Essential

GACA REGULATIONS - SECTION 14 - AERODROMES  
VOLUME I – AERODROME DESIGN AND OPERATIONS

APPENDIX 5. AERONAUTICAL DATA QUALITY REQUIREMENTS

Table A5-4. Bearing

Latitude and longitude	Accuracy Date type	Integrity Classification
ILS localizer alignment	1/100 Surveyed / calculated	Essential
MLS zero azimuth alignment	1/100 Surveyed / calculated	Essential
Runway bearing (true)	1/100 Surveyed / calculated	Routine




**GACA REGULATIONS - SECTION 14 - AERODROMES  
VOLUME I – AERODROME DESIGN AND OPERATIONS**

**APPENDIX 5. AERONAUTICAL DATA QUALITY REQUIREMENTS**

**Table A5-5. Length/Distance/Dimension**


<b>Latitude and longitude</b>	<b>Accuracy Date type</b>	<b>Integrity Classification</b>
Runway Length	1 Surveyed	Critical
Runway Width	1 Surveyed	Essential
Displaced threshold distance	1 Surveyed	Routine
Stopway length and width	1 Surveyed	Critical
Clearway length and width	1 Surveyed	Essential
Landing distance available	1 Surveyed	Critical
Take-off run available	1 Surveyed	Critical
Take-off distance available	1 Surveyed	Critical
Accelerate-stop distance available	1 Surveyed	Critical
Runway shoulder width	1 Surveyed	Essential
Taxiway width	1 Surveyed	Essential
Taxiway shoulder width	1 Surveyed	Essential
ILS localizer antenna –runway end distance	3 calculated	Routine
ILS glide slope antenna threshold distance along center line	3 calculated	Routine
ILS marker threshold distance	3 calculated	Essential
ILS DME antenna threshold distance along center line	3 calculated	Essential
MLS azimuth antenna –runway end distance	3 calculated	Routine
MLS elevation antenna threshold distance along center line	3 calculated	Routine
MLS DME/P antenna threshold distance along center line	3 calculated	Essential

## APPENDIX 6. LOCATION OF LIGHTS ON OBSTACLES




Note.— High-intensity obstacle lighting is recommended on structures with a height of more than 150 m above ground level. If medium-intensity lighting is used, marking will also be required.

Figure A6-1. Medium-intensity flashing-white obstacle lighting system, Type A









Note.— For night-time use only.


Figure A6-2. Medium-intensity flashing-red obstacle lighting system, Type B





*Note.*— High-intensity obstacle lighting is recommended on structures with a height of more than 150 m above ground level. If medium-intensity lighting is used, marking will also be required.

**Figure A6-4. Medium-intensity dual obstacle lighting system, Type A/Type B**



Note.— High-intensity obstacle lighting is recommended on structures with a height of more than 150 m above ground level. If medium-intensity lighting is used, marking will also be required.

**Figure A6-5. Medium-intensity dual obstacle lighting system, Type A/Type C**





Figure A6-6. High-intensity flashing-white obstacle lighting system, Type A

**GACA REGULATIONS - SECTION 14 - AERODROMES**  
**VOLUME I - AERODROME DESIGN AND OPERATIONS**  
**APPENDIX 6. LOCATION OF LIGHTS ON OBSTACLES**



**Figure A6-7. High-/medium-intensity dual obstacle lighting system, Type A/Type B**






Figure A6-8. High-/medium-intensity dual obstacle lighting system, Type A/Type C

**ATTACHMENT A - GUIDANCE MATERIAL  
SUPPLEMENTARY TO SECTION 14, VOLUME I**

**1. Number, siting and orientation of runways**  
**Siting and orientation of runways**

**Siting and orientation of runways**

1.1 Many factors should be taken into account in the determination of the siting and orientation of runways. Without attempting to provide an exhaustive list of neither these factors nor an analysis of their effects, it appears useful to indicate those which most frequently require study. These factors may be classified under four headings:

1.1.1 Type of operation. Attention should be paid in particular to whether the aerodrome is to be used in all meteorological conditions or only in visual meteorological conditions, and whether it is intended for use by day and night, or only by day.

1.1.2 Climatological conditions. A study of the wind distribution should be made to determine the usability factor. In this regard, the following comments should be taken into account:

- a) Wind statistics used for the calculation of the usability factor are normally available in ranges of speed and direction, and the accuracy of the results obtained depends, to a large extent, on the assumed distribution of observations within these ranges. In the absence of any sure information as to the true distribution, it is usual to assume a uniform distribution since, in relation to the most favorable runway orientations; this generally results in a slightly conservative figure for the usability factor.
- b) The maximum mean cross-wind components given in Chapter 3, 3.1.2 refer to normal circumstances. There are some factors which may require that a reduction of those maximum values be taken into account at a particular aerodrome. These include:
  - 1) the wide variations which may exist, in handling characteristics and maximum permissible cross-wind components, among diverse types of aeroplanes (including future types) within each of the three groups given in 3.1.2;
  - 2) prevalence and nature of gusts;
  - 3) prevalence and nature of turbulence;
  - 4) the availability of a secondary runway;
  - 5) the width of runways;
  - 6) the runway surface conditions — water, snow and ice on the runway materially reduce the allowable crosswind component; and
  - 7) the strength of the wind associated with the limiting cross-wind component.

A study should also be made of the occurrence of poor visibility and/or low cloud base. Account should be taken of their frequency as well as the accompanying wind direction and speed.

1.1.3 Topography of the aerodrome site, its approaches, and surroundings, particularly:

- a) compliance with the obstacle limitation surfaces;
- b) current and future land use. The orientation and layout should be selected so as to protect as far as possible the particularly sensitive areas such as residential, school and hospital zones from the discomfort caused by aircraft noise;
- c) current and future runway lengths to be provided;
- d) construction costs; and
- e) possibility of installing suitable non-visual and visual aids for approach-to-land.

1.1.4 Air traffic in the vicinity of the aerodrome, particularly:

- a) proximity of other aerodromes or ATS routes;
- b) traffic density; and
- c) air traffic control and missed approach procedures.

**Number of runways in each direction**

1.2 The number of runways to be provided in each direction depends on the number of aircraft movements to be catered to.

**2. Clearways and stopways**

2.1 The decision to provide a stopway and/or a clearway as an alternative to an increased length of runway will depend on the physical characteristics of the area beyond the runway end, and on the operating performance requirements of the prospective aeroplanes. The runway, stopway and clearway lengths to be provided are determined by the aeroplane takeoff performance but a check should also be made of the landing distance required by the aeroplanes using the runway to ensure that adequate runway length is provided for landing. The length of a clearway, however, cannot exceed half the length of take-off run available.

2.2 The aeroplane performance operating limitations require a length which is enough to ensure that the aeroplane can, after starting a take-off, either be brought safely to a stop or complete the take-off safely. For the purpose of discussion it is supposed that the runway, stopway and clearway lengths provided at the aerodrome are only just adequate for the aeroplane requiring the longest take-off and accelerate-stop distances, taking into

account its take-off mass, runway characteristics and ambient atmospheric conditions. Under these circumstances there is, for each take-off, a speed, called the decision speed; below this speed, the take-off must be abandoned if an engine fails, while above it the take-off must be completed. A very long take-off run and take-off distance would be required to complete a take-off when an engine fails before the decision speed is reached, because of the insufficient speed and the reduced power available. There would be no difficulty in stopping in the remaining accelerate-stop distance available provided action is taken immediately. In these circumstances the correct course of action would be to abandon the take-off.

2.3 On the other hand, if an engine fails after the decision speed is reached; the aeroplane will have sufficient speed and power available to complete the take-off safely in the remaining takeoff distance available. However, because of the high speed, there would be difficulty in stopping the aeroplane in the remaining accelerate-stop distance available.

2.4 The decision speed is not a fixed speed for any aeroplane, but can be selected by the pilot within limits to suit the accelerate-stop and take-off distance available, aeroplane take-off mass, runway characteristics, and ambient atmospheric conditions at the aerodrome. Normally, a higher decision speed is selected as the accelerate-stop distance available increases.

2.5 A variety of combinations of accelerate-stop distances required and take-off distances required can be obtained to accommodate a particular aeroplane, taking into account the aeroplane take-off mass, runway characteristics, and ambient atmospheric conditions. Each combination requires its particular length of take-off run.

2.6 The most familiar case is where the decision speed is such that the take-off distance required is equal to the accelerate-stop distance required; this value is known as the balanced field length. Where stopway and clearway are not provided, these distances are both equal to the runway length.

However, if landing distance is for the moment ignored, runway is not essential for the whole of the balanced field length, as the take-off run required is, of course, less than the balanced field length. The balanced field length can, therefore, be provided by a runway supplemented by an equal length of clearway and stopway, instead of wholly as a runway. If the runway is used for take-off in both directions, an equal length of clearway and stopway has to be provided at each runway end. The saving in runway length is, therefore, bought at the cost of a greater over-all length.

2.7 In case economic considerations preclude the

provision of stopway and, as a result, only runway and clearway are to be provided, the runway length (neglecting landing requirements) should be equal to the accelerate-stop distance required or the take-off run required, whichever is the greater. The take-off distance available will be the length of the runway plus the length of clearway.

2.8 The minimum runway length and the maximum stopway or clearway length to be provided may be determined as follows, from the data in the aeroplane flight manual for the aeroplane considered to be critical from the viewpoint of runway length requirements:

- a) if a stopway is economically possible, the lengths to be provided are those for the balanced field length. The runway length is the take-off run required or the landing distance required, whichever is the greater. If the accelerate-stop distance required is greater than the runway length so determined, the excess may be provided as stopway, usually at each end of the runway. In addition, a clearway of the same length as the stopway must also be provided;
- b) if a stopway is not to be provided, the runway length is the landing distance required, or if it is greater, the accelerate-stop distance required, which corresponds to the lowest practical value of the decision speed. The excess of the take-off distance required over the runway length may be provided as clearway, usually at each end of the runway.

2.9 In addition to the above consideration, the concept of clearways in certain circumstances can be applied to a situation where the take-off distance required for all engines operating exceeds that required for the engine failure case.

2.10 The economy of a stopway can be entirely lost if, after each usage, it must be regraded and compacted. Therefore, it should be designed to withstand at least a certain number of loadings of the aeroplane which the stopway is intended to serve without inducing structural damage to the aeroplane.

### 3. Calculation of declared distances

3.1 The declared distances to be calculated for each runway direction comprise: the take-off run available (TORA), take-off distance available (TODA), accelerate-stop distance available (ASDA) and landing distance available (LDA).

3.2 Where a runway is not provided with a stopway or clearway and the threshold is located at the extremity of

the runway, the four declared distances should normally be equal to the length of the runway, as shown in Figure A-1 (A).

3.3 Where a runway is provided with a clearway (CWY), then the TODA will include the length of clearway, as shown in Figure A-1 (B).

3.4 Where a runway is provided with a stopway (SWY), then the ASDA will include the length of stopway, as shown in Figure A-1 (C).

3.5 Where a runway has a displaced threshold, then the LDA will be reduced by the distance the threshold is displaced, as shown in Figure A-1 (D). A displaced threshold affects only the LDA for approaches made to that threshold; all declared distances for operations in the reciprocal direction are unaffected.

3.6 Figures A-1 (B) through A-1 (D) illustrate a runway provided with a clearway or a stopway or having a displaced threshold. Where more than one of these features exist, then more than one of the declared distances will be modified — but the modification will follow the same principle illustrated. An example showing a situation where all these features exist is shown in Figure A-1 (E).

3.7 A suggested format for providing information on declared distances is given in Figure A-1 (F). If a runway direction cannot be used for take-off or landing, or both, because it is operationally forbidden, then this should be declared and the words “not usable” or the abbreviation “NU” entered.

#### 4. Slopes on a runway

4.1 The following example illustrates how the distance between slope changes is to be determined (see Figure A-2):

D for a runway where the code number is 3 should be at least:

$$15,000 (|x - y| + |y - z|) \text{ m}$$

$|x - y|$  being the absolute numerical value of  $x - y$

$|y - z|$  being the absolute numerical value of  $y - z$

Assuming  $x = +0.01$

$$y = -0.005$$

$$z = +0.005$$

$$\text{then } |x - y| = 0.015$$

$$|y - z| = 0.01$$

To comply with the specifications, D should be not less than:  $15,000 (0.015 + 0.01) \text{ m}$ ,

that is,  $15,000 \times 0.025 = 375 \text{ m}$

4.2 Consideration of longitudinal and transverse slopes  
When a runway is planned that will combine the extreme values for the slopes and changes in slope permitted under Chapter 3, 3.1.12 to 3.1.18, a study should be made to ensure that the resulting surface profile will not hamper the operation of aeroplanes.

4.3 Radio altimeter operating area In order to accommodate aeroplanes making auto-coupled approaches and automatic landings (irrespective of weather conditions) it is desirable that slope changes be avoided or kept to a minimum, on a rectangular area at least 300 m long before the threshold of a precision approach runway. The area should be symmetrical about the extended center line, 120 m wide. When special circumstances so warrant, the width may be reduced to no less than 60 m if an aeronautical study indicates that such reduction would not affect the safety of operations of aircraft. This is desirable because these aeroplanes are equipped with a radio altimeter for final height and flare guidance, and when the aeroplane is above the terrain immediately prior to the threshold, the radio altimeter will begin to provide information to the automatic pilot for autoflare. Where slope changes cannot be avoided, the rate of change between two consecutive slopes should not exceed 2 per cent per 30 m.

#### 5. Runway surface evenness

5.1 In adopting tolerances for runway surface irregularities, the following standard of construction is achievable for short distances of 3 m and conforms to good engineering practice:

Except across the crown of a camber or across drainage channels, the finished surface of the wearing course is to be of such regularity that, when tested with a 3 m straightedge placed anywhere in any direction on the surface, there is no deviation greater than 3 mm between the bottom of the straight-edge and the surface of the pavement anywhere along the straight edge.





Figure A-1. Illustration of declared distances



**Figure A-2. Profile on center line of runway**

5.2 Caution should also be exercised when inserting runway lights or drainage grilles in runway surfaces to ensure that adequate smoothness of the surface is maintained.

5.3 The operation of aircraft and differential settlement of surface foundations will eventually lead to increases in surface irregularities. Small deviations in the above tolerances will not seriously hamper aircraft operations. In general, isolated irregularities of the order of 2.5 cm to 3 cm over a 45 m distance are tolerable. Although maximum acceptable deviation cannot be given, as it varies with the type and speed of an aircraft, the limits of acceptable surface irregularities can be estimated to a reasonable extent. The following table describes maximum and temporarily acceptable limits. If the maximum limits are exceeded, corrective action should be undertaken as soon as reasonably practicable to improve the ride quality. If the temporarily acceptable limits are exceeded, the portions of the runway that exhibit such roughness should have corrective measures taken immediately if aircraft operations are to be continued.

5.4 The following figure illustrates a comparison of the surface roughness criteria with those developed by the United States Federal Aviation Administration

Surface Integrity	Minimum Acceptable Length of Irregularity (m)						
	3	6	9	12	15	20	30
Surface Irregularity Height (or Depth) (cm)	3	3.5	4	5	5.5	6	6.5
Temporary Acceptable Surface Irregularity Height (or Depth) (cm)	3.5	5.5	6.5	7.5	8	9	11



Note that “Surface Irregularity” is defined herein to mean isolated surface elevation deviations that do not lie along a uniform slope through any given section of a runway. For the purposes of this concern, a “section of a runway” is defined herein to mean a segment of a runway throughout which a continuing general uphill, downhill or flat slope is prevalent. The length of this section is generally between 30 and 60 metres, and can be greater, depending on the longitudinal profile and the condition of the pavement

## 6. Assessing the surface friction characteristics of snow, slush, ice and frost-covered paved surfaces

6.1 There is an operational need for reliable and uniform information concerning the surface condition of contaminated runways. Contaminant type, distribution and for loose contaminants, depth are assessed for each third of the runway. An indication of surface friction characteristics is helpful in conducting runway condition assessment. It can be obtained by friction measuring devices; however, there is no international consensus on the ability to correlate the results obtained by such equipment directly with aircraft performance. However, for contaminants such as slush, wet snow and wet ice, contaminant drag on the equipment’s measuring wheel, amongst other factors, may cause readings obtained in these conditions to be unreliable.

6.2. Any friction measuring device intended predict aircraft braking performance according to an agreed local or national procedure should be shown to correlate such performance in a manner acceptable to GACA. Information on the practice of one State providing correlation directly with aircraft braking performance can be found in the ICAO Circular 329 Runway Surface Condition Assessment, Measurement and Reporting. Appendix A.

6.3 The friction conditions of a runway can be assessed in descriptive terms of “estimated surface friction”. The estimated friction is categorized as good medium to good, medium, medium to poor, and poor, and promulgated in Annex 15, Appendix 2-SNOWTAM format as well as in PANS-ATM, Chapter 12.3-ATC phraseologies.

6.4 The table below with associated descriptive terms was developed from friction data collected only in compacted snow and ice and should not therefore be taken to be absolute values applicable in all conditions. If the surface is affected by snow or ice and the estimated surface friction is reported as “good”, pilots should not expect to find conditions as good as on a clean dry runway (where the available friction may well be greater than that needed in any case). The value “good” is a comparative value and is intended to mean that aeroplanes should not experience

directional control or braking difficulties, especially when landing. The figures in the “Measured Coefficient  $\mu$ ” column are given as an indication. At each aerodrome a specific table can be developed according to the measuring device used on the aerodrome and according to the standard and correlation criteria set or agreed by the State. The  $\mu$  values given will be specific to each friction measuring device as well as to the surface being measured and the speed employed.

<i>Measured coefficient <math>\mu</math></i>	<i>Estimated Surface friction</i>	<i>Code</i>
0.40 and above	Good	5
0.39 to 0.36	Medium to good	4
0.35 to 0.30	Medium	3
0.29 to 0.26	Medium to poor	2
0.25 and below	Poor	1

6.5. It has been elusive trying to relate braking action to friction measurements over the years. The main reason is that the industry to date has not achieved the ability to control the total uncertainty associated with the readings from these devices. Consequently, readings from a friction measuring device should only be used a part of an overall runway condition assessment. A major difference between the decelerometer type of devices and the other types is that when using the decelerometer type the operator is an integrated part of the measuring process. In addition to carrying out the measurement, the operator can feel the behavior of the vehicle where the decelerometer is installed and by that feel the deceleration process. This gives additional information in the total assessment process.

6.6 It has been found necessary to provide assessed surface condition information, including estimated surface friction for each third of a runway. The thirds are called A, B and C. For the purpose of reporting information to aeronautical service units, section A is always the section associated with the lower runway designation number. When giving landing information to a pilot before landing, the sections are however referred to as first, second or third part of the runway. The first part always means the first third of the runway as seen in the direction of landing. Assessments are made along two lines parallel to the runway, i.e. along a line on each side of the center line approximately 3 m, or that distance from the center line at which most operations take place. The objective of the assessment is to determine the type, depth and coverage of the contaminants and its effect on estimated surface friction given the prevailing weather conditions for sections A, B and C. In cases where a continuous friction measuring device is used, the mean values are


ATTACHMENT A

obtained from the friction values recorded for each section.

In cases where a spot measuring friction measuring device is used as part of the total assessment of estimated surface friction each third of the runway should have a minimum of three tests carried out on it where achievable. Information collected and assessed on the state of pavement surface is disseminated using forms prepared

by the State for SNOWTAM and NOTAM (Airport Services Manual (Doc 9137) Part 2).

6.7. The Airport Service Manual (Doc 9137), Part 2 provides guidance on the uniform use of test equipment and other information on removal of surface contamination and improvement of friction conditions.






Figure A-3: Comparison of Roughness Criteria

## 7. Determination of surface friction characteristics for construction and maintenance purposes.

The guidance in this section deals with the functional measurement of friction-related aspects related to runways construction and maintenance. Excluded in this section is the operational, as opposed to functional, measurement of friction for contamination runways. However, the devices used for functional measurement could also be used for operational measurement, but in the latter case, the figures given in Airport Services Manual (Doc 9137), Part 2, Table 3-1 are not relevant.

7.1 The surface friction characteristics of a paved runway should be:

- a) assessed to verify the surface friction characteristics of new or resurfaced paved runways (Chapter 3, 3.1.23);
- b) assessed periodically in order to determine the slipperiness of paved runways when wet (Chapter 10, 10.24);

7.2 The condition of a runway pavement is generally assessed under dry conditions using a self wetting continuous friction measuring device. Evaluation tests of runway surface friction characteristics are made on clean surfaces of the runway when first constructed or after resurfacing.

7.3 Friction tests of existing surface conditions are taken periodically in order to avoid falling below the minimum friction level specified by GACA. When the friction of any portion of a runway is found to be below this value, then such information is promulgated in a NOTAM specifying which portion of the runway is below the minimum friction level, and its location on the runway. A corrective maintenance action must be initiated without delay. Friction measurements are taken at time intervals that will ensure identification of runways in need of maintenance or special surface treatment before their condition becomes serious. The time intervals and mean frequency of measurements depend on factors such as: aircraft type and frequency of usage, climatic conditions, pavement type, and pavement service and maintenance requirements.

7.4 Friction measurements of existing, new or resurfaced runways are made with a continuous friction measuring device provided with a smooth tread tire. The device should use self-wetting features to allow measurements of the friction characteristics to be made at a water depth of 1 mm.

7.5 When it is suspected that the friction characteristics of

a runway may be reduced because of poor drainage, owing to inadequate slopes or depressions, then an additional measurement is made, but this time under natural conditions representative of a local rain. This measurement differs from the previous one in that water depths in the poorly cleared areas are normally greater in a local rain condition. The measurement results are thus more apt to identify problem areas having low friction values that could induce aquaplaning than the previous measurement. If circumstances do not permit tests to be conducted during natural conditions representative of a rain, then this condition may be simulated. (See Section 8).

7.6 When conducting friction tests using a self wetting continuous friction measuring device, it is important to note that, unlike compacted snow and ice conditions, in which there is very limited variation of the friction coefficient with speed, a wet runway produces a drop in friction with an increase in speed. However, as the speed increases, the rate at which the friction is reduced becomes less. Among the factors affecting the friction coefficient between the tire and the runway surface, texture is particularly important. If the runway has a good macro-texture allowing the water to escape beneath the tire, then the friction value will be less affected by speed. Conversely, a low macro-texture surface will produce a larger drop in friction with increase in speed.

7.7 GACA Regulation Section 14 and ICAO Annex 14, Volume I requires the GACA to specify taken. As criteria for surface friction characteristics of new or resurfaced runway surfaces and its maintenance planning, GACA can establish a maintenance planning level below which appropriate corrective maintenance action should be initiated to improve the friction. The Airport Services Manual (Doc 9137), Part 2 provides guidances on establishing maintenance and minimum friction levels for runways surfaces in use.

## 8. Drainage characteristics of the movement area and adjacent areas

### 8.1. General

8.1.1. Rapid drainage of surface water is a primary safety consideration in the design, construction and maintenance of movement area and adjacent areas. The objective is to minimize water depth on the surface by draining water off the runway in the shortest path possible and particularly out of the area of the wheel path. There are two distinct drainage processes taking in place:

- a. natural drainage of the surface water from the top of the pavement surface until it reaches the final recipient such as rivers or other water bodies; and

- b. dynamic drainage of the surface water trapped under a moving tire it reaches outside the tire-to-ground contact area.

8.1.2 Both processes can be controlled through:

- a. design
- b. construction; and
- c. maintenance

of the pavements in order to prevent accumulation of water on the pavement surface.

## **8.2 Design of pavement.**

8.2.1 Surface drainage is a basic requirement and serves to minimize water depth on the surface. The objective is to drain water off the runway in the shortest path. Adequate surface drainage is provided primarily by an appropriately sloped surface (in both the longitudinal and transverse direction). The resulting combined longitudinal and transverse slope is the path for drainage runoff. This path can be shortened by adding transverse grooves.

8.2.2 Dynamic drainage is achieved through built-in texture in the pavement surface. The rolling tire builds up water pressure and squeezes the water out the escape channels provided by the texture. The dynamic drainage of the tire-to-ground contact area may be improved by adding transverse grooves provided that they are subject to rigorous maintenance.

## **8.3 Construction of pavement.**

8.3.1 Through construction, the drainage characteristics of the surface are built into pavement. The surface characteristics are:

- a. Slope;
- b. Texture
  - i. Microtexture;
  - ii. Macrotexture;

8.3.2 Slopes for the various parts of the movement area and adjacent parts are described in GACAR Section 14, Volume 1, Chapter 3 and figures are given as per cent. Further guidance is given in Aerodrome Design Manual, Part 1, Runways, Chapter 5.

8.3.3 Texture in the literature is described as microtexture or macrotexture. These terms are understood differently in various parts of the aviation industry.

8.3.4 Microtexture is the texture of the individual stones and is hardly detectable by the eye. Microtexture is considered a primary component in skid resistance at slow speeds. On a wet surface at higher speeds a water film may prevent direct contact between the surface asperities and the tire due to insufficient drainage from the tire-to-ground contact area.

8.3.5 Microtexture is a built-in quality of the pavement surface. By specifying crushed material that will withstand polishing microtexture, drainage of thin water films are ensured for a longer period of time. Resistance against polishing is expressed in terms of the Polished Stone Values (PSV) which is in principle a value obtained from a friction measurement in accordance with international standards. These standards define the PSV minima that will enable a material with a good microtexture to be selected.

8.3.6 A major problem with microtexture is that it can change within short time periods without being easily detected. A typical example of this is the accumulation of rubber deposits in the touchdown area which will largely mask microtexture without necessarily reducing macrotexture.

8.3.7 Macrotexture is the texture among the individual stones. This scale of texture may be judged approximately by the eye. Macrotexture is primarily created by the size of aggregate used or by surface treatment of the pavement and is the major factor influencing drainage capacity at high speeds. Materials shall be selected so as to achieve good macrotexture.

8.3.8 The primary purpose of grooving a runway surface is to enhance drainage. Natural drainage can be slowed down by surface texture, but grooving can speed up the drainage by providing a shorter drainage path and increasing the drainage rate.

8.3.9 For measurement of macrotexture, simple methods such as the “sand and grease patch” – methods described in the Airport Services Manual (Doc 9137), Part 2 were developed. These methods were used for the early research on which current airworthiness requirements are based upon, which refers to a classification categorizing macrotexture from A to E. This classification was developed, using sand or grease patch measuring techniques, and issued in 1971 by the Engineering Sciences Data Unit (ESDU).

Runway classification based on texture information from ESDU 71026:

Classification	Texture depth (mm)
A	0.10 – 0.14
B	0.15 – 0.24
C	0.25 – 0.50
D	0.51 – 1.00
E	1.01 – 2.54



8.3.10 Using this classification the threshold value between microtexture and macrotexture is 0.1 mm mean texture depth (MTD). Related to this scale the normal wet runway aircraft performance is based upon texture giving drainage and friction qualities midway between classification B and C (0.25). Improved drainage through better texture might qualify for a better aircraft performance class. However, such credit must be in accordance with aeroplane manufacturers documentation and agreed by GACA. Presently credit is given to grooved or porous friction course runways following design, construction and maintenance criteria acceptable to the GACA. The harmonized certification standards of some States refer to texture giving drainage and friction qualities midway between classification D and E (1.0mm).

8.3.11 For construction, design and maintenance, States use various international Standards. Currently *ISO 13473-1: Characterization of pavement texture by use of surface profiles – Part 1: Determination of Mean Profile Depth* links the volumetric measuring technique with non contact profile measuring techniques giving comparable texture values. These standards describe the threshold value between microtexture and macrotexture as 0.5mm. The volumetric method has a validity range from 0.25 to 5 mm MTD. The profilometry method has a validity range 0 to 5 mm mean profile depth (MTD). The values of MPD and MTD differ due to the finite size of the glass spheres used in the volumetric technique and because the MPD is derived from two-dimensional profile rather than a three-dimensional surface. Therefore a transformation equation must be established for the measuring equipment used to relate MPD and MTD.

8.3.12 The ESDU scale groups runway surface based on macro texture from A through E, where E represent the surface with best dynamic drainage capacity. The ESDU scale thus reflects the dynamic drainage characteristics of the pavement. Grooving any of these surfaces enhances the dynamic drainage capacity. The resulting drainage capacity of the surface is thus a function of texture (A through E) and grooving. The contribution from grooving is a function of the size of the grooves and the spacing between the grooves. Aerodromes exposed to heavy or torrential rainfall must ensure that the pavement and adjacent areas have drainage capability to withstand these rainfalls or put limitations on the use of the pavements under such extreme situations. These airports should seek to have the maximum allowable slopes and the use of aggregates providing good drainage characteristics. They should also consider grooved pavements in the E classification to ensure that safety is not impaired.

#### **8.4 Maintenance of drainage characteristics of pavement**

8.4.1 Macrotexture does not change within a short timespan but accumulation of rubber can fill up the texture and as such reduce the drainage capacity, which can result in impaired safety. Furthermore the runway structure may change over time and give unevenness which results in ponding after rainfall. Guidance on rubber removal and unevenness can be found in Airport Service Manual (Doc 9137), Part 2. Guidance on methods for improving surface texture can be found in Aerodrome Design Manual (Doc 9157), Part 3.

8.4.2 When grooving are used, the condition of the grooves should be regularly inspected to ensure that no deterioration has occurred and that the grooves are in good condition. Guidance on maintenance of pavement is available in Doc 9137, Airport Services Manual, Part 2 – Pavement Surface Conditions and Part 9 – Airport Maintenance Practices and Doc 9157, Part 2.

8.4.3 The pavement may be short blasted in order to enhance the pavement macrotexture.

### **9. Strips**

#### **9.1 Shoulders**

8.1.1 The shoulder of a runway or stopway should be prepared or constructed so as to minimize any hazard to an aeroplane running off the runway or stopway. Some guidance is given in the following paragraphs on certain special problems which may arise, and on the further question of measures to avoid the ingestion of loose stones or other objects by turbine engines.

9.1.2 In some cases, the bearing strength of the natural ground in the strip may be sufficient, without special preparation, to meet the requirements for shoulders. Where special preparation is necessary, the method used will depend on local soil conditions and the mass of the aeroplanes the runway is intended to serve. Soil tests will help in determining the best method of improvement (e.g. drainage, stabilization, surfacing, lighting, paving).

9.1.3 Attention should also be paid when designing shoulders to prevent the ingestion of stones or other objects by turbine engines. Similar considerations apply here to those which are discussed for the margins of taxiways in the ICAO Aerodrome Design Manual, Part 2, both as to the special measures which may be necessary and as to the distance over which such special measures, if required, should be taken.

9.1.4 Where shoulders have been treated specially, either to provide the required bearing strength or to prevent the presence of stones or debris, difficulties may arise because of a lack of visual contrast between the runway



ATTACHMENT A

surface and that of the adjacent strip. This difficulty can be overcome either by providing a good visual contrast in the surfacing of the runway or strip, or by providing a runway side stripe marking.

### 9.2 Objects on strips

within the general area of the strip adjacent to the runway, measures should be taken to prevent an airplane's wheel, when sinking into the ground, from striking a hard vertical face. Special problems may arise for runway light fittings or other objects mounted in the strip or at the intersection with a taxiway or another runway. In the case of construction, such as runways or taxiways, where the surface must also be flush with the strip surface, a vertical face can be eliminated by chamfering from the top of the construction to not less than 30 cm below the strip surface level. Other objects, the functions of which do not require them to be at surface level, should be buried to a depth of not less than 30 cm.

### 9.3 Grading of a strip for precision approach runways

Chapter 3, 3.3.8 recommends that the portion of a strip of an instrument runway within at least 75 m from the center line should be graded where the code number is 3 or 4. For a precision approach runway, it may be desirable to adopt a greater width where the code number is 3 or 4. Figure A-3 shows the shape and dimensions of a wider strip that may be considered for such a runway. This strip has been designed using information on aircraft running off runways. The portion to be graded extends to a distance of 105 m from the center line, except that the distance is gradually reduced to 75 m from the center line at both ends of the strip, for a length of 150 m from the runway end.

## 10. Runway end safety areas

10.1 Where a runway end safety area is provided in accordance with Chapter 3, consideration should be given to providing an area long enough to contain overruns and undershoots resulting from a reasonably probable combination of adverse operational factors. On a precision approach runway, the ILS localizer is normally

the first upstanding obstacle, and the runway end safety area should extend up to this facility. In other circumstances the first upstanding obstacle may be a road, a railroad or other constructed or natural feature. The provision of a runway end safety area should take such obstacle into consideration.

10.2 Where provision of a runway end safety area would be particularly prohibitive to implement, consideration would have to be given to reducing some of the declared distances of the runway for the provision of a runway end safety area and installation of an arresting system.

10.3 Research programs, as well as evaluation of actual aircraft overruns into arresting systems, have demonstrated that the performance of some arresting systems can be predictable and effective in arresting aircraft overruns.

10.4 Demonstrated performance of an arresting system can be achieved by a validated design method, which can predict the performance of the system. The design and performance should be based on the type of aircraft anticipated to use the associated runway that imposes the greatest demand upon the arresting system.

10.5 The design of an arresting system must consider multiple aircraft parameters, including but not limited to, allowable aircraft gear loads, gear configuration, tire contact pressure, aircraft center of gravity and aircraft speed. Accommodating undershoots must also be addressed. Additionally, the design must allow the safe operation of fully loaded and fire fighting vehicles, including their ingress and egress.

10.6 The information relating to the provision of a runway end safety area and the presence of an arresting system should be published in the AIP.

10.7 Additional information is contained in the Aerodrome Design Manual (Doc 9157), Part 1.




Figure A-3. Graded portion of a strip including a precision approach runway where the code number is 3 or 4

## 11. Location of threshold

### 11.1 General

10.1.1 The threshold is normally located at the extremity of a runway, if there are no obstacles penetrating above the approach surface. In some cases, however, due to local conditions it may be desirable to displace the threshold permanently (see below). When studying the location of a threshold, consideration should also be given to the height of the ILS reference datum and/or MLS approach reference datum and the determination of the obstacle clearance limits. (Specifications concerning the height of the ILS reference datum and MLS approach reference datum are given in GACA Regulation Section – 10 and ICAO Annex 10, Volume I, Part I.)

11.1.2 In determining that no obstacle penetrate above the approach surface, account should be taken of mobile objects (vehicles on roads, trains, etc.) at least within that portion of the approach area within 1 200 m longitudinally from the threshold and of an over-all width of not less than 150 m.

### 11.2 Displaced threshold

10.2.1 If an object extends above the approach surface and the object cannot be removed, consideration should be given to displacing the threshold permanently.

11.2.2 To meet the obstacle limitation objectives of Chapter 4, the threshold should ideally be displaced down the runway for the distance necessary to provide that the approach surface is cleared of obstacles.

11.2.3 However, displacement of the threshold from the runway extremity will inevitably cause reduction of the landing distance available, and this may be of greater operational significance than penetration of the approach surface by marked and lighted obstacles. A decision to displace the threshold, and the extent of such displacement, should therefore have regard to an optimum

balance between the considerations of clear approach surfaces and adequate landing distance. In deciding this question, account will need to be taken of the types of aeroplanes which the runway is intended to serve, the limiting visibility and cloud base conditions under which the runway will be used, the position of the obstacles in relation to the threshold and extended center line and, in the case of a precision approach runway, the significance of the obstacles to the determination of the obstacle clearance limit.

1.2.4 Notwithstanding the consideration of landing distance available, the selected position for the threshold should not be such that the obstacle-free surface to the threshold is steeper than 3.3 per cent where the code number is 4 or steeper than 5 per cent where the code number is 3.

11.2.5 In the event of a threshold being located according to the criteria for obstacle-free surfaces in the preceding paragraph, the obstacle marking requirements of Chapter 6 should continue to be met in relation to the displaced threshold.

11.2.6 Depending on the length of the displacement, the RVR at the threshold could differ from that at the beginning of the runway for take-offs. The use of red runway edge lights with photometric intensities lower than the nominal value of 10 000 cd for white lights increases that phenomenon. The impact of a displaced threshold on take-off minima should be assessed by the appropriate authority.

11.2.7 Provisions in Annex 14, Volume I, regarding marking and lighting of displaced thresholds and some operational recommendations can be found in paragraphs 5.2.4.9 and 10, 5.3.5.5, 5.3.8.1, 5.3.9.7, 5.3.10.3 and 7, and 5.3.12.6

## 12. Approach lighting systems

### 12.1 Types and characteristics

11.1.1 The specifications in this volume provide for the basic characteristics for simple and precision approach lighting systems. For certain aspects of these systems, some latitude is permitted, for example, in the spacing between center line lights and crossbars. The approach lighting patterns that have been generally adopted are shown in Figures A-5 and A-6. A diagram of the inner 300 m of the precision approach category II and III lighting system is shown in Figure 5-13.

12.1.2 The approach lighting configuration is to be provided irrespective of the location of the threshold, i.e. whether the threshold is at the extremity of the runway or displaced from the runway extremity. In both cases, the approach lighting system should extend up to the threshold.

However, in the case of a displaced threshold, inset lights are used from the runway extremity up to the threshold to obtain the specified configuration. These inset lights are designed to satisfy the structural requirements specified in Chapter 5, 5.3.1.9, and the photometric requirements specified in Appendix 2, Figure 2.1 or 2.2.

12.1.3 Flight path envelopes to be used in designing the lighting are shown in Figure A-4.

12.2 Installation tolerances

#### Horizontal

12.2.1 The dimensional tolerances are shown in Figure A-6.

12.2.2 The center line of an approach lighting system should be as coincident as possible with the extended center line of the runway with a maximum tolerance of  $\pm 15$ .

12.2.3 The longitudinal spacing of the center line lights should be such that one light (or group of lights) is located in the center of each crossbar, and the intervening center line lights are spaced as evenly as practicable between two crossbars or a crossbar and a threshold.

12.2.4 The crossbars and barrettes should be at right angles to the center line of the approach lighting system with a tolerance of  $\pm 30'$ , if the pattern in Figure A-6 (A) is adopted or  $\pm 2^\circ$ , if Figure A-6 (B) is adopted.

12.2.5 When a crossbar has to be displaced from its standard position, any adjacent crossbar should, where

possible, be displaced by appropriate amounts in order to reduce the differences in the crossbar spacing.

12.2.6 When a crossbar in the system shown in Figure A-6 (A) is displaced from its standard position, its overall length should be adjusted so that it remains one-twentieth of the actual distance of the crossbar from the point of origin. It is not necessary, however, to adjust the standard 2.7 m spacing between the crossbar lights, but the crossbars should be kept symmetrical about the center line of the approach lighting.

#### Vertical

12.2.7 The ideal arrangement is to mount all the approach lights in the horizontal plane passing through the threshold (see Figure A-7), and this should be the general aim as far as local conditions permit. However, buildings, trees, etc., should not obscure the lights from the view of a pilot who is assumed to be  $1^\circ$  below the electronic glide path in the vicinity of the outer marker.

12.2.8 Within a stopway or clearway, and within 150 m of the end of a runway, the lights should be mounted as near to the ground as local conditions permit in order to minimize risk of damage to aeroplanes in the event of an overrun or undershoot. Beyond the stopway and clearway, it is not so necessary for the lights to be mounted close to the ground and therefore undulations in the ground contours can be compensated for by mounting the lights on poles of appropriate height.

12.2.9 It is desirable that the lights be mounted so that, as far as possible, no object within a distance of 60 m on each side of the center line protrudes through the plane of the approach lighting system. Where a tall object exists within 60 m of the center line and within 1 350 m from the threshold for a precision approach lighting system, or 900 m for a simple approach lighting system, it may be advisable to install the lights so that the plane of the outer half of the pattern clears the top of the object.





Figure A-4. Flight path envelopes to be used for lighting design  
for category I, II and III operations



**Figure A-5 Runway end safety area for a runway where the code number is 3 or 4**




Figure A-6. Simple approach lighting systems






Figure A-7. Precision approach category I lighting systems




Figure A-8. Vertical installation tolerances

12.2.10 In order to avoid giving a misleading impression of the plane of the ground, the lights should not be mounted below a gradient of 1 in 66 downwards from the threshold to a point 300 m out, and below a gradient of 1 in 40 beyond the 300 m point. For a precision approach category II and III lighting system, more stringent criteria may be necessary, e.g. negative slopes not permitted within 450 m of the threshold.

#### 12.2.11 Center line

The gradients of the center line in any section (including a stopway or clearway) should be as small as practicable, and the changes in gradients should be as few and small as can be arranged and should not exceed 1 in 60. Experience has shown that as one proceeds outwards from the runway, rising gradients in any section of up to 1 in 66, and falling gradients of down to 1 in 40, are acceptable.

#### 12.2.12 Crossbars

The crossbar lights should be so arranged as to lie on a straight line passing through the associated center line lights, and wherever possible this line should be horizontal. It is permissible, however, to mount the lights on a transverse gradient not more than 1 in 80, if this enables crossbar lights within a stopway or clearway to be mounted nearer to the ground on sites where there is a crossfall.

#### 12.3 Clearance of obstacles

12.3.1 An area, hereinafter referred to as the light plane, has been established for obstacle clearance purposes, and all lights of the system are in this plane. This plane is rectangular in shape and symmetrically located about the approach lighting system's center line. It starts at the threshold and extends 60 m beyond the approach end of the system, and is 120 m wide.

12.3.2 No objects are permitted to exist within the boundaries of the light plane which are higher than the light plane except as designated herein. All roads and highways are considered as obstacles extending 4.8 m above the crown of the road, except aerodrome service roads where all vehicular traffic is under control of the aerodrome authorities and coordinated with the aerodrome traffic control tower. Railroads, regardless of the amount of traffic, are considered as obstacles extending 5.4 m above the top of the rails.

12.3.3 It is recognized that some components of electronic landing aids systems, such as reflectors, antennas, monitors, etc., must be installed above the light plane. Every effort should be made to relocate such components outside the boundaries of the light plane. In the case of reflectors and monitors, this can be done in many instances.

12.3.4 Where an ILS localizer is installed within the light plane boundaries, it is recognized that the localizer, or screen if used, must extend above the light plane. In such cases the height of these structures should be held to a minimum and they should be located as far from the threshold as possible. In general the rule regarding permissible heights is 15 cm for each 30 m the structure is located from the threshold. As an example, if the localizer is located 300 m from the threshold, the screen will be permitted to extend above the plane of the approach lighting system by  $10 \square \square 15 = 150$  cm maximum, but preferably should be kept as low as possible consistent with proper operation of the ILS.

12.3.5 In locating an MLS azimuth antenna the guidance contained in GACA Regulation Section 15 and ICAO Annex 15, Volume I, Attachment G to Part I should be followed. This material, which also provides guidance on co-locating an MLS azimuth antenna with an ILS localizer antenna, suggests that the MLS azimuth antenna may be sited within the light plane boundaries where it is not possible or practical to locate it beyond the outer end of the approach lighting for the opposite direction of approach. If the MLS azimuth antenna is located on the extended center line of the runway, it should be as far as possible from the closest light position to the MLS azimuth antenna in the direction of the runway end. Furthermore, the MLS azimuth antenna phase center should be at least 0.3 m above the light center of the light position closest to the MLS azimuth antenna in the direction of the runway end. (This could be relaxed to 0.15 m if the site is otherwise free of significant multipath problems.)

Compliance with this requirement, which is intended to ensure that the MLS signal quality is not affected by the approach lighting system, could result in the partial obstruction of the lighting system by the MLS azimuth antenna. To ensure that the resulting obstruction does not degrade visual guidance beyond an acceptable level, the MLS azimuth antenna should not be located closer to the runway end than 300 m and the preferred location is 25 m beyond the 300 m crossbar (this would place the antenna 5 m behind the light position 330 m from the runway end). Where an MLS azimuth antenna is so located, a central part of the 300 m crossbar of the approach lighting system would alone be partially obstructed. Nevertheless, it is important to ensure that the unobstructed lights of the crossbar remain serviceable all the time.

12.3.6 Objects existing within the boundaries of the light plane, requiring the light plane to be raised in order to meet the criteria contained herein, should be removed, lowered or relocated where this can be accomplished more economically than raising the light plane.

12.3.7 In some instances objects may exist which cannot be removed, lowered or relocated economically. These objects may be located so close to the threshold that they cannot be cleared by the 2 per cent slope. Where such conditions exist and no alternative is possible, the 2 per cent slope may be exceeded or a “stair step” resorted to in order to keep the approach lights above the objects. Such “step” or increased gradients should be resorted to only when it is impracticable to follow standard slope criteria, and they should be held to the absolute minimum. Under this criterion no negative slope is permitted in the outermost portion of the system.

#### 12.4 Consideration of the effects of reduced lengths

12.4.1 The need for an adequate approach lighting system to support precision approaches where the pilot is required to acquire visual references prior to landing, cannot be stressed too strongly. The safety and regularity of such operations is dependent on this visual acquisition. The height above runway threshold at which the pilot decides there are sufficient visual cues to continue the precision approach and land will vary, depending on the type of approach being conducted and other factors such as meteorological conditions, ground and airborne equipment, etc. The required length of approach lighting system which will support all the variations of such approaches is 900 m, and this shall always be provided whenever possible

12.4.2 However, there are some runway locations where it is impossible to provide the 900 m length of approach lighting system to support precision approaches.

12.4.3 In such cases, every effort should be made to provide as much approach lighting system as possible. The appropriate authority may impose restrictions on operations to runways equipped with reduced lengths of lighting. There are many factors which determine at what height the pilot must have decided to continue the approach to land or execute a missed approach. It must be understood that the pilot does not make an instantaneous judgment upon reaching a specified height. The actual decision to continue the approach and landing sequence is an accumulative process which is only concluded at the specified height. Unless lights are available prior to reaching the decision point, the visual assessment process is impaired and the likelihood of missed approaches will increase substantially. There are many operational considerations which must be taken into account by the appropriate authorities in deciding if any restrictions are necessary to any precision approach and these are detailed in GACA Regulation Section 6 and ICAO Annex 6.

### 13. Priority of installation of visual approach slope indicator systems

13.1 It has been found impracticable to develop guidance material that will permit a completely objective analysis to be made of which runway on an aerodrome should receive first priority for the installation of a visual approach slope indicator system. However, factors that must be considered when making such a decision are:

- a) frequency of use;
- b) seriousness of the hazard;
- c) presence of other visual and non-visual aids;
- d) type of aeroplanes using the runway; and
- e) frequency and type of adverse weather conditions under which the runway will be used.

13.2 With respect to the seriousness of the hazard, the order given in the application specifications for a visual approach slope indicator system, 5.3.5.1 b) to e) of Chapter 5 may be used as a general guide. These may be summarized as:

- a. inadequate visual guidance because of:
  1. approaches over water or featureless terrain, or absence of sufficient extraneous light in the approach area by night;
  2. deceptive surrounding terrain;
- b. serious hazard in approach;
- c. serious hazard if aeroplanes undershoot or overrun; and
- d. unusual turbulence.

13.3 The presence of other visual or non-visual aids is a very important factor. Runways equipped with ILS or MLS would generally receive the lowest priority for a visual approach slope indicator system installation. It must be remembered, though, that visual approach slope indicator systems are visual approach aids in their own right and can supplement electronic aids. When serious hazards exist and/or a substantial number of aeroplanes not equipped for ILS or MLS use a runway, priority might be given to installing a visual approach slope indicator on this runway.

13.4 Priority should be given to runways used by turbojet aeroplanes.

### 14. Lighting of unserviceable areas

14.1 Where a temporarily unserviceable area exists, it may be marked with fixed-red lights. These lights should mark the most potentially dangerous extremities of the area. A minimum of four such lights should be used,

except where the area is triangular in shape where a minimum of three lights may be employed. The number of lights should be increased when the area is large or of unusual configuration. At least one light should be installed for each 7.5 m of peripheral distance of the area. If the lights are directional, they should be orientated so that as far as possible their beams are aligned in the direction from which aircraft or vehicles will approach.

Where aircraft or vehicles will normally approach from several directions, consideration should be given to adding extra lights or using omnidirectional lights to show the area from these directions. Unserviceable area lights should be frangible. Their height should be sufficiently low to preserve clearance for propellers and for engine pods of jet aircraft.

### 15. Rapid exit taxiway indicator lights

15.1 Rapid exit taxiway indicator lights (RETILs) comprise a set of yellow unidirectional lights installed in the runway adjacent to the center line. The lights are positioned in a 3-2-1 sequence at 100 m intervals prior to the point of tangency of the rapid exit taxiway center line. They are intended to give an indication to pilots of the location of the next available rapid exit taxiway.

15.2 In low visibility conditions, RETILs provide useful situational awareness cues while allowing the pilot to concentrate on keeping the aircraft on the runway center line.

15.3 Following a landing, runway occupancy time has a significant effect on achievable runway capacity. RETILs allow pilots to maintain a good roll-out speed until it is necessary to decelerate to an appropriate speed for the turn into a rapid exit turn-off. A roll-out speed of 60 knots until the first RETIL (three-light barrette) is reached is seen as the optimum.

### 16. Intensity control of approach and runway lights

16.1 The conspicuity of a light depends on the impression received of contrast between the light and its background. If a light is to be useful to a pilot by day when on approach, it must have an intensity of at least 2 000 or 3 000 cd, and in the case of approach lights an intensity of the order of 20 000 cd is desirable. In conditions of very bright daylight fog it may not be possible to provide lights of sufficient intensity to be effective

On the other hand, in clear weather on a dark night, an intensity of the order of 100 cd for approach lights and 50 cd for the runway edge lights may be found suitable. Even then, owing to the closer range at which they are viewed,

pilots have sometimes complained that the runway edge lights seemed unduly bright.

16.2 In fog the amount of light scattered is high. At night this scattered light increases the brightness of the fog over the approach area and runway to the extent that little increase in the visual range of the lights can be obtained by increasing their intensity beyond 2 000 or 3 000 cd. In an endeavour to increase the range at which lights would first be sighted at night, their intensity must not be raised to an extent that a pilot might find excessively dazzling at diminished range.

16.3 From the foregoing will be evident the importance of adjusting the intensity of the lights of an aerodrome lighting system according to the prevailing conditions, so as to obtain the best results without excessive dazzle that would disconcert the pilot. The appropriate intensity setting on any particular occasion will depend both on the conditions of background brightness and the visibility. Detailed guidance material on selecting intensity setting for different conditions is given in the ICAO Aerodrome Design Manual, Part 4.

### 17. Signal area

A signal area need be provided only when it is intended to use visual ground signals to communicate with aircraft in flight. Such signals may be needed when the aerodrome does not have an aerodrome control tower or an aerodrome flight information service unit, or when the aerodrome is used by aeroplanes not equipped with radio. Visual ground signals may also be useful in the case of failure of two-way radio communication with aircraft. It should be recognized, however, that the type of information which may be conveyed by visual ground signals should normally be available in AIPs or NOTAM. The potential need for visual ground signals should therefore be evaluated before deciding to provide a signal area.

### 18. Rescue and fire fighting services

#### 18.1 Administration

17.1.1 The rescue and fire fighting service at an aerodrome should be under the administrative control of the aerodrome management, which should also be responsible for ensuring that the service provided is organized, equipped, staffed, trained and operated in such a manner as to fulfill its proper functions.

18.1.2 In drawing up the detailed plan for the conduct of search and rescue operations in accordance with 4.2.1 of GACA Regulation Section 12 and ICAO Annex 12, the aerodrome management should coordinate its plans with the relevant rescue coordination centers to ensure that the respective limits of their responsibilities for an aircraft



accident within the vicinity of an aerodrome are clearly delineated.

18.1.3 Coordination between the rescue and fire fighting service at an aerodrome and public protective agencies, such as local fire brigade, police force, coast guard and hospitals, should be achieved by prior agreement for assistance in dealing with an aircraft accident

18.1.4 A grid map of the aerodrome and its immediate vicinity should be provided for the use of the aerodrome services concerned. Information concerning topography, access roads and location of water supplies should be indicated. This map should be conspicuously posted in the control tower and fire station and available on the rescue and fire fighting vehicles and such other supporting vehicles required to respond to an aircraft accident or incident. Copies should also be distributed to public protective agencies as desirable.

18.1.5 Coordinated instructions should be drawn up detailing the responsibilities of all concerned and the action to be taken in dealing with emergencies. The appropriate authority should ensure that such instructions are promulgated and observed.

### **18.2 Training**

The training curriculum should include initial and recurrent instruction in at least the following areas:

- a. airport familiarization;
- b. aircraft familiarization;
- c. rescue and fire fighting personnel safety;
- d. emergency communications systems on the aerodrome, including aircraft fire related alarms;
- e. use of the fire hoses, nozzles, turrets and other appliances required for compliance with Chapter 9, 9.2;
- f. application of the types of extinguishing agents required for compliance with Chapter 9, 9.2;
- g. emergency aircraft evacuation assistance;
- h. fire fighting operations;
- i. adaptation and use of structural rescue and fire fighting equipment for aircraft rescue and fire fighting;
- j. dangerous goods;
- k. familiarization with fire fighters' duties under the aerodrome emergency plan; and
- l. protective clothing and respiratory protection.

### **18.3 Level of protection to be provided**

18.3.1 In accordance with Chapter 9, 9.2 aerodromes should be categorized for rescue and fire fighting purposes and the level of protection provided should be appropriate to the aerodrome category.

18.3.2 However, Chapter 9, 9.2.3 permits a lower level of protection to be provided for a limited period where the number of movements of the aeroplanes in the highest category normally using the aerodrome is less than 700 in the busiest consecutive three months. It is important to note that the concession included in 9.2.3 is applicable only where there is a wide range of difference between the dimensions of the aeroplanes included in reaching 700 movements.

### **18.4 Rescue equipment for difficult environments**

18.4.1 Suitable rescue equipment and services should be available at an aerodrome where the area to be covered by the service includes water, swampy areas or other difficult environment that cannot be fully served by conventional wheeled vehicles. This is particularly important where a significant portion of approach/departure operations takes place over these areas.

18.4.2 The rescue equipment should be carried on boats or other vehicles such as helicopters and amphibious or aircushion vehicles, capable of operating in the area concerned. The vehicles should be so located that they can be brought into action quickly to respond to the areas covered by the service.

18.4.3 At an aerodrome bordering the water, the boats or other vehicles should preferably be located on the aerodrome, and convenient launching or docking sites provided. If these vehicles are located off the aerodrome, they should preferably be under the control of the aerodrome rescue and fire fighting service or, if this is not practicable, under the control of another competent public or private organization working in close coordination with the aerodrome rescue and fire fighting service (such as police, military services, harbor patrol or coast guard).

18.4.4 Boats or other vehicles should have as high a speed as practicable so as to reach an accident site in minimum time. To reduce the possibility of injury during rescue operations, water jet-driven boats are preferred to water propeller-driven boats unless the propellers of the latter boats are ducted.

Should the water areas to be covered by the service be frozen for a significant period of the year, the equipment should be selected accordingly. Vehicles used in this service should be equipped with life rafts and life preservers related to the requirements of the larger aircraft normally using the aerodrome, with two-way radio communication, and with floodlights for night operations. If aircraft operations during periods of low visibility are expected, it may be necessary to provide guidance for the responding emergency vehicles.



18.4.5 The personnel designated to operate the equipment should be adequately trained and drilled for rescue services in the appropriate environment.

### 18.5 Facilities

18.5.1 The provision of special telephone, two-way radio communication and general alarm systems for the rescue and fire fighting service is desirable to ensure the dependable transmission of essential emergency and routine information. Consistent with the individual requirements of each aerodrome, these facilities serve the following purposes:

- a. direct communication between the activating authority and the aerodrome fire station in order to ensure the prompt alerting and dispatch of rescue and fire fighting vehicles and personnel in the event of an aircraft accident or incident;
- b. direct communication between the rescue and fire fighting service and the flight crew of an aircraft in emergency
- c. emergency signals to ensure the immediate summoning of designated personnel not on standby duty;
- d. as necessary, summoning essential related services on or off the aerodrome; and
- e. maintaining communication by means of two-way radio with the rescue and fire fighting vehicles in attendance at an aircraft accident or incident.

18.5.2 The availability of ambulance and medical facilities for the removal and after-care of casualties arising from an aircraft accident should receive the careful consideration of the appropriate authority and should form part of the overall emergency plan established to deal with such emergencies.

## 19. Operators of vehicles

19.1 The authorities responsible for the operation of vehicles on the movement area should ensure that the operators are properly qualified. This may include, as appropriate to the driver's function, knowledge of:

- a. the geography of the aerodrome;
- b. aerodrome signs, markings and lights;
- c. radiotelephone operating procedures;
- d. terms and phrases used in aerodrome control including the ICAO spelling alphabet;
- e. rules of air traffic services as they relate to ground operations;
- f. airport rules and procedures; and
- g. specialist functions as required, for example, in rescue and fire fighting.

19.2 The operator should be able to demonstrate competency, as appropriate, in:

- a. the operation or use of vehicle transmit/receive equipment;
- b. understanding and complying with air traffic control and local procedures;
- c. vehicle navigation on the aerodrome; and
- d. special skills required for the particular function.

In addition, as required for any specialist function, the operator should be the holder of a State driver's license, a State radio operator's license or other licenses.

19.3 The above should be applied as is appropriate to the function to be performed by the operator and it is not necessary that all operators be trained to the same level, for example, operators whose functions are restricted to the apron.

19.4 If special procedures apply for operations in low visibility conditions, it is desirable to verify an operator's knowledge of the procedures through periodic checks.

## 20. The ACN-PCN method of reporting pavement strength

### 20.1 Overload operations

20.1.1 Overloading of pavements can result either from loads too large, or from a substantially increased application rate, or both. Loads larger than the defined (design or evaluation) load shorten the design life, whilst smaller loads extend it. With the exception of massive overloading, pavements in their structural behavior are not subject to a particular limiting load above which they suddenly or catastrophically fail. Behavior is such that a pavement can sustain a definable load for an expected number of repetitions during its design life. As a result, occasional minor over-loading is acceptable, when expedient, with only limited loss in pavement life expectancy and relatively small acceleration of pavement deterioration. For those operations in which magnitude of overload and/or the frequency of use do not justify a detailed analysis, the following criteria are suggested:

- a. For flexible pavements, occasional movements by aircraft with ACN not exceeding 10 per cent above the reported PCN should not adversely affect the pavement;
- b. for rigid or composite pavements, in which a rigid pavement layer provides a primary element of the structure, occasional movements by aircraft with CAN not exceeding 5 per cent above the reported PCN should not adversely affect the pavement;

- c. if the pavement structure is unknown, the 5 per cent limitation should apply; and
- d. the annual number of overload movements should not exceed approximately 5 per cent of the total annual aircraft movements.

20.1.2 Such overload movements should not normally be permitted on pavements exhibiting signs of distress or failure. Furthermore, overloading should be avoided during any periods of thaw following frost penetration, or when the strength of the pavement or its subgrade could be weakened by water. Where overload operations are conducted, the appropriate authority should review the relevant pavement condition regularly, and should also review the criteria for overload operations periodically since excessive repetition of overloads can cause severe shortening of pavement life or require major rehabilitation of pavement.

#### 20.2 ACNs for several aircraft types

For convenience, several aircraft types currently in use have been evaluated on rigid and flexible pavements founded on the four subgrade strength categories in Chapter 2, 2.6.6 b) and the results tabulated in the ICAO Aerodrome Design Manual, Part 3.

Intentionally left blank

**ATTACHMENT B. OBSTACLE LIMITATION SURFACES**




Figure B-1



LIMITED INDEX OF SIGNIFICANT SUBJECTS  
INCLUDED IN ANNEX 14, VOLUME I

**LIMITED INDEX OF SIGNIFICANT SUBJECTS  
INCLUDED IN GACA REGULATION SECTION 14,  
VOLUME I**

**AERODROME OPERATION\***

apron management service 9.5  
bird hazard reduction 9.4  
denoting closed areas 7.1  
denoting unserviceable areas 7.4  
disabled aircraft removal 9.3  
emergency planning 9.1  
ground servicing of aircraft 9.6  
light intensity control A-15  
lighting of unserviceable areas A-13  
maintenance 10  
marking of vehicles or mobile objects 6.1.6;  
6.2.2; 6.2.14  
measuring runway braking action/friction A-6; A-7  
mobile obstacles on runway strips 3.4.7  
monitoring visual aids 8.3  
overload operations A-19.1  
reporting aerodrome data 2  
rescue and fire fighting 9.2; A-17  
secondary power supply 8.1

**APRON**

clearance of debris 10.2.1  
clearance of snow, ice, etc. 10.2.9; 10.2.10  
definition 1.1  
physical characteristics 3.13  
isolated aircraft parking position 3.14  
lighting 5.3.23  
reporting requirements 2.5.1 d)  
safety lines 5.2.14

**APRON MANAGEMENT SERVICE**

definition 1.1  
provision 9.5

**CLEARWAY**

accountability as runway length 3.1.8  
definition 1.1  
frangibility 9.9.1 b); 9.9.2 c)  
general A-2  
physical characteristics 3.6  
reporting requirements 2.5.1 f)  
\*Those specifications which relate to the daily operation  
of an aerodrome as compared with those which relate to  
its design or facilities to be provided.

**DE-ICING/ANTI-ICING FACILITY**

definition 1.1  
lighting 5.3.21  
location 3.15.2  
marking 5.2.11.2

**DECLARED DISTANCES**

calculation A-3  
definition 1.1  
reporting requirements 2.8

**DISABLED AIRCRAFT REMOVAL**

capability 9.3  
reporting requirements 2.10

**DISPLACED THRESHOLD**

definition 1.1  
lights 5.3.10.1; 5.3.10.3  
location A-10.2  
marking 5.2.4.9; 5.2.4.10

**FRANGIBILITY**

definition of frangible object 1.1  
elevated approach lights 5.3.1.4.; 5.3.1.5  
markers 5.5.1  
objects on operational areas 9.9  
objects on runway strips 3.4.7  
other elevated lights 5.3.1.7  
PAPI and APAPI 5.3.5.27  
signs 5.4.1.3  
T-VASIS and AT-VASIS 5.3.5.16

**GRADING**

radio altimeter operating area 3.8.4  
runway end safety areas 3.5.7  
runway strips 3.4.8-3.4.11  
strip for precision approach runways A-8.3  
taxiway strips 3.11.4

**HELIPORT**

definition 1.1  
specifications *See* GACA Regulation Section 14, Volume  
II



LIMITED INDEX OF SIGNIFICANT SUBJECTS  
INCLUDED IN ANNEX 14, VOLUME I

**HOLDING BAY**

definition 1.1  
physical characteristics 3.12

condition of the movement area and related facilities 2.9.1-2.9.3  
visual aids 8.3

**INTERMEDIATE HOLDING POSITION**

definition 1.1  
lighting 5.3.20  
location 3.12.4  
marking 5.2.11  
signs 5.4.3.9

**NON-INSTRUMENT RUNWAY**

approach lighting system 5.3.4.1-5.3.4.9  
definition 1.1  
holding bays 3.12.6  
obstacle limitation requirements 4.2.1-4.2.6  
runway-holding position marking 5.2.10.2  
secondary power supply Table 8-1  
threshold lights 5.3.10.1; 5.3.10.4 a)

**LIGHTING**

approach lighting systems 5.3.4; A-11; Appendix 2  
color specifications Appendix 1  
definitions for lights, etc. 1.1  
electrical systems Chapter 8  
intensity control 5.3.1.10; 5.3.1.11; A-15  
lights 5.3  
lighting of unserviceable areas A-13  
maintenance 10.1; 10.4  
monitoring 8.3  
obstacle lighting 6.3; Appendix 6  
photometric characteristics Appendix 2  
priority of installation of visual approach slope indicator systems A-12  
reporting requirements 2.9.2 h); 2.12  
secondary power supply 8.1  
security lighting 9.11

**NON-PRECISION APPROACH RUNWAY**

approach lighting system 5.3.4.1-5.3.4.9  
definition 1.1  
holding bays 3.12.6  
obstacle limitation requirements 4.2.7-4.2.12  
runway threshold identification lights 5.3.8  
runway-holding position marking 5.2.10.2  
secondary power supply Table 8-1  
threshold lights 5.3.10.1; 5.3.10.4 a)

**MAINTENANCE**

clearance of debris 10.2.1; 10.2.7  
clearance of snow, ice, etc. 10.2.8-10.2.12  
general 10.1  
pavement overlays 10.3  
runway evenness 10.2.2; A-5  
visual aids 10.4

**OBSTACLE/OBJECT**

clearance of obstacles A-11.3  
definition of obstacle and obstacle free zone 1.1  
lighting 6.3; Appendix 6  
limitation requirements 4.2  
limitation surfaces 4.1  
marking 6.2  
objects to be marked and/or lighted 6.1  
on clearways 3.6.6  
on runway end safety areas 3.5.6  
on runway strips 3.4.6; 3.4.7  
on taxiway strips 3.11.3; 9.9  
other objects 4.4  
outside the obstacle limitation surfaces 4.3  
protection surface 5.3.5.41-5.3.5.45  
reporting of obstacles and obstacle free zone 2.5  
secondary power supply 8.1

**MARKER**

definition 1.1  
marker aids 5.5

**MARKING**

Color specifications 5.2; Appendix 1  
definition 1.1  
marking of objects 6.2  
surface marking patterns 5.2

**PAVEMENT STRENGTH**

ACNs for aircraft A-19.2  
aprons 3.13.3  
overload operations A-19.1  
reporting requirements 2.6  
runways 3.1.20  
shoulders A-8.1  
stopways 3.7.3; A-2.10  
taxiways 3.9.12

**MONITORING**



LIMITED INDEX OF SIGNIFICANT SUBJECTS  
INCLUDED IN ANNEX 14, VOLUME I

**PRECISION APPROACH RUNWAY CATEGORY I**

approach lighting system 5.3.4.10-5.3.4.21  
center line lights 5.3.12.2; 5.3.12.5  
definition 1.1  
flight path envelope Figure A-4  
frangibility 9.9  
holding bays 3.12.6-3.12.9  
holding position signs 5.4.2.3; 5.4.2.4; 5.4.2.5; 5.4.2.7;  
5.4.2.8;  
5.4.2.10; 5.4.2.12; 5.4.2.13; 5.4.2.15; 5.4.2.16  
maintenance of visual aids 10.4.1; 10.4.2; 10.4.10  
objects on strips 3.4.7  
obstacle limitation requirements 4.2.13; 4.2.14;  
4.2.16-4.2.21  
runway light characteristics Appendix 2  
runway-holding position marking 5.2.10.3  
secondary power supply Table 8-1  
threshold lights 5.3.10.4 b)

**PRECISION APPROACH RUNWAYS  
CATEGORIES II AND III**

approach lighting system 5.3.4.22-5.3.4.39  
definition 1.1  
flight path envelopes Figure A-4  
frangibility 9.9  
holding bays 3.12.6-3.12.9  
holding position signs 5.4.2.3; 5.4.2.4; 5.4.2.5; 5.4.2.7;  
5.4.2.8;  
5.4.2.10; 5.4.2.12; 5.4.2.13; 5.4.2.15; 5.4.2.16  
maintenance of visual aids 10.4.1-10.4.9  
objects on strips 3.4.7  
obstacle limitation requirements 4.2.15-4.2.21  
runway center line lights 5.3.12.1; 5.3.12.5  
runway end lights 5.3.11.3  
runway light characteristics Appendix 2  
runway-holding position marking 5.2.10.3  
secondary power supply Table 8-1  
stop bars 5.3.19  
taxiway center line lights 5.3.16  
taxiway light characteristics Appendix 2  
threshold lights 5.3.10.4 c)  
touchdown zone lights 5.3.13

**RESCUE AND FIRE FIGHTING**

communication and alerting system 9.2.31; 9.2.32  
emergency access roads 9.2.26-9.2.28  
extinguishing agents 9.2.8-9.2.19  
fire stations 9.2.29; 9.2.30  
general 9.2 (*Introductory Note*)  
level of protection 9.2.3-9.2.7; A-17.3  
personnel 9.2.34-9.2.38  
reporting requirements 2.11  
rescue equipment 9.2.20; 9.2.33

response time 9.2.21-9.2.25  
vehicles 9.2.33

**RUNWAY**

clearance of debris 10.2.1  
clearance of snow, ice, etc. 10.2.8; A-6  
closed runway marking 7.1  
definition 1.1  
lights 5.3.7-5.3.13; Appendix 2  
markers 5.5.2; 5.5.4  
marking 5.2.2-5.2.7; 5.2.9  
number, siting and orientation A-1  
pavement overlays 10.3  
physical characteristics 3.1  
reporting requirements 2.3.2; 2.5.1. a); 2.8;  
2.9.2; 2.9.4-2.9.11; A-6; A-7  
runway surface evenness A-5  
shoulders 3.2  
slopes 3.1.12-3.1.19; A-4  
strips 2.5.1 b); 3.4; 9.9.1 a); 9.9.4; 9.9.6  
turn pads 3.3

**RUNWAY END SAFETY AREA**

definition 1.1  
frangibility 9.9.1 a); 9.9.2 b)  
general A-9  
physical characteristics 3.5  
reporting requirements 2.5.1 b)

**RUNWAY-HOLDING POSITION**

definition 1.1  
location 3.12.2; 3.12.3; 3.12.9  
marking 5.2.10  
runway guard lights 5.3.22  
signs 5.4.2.2-5.4.2.5; 5.4.2.7; 5.4.2.8;  
5.4.2.10; 5.4.2.12; 5.4.2.13; 5.4.2.15;  
5.4.2.16  
stop bars 5.3.19

**RUNWAY MEANT FOR TAKE-OFF**

climb surface 4.1.25-4.1.29  
frangibility 9.9  
maintenance of visual aids 10.4.1; 10.4.2; 10.4.11; 10.4.12  
obstacle limitation requirements 4.2.22-4.2.27  
runway lighting 5.3.9.2; 5.3.12.3; 5.3.12.4  
secondary power supply Table 8-1  
taxiway lighting 5.3.16; 5.3.17

## **RUNWAY SURFACE FRICTION CHARACTERISTICS**

maintenance 10.2.1-10.2.5; 10.2.7; 10.2.10  
reporting requirements 2.9  
runway design 3.1.22  
runway surface friction 2.9.6; 2.9.9  
snow- and ice-covered paved surfaces – general A-6  
wet runways – general A-7

## **SECURITY**

aerodrome emergency planning 9.1.2 (*Note*)  
airport design 1.5  
fencing 9.10  
isolated aircraft parking position 3.14  
lighting 9.11

## **STOPWAY**

accountability as runway length 3.1.8  
definition 1.1  
general A-2  
lights 5.3.15; Appendix 2  
markers 5.5.3  
physical characteristics 3.7  
reporting requirements 2.5.1. b)

## **TAXIWAY**

closed taxiway marking 7.1  
definition 1.1  
lights 5.3.16; 5.3.17; Appendix 2  
markers 5.5.5; 5.5.6; 5.5.7  
marking 5.2.8; 5.2.11; 7.2  
physical characteristics 3.9  
rapid exit 3.9.15-3.9.18  
removal of contaminants 10.2.7; 10.2.9; 10.2.11  
reporting requirements 2.5.1 c)  
shoulders 3.10  
strips 3.11; 9.9.1 a); 9.9.4

## **VISUAL APPROACH SLOPE INDICATOR SYSTEMS**

characteristics 5.3.5  
priority of installation A-12  
reporting requirements 2.12  
secondary power supply 8.1

**Intentionally left blank**

— END —